



REFURBISHMENT/REPAIRS OF IMPHAL SECTT. BRANCH  
BOQ for Supply and Installation of Air-conditioners

ANNEXURE-III

Sl.No.	Description	UOM	Qty.	Rate (Rs.) (Exclusive of GST )	Amount (Rs.) (Exclusive of GST )
1	Supply of 1.0 TR Capacity Hi Wall mounting 5-star rated Inverter Split AC with cordless remote and Copper Condensor Coil. <b>AC Make, Voltas/Bluestar /Carrier/Daikin /LG/Godrej</b>	No.	1		
2	Supply of 1.5 TR Capacity Hi Wall mounting 5-star rated Inverter Split AC with cordless remote and Copper Condensor Coil. <b>AC Make, Voltas/Bluestar /Carrier/Daikin /LG/Godrej</b>	No.	3		
3	Installation charges of the <b>1.0/1.5 TR</b> Hi-Wall Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	4		
4	<b>For 1.0 TR/1.5 TR Hi-Wall type split air conditioners:</b> Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessities and making good all the damages.	RM	24		
5	Supply and Installation of 4 KVA Stabilizer for 1.0 TR/1.5 TR Split Acs	Nos.	4		
<b>GST will be extra as applicable.</b>		<b>Grand Total(In Rupees)</b>			