Annexure-II

Shifting of Regional Business Office, Imphal, Manipur
BOQ for Supply and Installation of Air-conditioners

Sl.No.	Description	UOM	Qty.	Rate (Rs.) (Exclusive of GST)	Amount (Rs.) (Exclusive of GST)
1	Supply of 1.5 TR Capacity Hi Wall mounting 3 Star rated Inverter /5-star rated Split AC with cordless remote and Copper Condensor Coil. **AC Make, Voltas/Bluestar /Carrier/Daikin /LG/Godrej**	No.	11		
2	Supply of 2.0 TR Copper Cassette type split air conditioners with refrigerant (R32 or R 410A) **Indoor unit** ceiling hung comprising cooling coil, evaporator fan with motor, filters, insulated drain pan, drain pump, expansion valve, refrigerant filter drier with codeless remote control unit, etc. **Outdoor unit** comprising single phase hermetically sealed scroll / rotary compressors, condenser coil with fan & motor, starters / controls / cutouts / relays etc., mounted inside a powder coated sheet metal cabinet of 2mm thick, duly treated for corrosion protection complete, mounted on ribbed rubber pads. **AC Make, Voltas/Blue Star/Carrier/Daikin /LG**	No.	15		
3	Installation charges of the **1.5 TR** Hi-Wall Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	11		
4	Installation charges of the **2.0 TR** Cassette Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	15		
5	**For 2.0 TR Copper Cassette type split air conditioners**: Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages.	RM	200		
6	**For 1.5 TR Hi-Wall type split air conditioners:** Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages.	RM	70		
7	Supply and Installation of 4 KVA Stabilizer for 1.5 TR Split Acs	Nos.	11		
8	Supply and Installation of 5 KVA Stabilizer for 2.0 TR Cassette type Acs	Nos.	15		
GST will be extra as applicable.				**Grand Total**	