

TENDER DOCUMENTS FOR AC WORK FOR SBI JHANSI KUMS BRANCH.						
S.N	DESCRIPTION OF ITEM	QTY	UNIT	RATE	RATE	AMOUNT
1	<b>Old AC</b> : Unmounting, servicing and refixing of bank's split AC and stablizers at marked locations. Including cost of gas filling complete work .	No	3.00	<b>IN WORDS</b>	<b>IN WORDS</b>	
1	<b>Rate for Extra Piping(Rate above 12 Feet pipe which will be free with unit)</b>					
	<b>Ref. Piping (Only single distance will be measured between Indoor &amp; Outdoor Units)</b>					
a	1.5 TR HWM Split Unit	Mtr.	22.00			
2	<b>Electrical cabling (Only single distance will be considered)</b>					
a	1.5 TR HWM Split Unit	Mtr.	25.00			
	<b>AC Works</b>					
	Supply, Installation, Testing and Commissioning of hi-wall and cassette airconditioner on 9th floor. Item includes all the work related to airconditioning,installation, future servicing, drainage, interconnection of indoor and out door units in recessed manner in grid type false ceiling with full function wireless remote and auto restart feature, complete in all respects with indoor/outdoor unit, gas charge,caging with lock and key facility etc. Item includes all the work related to airconditioning,installation, future servicing, drainage, interconnection of indoor and out door units. Acceptable makes AC: Daikin/Hitachi/Carrier/ Blue Star/Voltas/Toshiba					
3	<b>1.0 TR HWM Split Unit ( 3 star rating ) Model ,with Cordless remote</b>					
a	Unit Cost (Excise+Transport)	No.	2.00			
b	Installation Cost (Upto 12 Feet of Piping)	No.	2.00			
c	Outdoor Stand	No.	2.00			
d	Caging with Lock & Key facility	No.	2.00			
4	<b>Rate for Extra Piping(Rate above 12 Feet pipe which will be free with unit) Ref. Piping (Only single distance will be measured between Indoor &amp; Outdoor Units)</b>					
a	1.0 TR HWM Split Unit	Mtr.	15.00			
5	<b>Electrical cabling (Only single distance will be considered)</b>					
a	4 core Interconnecting standard wire/cable between indoor and outdoor units for 1.0 TR HWM Split Unit	Mtr.	17.00			
6	<b>2 TR Cassette Unit/Model,Corded / Cordless remote</b>					
a	Unit Cost (Excise+Transport)	No.	4.00			
b	Installation Cost	No.	4.00			
c	Outdoor Stand	No.	4.00			
d	Caging with Lock & Key facility	No.	4.00			
7	<b>Ref. Piping (Only single distance will be measured between Indoor &amp; Outdoor Units)</b>					
b	Copper pipe for refrigerant piping for 2.0 Tr cassette AC set as per company specs and discharge to be measured as one composite run and not separately) with insulation, drainage pipe, etc.	Mtr.	60.00			
8	<b>Electrical cabling (Only single distance will be considered)</b>					
a	4 core Interconnecting standard wire/cable between indoor and outdoor units for 2TR Cassette Unit	Mtr.	65.00			
9	<b>Stabilizers</b>					
a	SITC of 4 KVA ,hi/lo cut off, TDR relay start stabilizer. Make-Inmag/ servel/ Stambh / MARC/AC MAKE	No	5.00			
b	SITC of 5 KVA ,hi/lo cut off, TDR relay start stabilizer. Make-Inmag/ servel/ Stambh / MARC /AC MAKE	No	4.00			
10	<b>Drain Pipings</b>					
a	Drain piping - Hard PVC pipe (25 mm) with 12mm expanded polythene insulation	Mtr.	30.00			
b	Drain piping - Hard PVC pipe (40 mm) with 12mm expanded polythene insulation	Mtr.	10.00			
11	<b>ADDITIONAL ITEMS</b>					
a	Chiselling of wall/floor etc	Rmt	30.00			
	<b>TOTAL</b>					