

<b>SCHEDULE OF QUANTITIES AND DETAILED SPECIFICATIONS FOR HIMAYATH NAGAR BRANCH AT, HYDERABAD.</b>					
<b>S.No.</b>	<b>Item. / Particulars.</b>	<b>Quan- tity.</b>	<b>Rate.</b>	<b>Unit.</b>	<b>Amount.</b>
<b>I.</b>	<b>INTERIOR WORKS:</b>				
<b>1.0</b>	<b>FIXED FURNITURE:</b>				
<b>1.1</b>	<b>FULL HEIGHT PARTITIONS:</b>	35		Sq.M.	
	<p>Providing and fixing metal stud dry wall partition with following specifications: The Partition will be fully opaque OR partly opaque and partly glazed as per specific site conditions and drawings.</p> <p>(a) Supporting system comprising of 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs at 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings.</p> <p>(b) 12mm MDF Exterior Grade Board fixed on both sides with 25mm dry wall screws for the entire height of the partition.</p> <p>(c) Partition from floor level upto Ceiling level to have 100mm Skirting with glossy laminate (silver color) at bottom + from 100mm to 300mm level to have 1mm Glossy Laminate (blue color) + from 300mm level to 950mm level to have 1mm Glossy Laminate (white color) + from 950mm level to 1100mm level 1mm Glossy Laminate (blue color) + from 1100mm level to 2250mm level to have 1mm Textured Laminate (white color) OR 8mm clear float glass as detailed in (d) below + from 2250mm level to 2350mm level 1mm Glossy Laminate (blue color) + above 2350mm level to Ceiling level 1mm Glossy laminate (White color) on both sides as shown in drawing.</p> <p>(d) Partition to have 8mm clear float glass instead of 1mm Textured Glossy Laminate fixed with 85mm x 18mm alround MDF Exterior Grade jamb and 12mm x 12mm MDF Exterior Grade button beading on both sides of the glass, to a neat finish as per drawings and directions etc., complete.</p>				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(e) All exposed surfaces of MDF Exterior Grade members to have minimum two coats of LOW VOC or NO VOC duco paint finish.				
	(f) All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				
<b>1.2</b>	<b>HALF HEIGHT PARTITIONS:</b>	50		Sq.M.	
	Same as item 1.1 above, but for height of 1100mm from finished floor level, to a neat finish as per drawings and directions etc., complete and the following:				
	(a) 6mm thick acrylic solid surface capping of 75mm on top, 50mm bands of 6mm acrylic solid surface on both sides of the partitions horizontally and vertically upto skirting as per drawings and directions etc., complete.				
	(b) Partition from floor level upto 1100mm level on both sides to have 100mm Skirting with Glossy laminate (Silver color) at bottom + from 100mm to 300mm level to have 1mm Glossy Laminate (blue color) + from 300mm level to 950mm level to have 1mm Glossy Laminate (white color) + from 950mm level to 1050mm level 1mm Glossy Laminate (blue color) + from 1050mm level to 1100mm level to have 6mm thick acrylic solid surface on both sides as shown in drawing.				
	(c) The cost to include all materials and hardware required etc., as per site conditions. The rate is for a finished item of work etc., complete as directed.				
<b>1.3</b>	<b>DOORS IN PARTITIONS:</b>				
<b>1.3.1</b>	<b>35MM DOORS IN PARTITIONS:</b>	10		Sq.M.	
	Providing and fixing 35mm thick solid core flush shutter with 85mm x 18mm MDF Exterior Grade jamb alround and 12mm x 12mm MDF Exterior Grade button beading fixed 1mm Laminate as specified on both sides and 8mm clear float glass with 3M privacy film fixed as per drawing with 50mm x 18mm MDF Exterior Grade jamb around the glass opening and 12mm x 12mm MDF Exterior Grade beading for fixing of glass on both sides.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	The rate to include necessary hardware viz., door stopper, door buffer, pair of " H " type handles, Mortise Dead Lock and Euro Profile Cylinder - Key and Knob 70mm SS, 4 Nos. SS 2 ball-bearing hinges - (127mm x 76mm x 2.5mm), door closer (all of approved make and quality), ZERO VOC or NO VOC duco paint finish for all exposed surfaces of MDF Exterior Grade members, etc., complete as directed.				
<b>1.4</b>	<b>FIXED GLASS WORKS: (12MM TOUGHENED GLASS WORK WITH MAIN ENTRANCE DOOR AND GLASS PARTITION DOORS)</b>	#REF!		Sq.M.	
	Providing, making and fixing in position Fixed 12mm / 10mm toughened glass as fixed glass from Floor to available Ceiling level along with Main Entrance Door and for Partitions. The glass is to be fixed with patch fittings and all the edges of the glass have to be polished for a smooth finish. The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.				
<b>1.5</b>	<b>12MM TOUGHENED GLASS MAIN ENTRANCE DOOR AND PARTITION DOORS:</b>	9		Sq.M.	
	Providing, making and fixing in position Fixed 12mm / 10mm toughened glass openable shutters work as per specifications given below and for the openings mentioned. Main Entrance Glass Work comprising of Door opening of approximate size 1800mm x 2250mm - 2400mm in two pieces, and Partition Doors of approximate size 900 - 1000mm x 2250mm - 2400mm. The entire work to be done as per site conditions with following specifications etc., complete as directed.				
	(a) Entrance door - Providing, fixing in position glazed entrance Double door and Single door with patch fitting or approved make (Double Door approx. Size: 1800mm - 1500mm x 2400mm - 2250mm and Single Door approx. Size: 900mm - 1200mm x 2400mm - 2250mm) using 12mm / 10mm toughened glass edge polished. The Door to consist of Heavy Duty Floor spring, Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Corner Lock and the side fixed glass to have 2 Nos. Bottom Patch and 2 Nos. Upper Patch for each door to a neat finish etc., complete as per drawing.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(b) The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.				
<b>1.6</b>	<b>WALL PANELLING:</b>				
<b>1.6.1</b>	<b>WALL PANELLING IN BANKING HALL:</b>	100		Sq.M.	
	Same as item 1.1 above, but for Wall Panelling. The basic frame work to comprise all cladding specified only from one side to a neat job as per drawings and directions etc., complete.				
	(a) Providing 18mm thick MDF Exterior Grade jamb for door and window openings of suitable depth as per site conditions.				
	(b) All exposed surfaces of MDF Exterior Grade members to have NO VOC or LOW VOC duco paint finish.				
<b>1.6.2</b>	<b>WALL PANELLING WITH SPECIAL HIGH GLOSS LAMINATE FOR E-LOBBY:</b>	45		Sq.M.	
	Same as item 1.4 above to be cladded with 1mm High Gloss Laminate ( <b>Laminate Base Rate Rs - 600/- Sq.M.</b> ) from one side to a neat finish as per drawings and directions etc., complete.				
<b>1.7</b>	<b>COLUMN PANELLING:</b>	30		Sq.M.	
	Providing and fixing metal stud column panelling with following specifications:				
	(a) Supporting system comprising of 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs at 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, lintel level and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings.				
	(b) 12mm MDF Exterior Grade Board fixed on all four sides with 25mm dry wall screws for the entire height of the partition.				
	(c) Column Panelling from floor level upto Ceiling level to have 100mm Skirting with glossy laminate (silver color) at bottom + from 100mm to Ceiling level to have 1mm Glossy Laminate (Beech Wood color) on two longer sides of the column as shown in drawing.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(d) Column Panelling to have 8mm toughened glass with 1mm glossy Laminate in blue color fixed with 12mm x 12mm MDF Exterior Grade button beading on two shorter sides of the column, to a neat finish as per drawings and directions etc., complete.				
	(e) All exposed surfaces of MDF Exterior Grade members to have minimum two coats of LOW VOC or NO VOC duco paint finish.				
	(f) All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				
<b>1.8</b>	<b>FALSE CEILING:</b>				
	Providing, making and fixing in position the following types of different false ceilings with different materials as specified below for a finished item of work as per drawings and directions etc., complete.				
<b>1.8.1</b>	<b>GRID FALSE CEILING:</b>	125		Sq.M.	
	<p>Providing &amp; Fixing of Mineral Fibre Acoustical Suspended Ceiling System with 15mm Tiles and Exposed GRID. The tiles should have Humidity Resistance (RH) of 90% - 99%, NRC 0.5, Light Reflectance <math>\geq 87\%</math>, Thermal Conductivity <math>k = 0.052 - 0.057 \text{ w/m K}</math>, Colour White, Fire Performance UK Class 0 / Class 1 (BS 476 pt - 6 &amp; 7) in module size of 600 x 600 x 16mm, suitable for Green Building application, with Recycled content of 30% - 45%.</p> <p>The tile shall be laid on Microline / Silhouette profile grid system with 15mm - 16mm white flanges incorporating a 6mm central reveal in white/black colour and with a web height of 38mm and a load carrying capacity of minimum 8 Kgs/M<sup>2</sup> &amp; minimum pull out strength of 100 Kgs. Microline / Silhouette, Main Runners &amp; Cross Tees to have mitred ends &amp; "birdsmouth" notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 90 grams per M<sup>2</sup> and need to be installed with Suspension system as per manufacturers details.</p>				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	<p>The Instalation to comprise main runner spaced at 1200mm centres securely fixed to the structural soffit using US Boral / Gyproc / Armstrong suspension system (specifications below) at 1200mm maximum centre. The First/Last suspension system at the end of each main runner should not be greater than 450mm from the adjacent wall.</p> <p>Flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm centre to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees. Perimeter trim to be Wall angles of size 3000mm x 19mm x 19mm, secured to walls at 450 mm maximum centres.</p>				
<b>1.8.2</b>	<b>PLAIN FALSE CEILING:</b>	90		Sq.M.	
	<p>Providing and fixing Concealed Grid suspended ceiling system of 12.5mm Gypsum Boards / Standard Plaster Boards fixed to ceiling Frame Work as per manufacturers instructions and details for a concealed grid key lock suspended ceiling system consisting of following:</p> <p>(a) 27 x 37 x 1.6mm Soffit Clip, 5mm suspension rod / 25 x 10 x 0.5mm Ceiling Angle, adjustable spring loaded suspension clip / 2.64mm dia Connecting Clip, 20 x 28 x 30 x 0.5mm Perimeter Channel, Top Cross Rail of 3000mm long of 0.55BMT Furring Channel / 15 x 45 x 15 x 0.9mm Intermediate Channel and 4000mm long made of 0.5mm BMT the Top Cross Rail / 80 x 26 x 0.5mm Ceiling Section to be suspended from ceiling at every 1200mm and Furring / Intermediate Channel to be fixed to Top Cross Rail / Ceiling Section at every 600mm to make a grid of 1200 x 600mm.</p> <p>(b) All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.</p> <p>(c) Further the rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed.</p>				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
<b>1.90</b>	<b>STORAGE UNITS:</b>				
<b>1.9.1</b>	<b>STORAGE UNITS: (WITH 6MM ACRYLIC SOLD SURFACE TOP)</b>	18		Sq.M.	
	Providing, making and placing in position Storage Units with horizontal partitions of 1200mm high abutting wall and 750mm high as back credenza or abutting partition made in 18mm MDF Exterior Grade Board to all members except table top and 25mm block board for table top. The Table top of 25mm Block Board to have extra thickening with 18mm x 50mm MDF Exterior Grade Board and front vertical facia to have 12mm x 43mm MDF Exterior Grade Board lipping cladded with 6mm thick acrylic solid surface for the entire table top and the front facia and remaining all exposed faces to have 1mm Glossy Laminate as specified. All other exposed faces of the unit to have 1mm Glossy Laminate as specified and all unexposed faces to have 0.8mm Laminate finish and all necessary hardware viz., 'W' or wing hinges, locks, handles, tower bolts etc., and MDF Exterior Grade beading 36mm x 36mm at top and MDF Exterior Grade edge lipping 18mm x 12mm etc., as per drawings and directions etc., complete.				
<b>2.0</b>	<b>LOOSE FURNITURE:</b>				
<b>2.1</b>	<b>BRANCH HEAD TABLE:</b>	1		Each.	
	Providing, making and placing in position Executive Table and Side Table of approximate size 2100mm x 900mm x 750mm + 1050mm x 450mm x 750mm with following specifications.  (a) Main Table and side Table top and to be made in 25mm block board with 6mm thick acrylic solid surface. The front side of the table to have a " C " made with 2 x 18mm thick MDF Exterior Grade Board cladded with 6mm acrylic solid surface on the front and the verticals towards the modesty panel. The modesty panel to have 18mm MDF Exterior Grade Board cladded with 1mm glossy Laminate (blue color) + 8mm clear toughened glass as specified.  (b) The " L " shaped table top of 25mm Block Board to have extra thickening with 18mm x 50mm MDF Exterior Grade Board and front vertical facia to have 12mm x 43mm MDF Exterior Grade Board lipping cladded with 6mm thick acrylic solid surface for the entire table top and the front facia and remaining all exposed faces to have 1mm Glossy Laminate as specified.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(c) All other members to be with 18mm MDF Exterior Grade Board and all exposed faces of the table to have 6mm acrylic solid surface OR 1mm Glossy Laminate as specified above to be used.				
	(d) All the edges of 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping.				
	(e) One readymade CPU mobile pedestal.				
	(f) One Molded Key Board Tray with channels etc.,				
	(g) One Three Drawer Unit made with 18mm MDF Exterior Grade Board and 12mm MDF Exterior Grade Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,				
	(h) One Side Table with shutter unit of 400mm made with 18mm MDF Exterior Grade Board and 19mm plywood with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,				
	(i) All the unexposed faces to have 0.8mm Laminate finish.				
	(j) Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
<b>2.2</b>	<b>OTHER OFFICER's EXECUTIVE TABLES:</b>				
<b>2.2.1</b>	<b>OFFICER's AND SIDE EXECUTIVE TABLES:</b>	<b>4</b>		<b>Each.</b>	
	Providing, making and placing in position Executive Table and Side Table of approximate size 1650mm - 1550mm x 750mm x 750mm + 1050mm x 450mm x 750mm with following specifications.				
	(a) Main Table and side Table top and to be made in 25mm block board with 6mm thick acrylic solid surface. The front side of the table to have a inverted " U " made with 2 x 18mm thick MDF Exterior Grade Board cladded with 6mm acrylic solid surface on the front and the verticals towards the modesty panel. The modesty panel to have 18mm MDF Exterior Grade Board cladded with 1mm Glossy Laminate and 1mm Laminate as specified.				



<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(b) The " L " shaped table top of 25mm Block Board to have extra thickening with 18mm x 50mm MDF Exterior Grade Board and front vertical facia to have 12mm x 43mm MDF Exterior Grade Board lipping cladded with 6mm thick acrylic solid surface for the entire table top and the front facia and remaining all exposed faces to have 1mm Glossy Laminate as specified.				
	(c) All other members to be with 18mm MDF Exterior Grade Board and all exposed faces of the table to have 6mm acrylic solid surface OR 1mm Glossy Laminate as specified above to be used.				
	(d) All the edges of 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping.				
	(e) One readymade CPU mobile pedestal.				
	(f) One Molded Key Board Tray with channels etc.,				
	(g) One Three Drawer Unit made with 18mm MDF Exterior Grade Board and 12mm MDF Exterior Grade Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,				
	(h) One Side Table with shutter unit of 400mm made with 18mm MDF Exterior Grade Board with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,				
	(i) All the unexposed faces to have 0.8mm Laminate finish.				
	(j) Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
<b>2.3</b>	<b>GRAHAK MITRA / TECH MITRA TABLE:</b>				
<b>2.3.1</b>	<b>GRAHAK MITRA TABLE:</b>	1		Each.	
	Providing, making and placing in position Grahakmitra Table of approximate size 1500mm x 800mm - 900mm x 750mm with following specifications.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(a) Main Table Top of 25mm Block Board to have extra thickening with 18mm x 50mm MDF Exterior Grade Board and front vertical facia to have 12mm x 43mm MDF Exterior Grade Board lipping cladded with 6mm thick acrylic solid surface for the entire table top and the front facia and remaining all exposed faces to have 1mm Glossy Laminate as specified. The vertical supports of the table is to be made with two side boxing of 75mm x 800mm x 750mm made with 18mm MDF Exterior Grade Board and the front side boxing to 200mm x 450mm x 750mm on either sides and central boxing of 250mm x 600mm x 750mm, all made with 18mm MDF Exterior Grade Board cladded with 6mm acrylic solid surface on all the exposed sides and top.				
	(b) The front of the table to have a 600mm x 1050mm proud portion with provision for cove lighting at bottom and this central portion to be cladded with 6mm thick blue colored lacqured glass.				
	(c) All other members to be with 18mm MDF Exterior Grade Board and all exposed faces of the table to have 6mm acrylic solid surface and the drawer unit to have 1mm Glossy Laminate as specified to be used.				
	(d) All the edges of 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping.				
	(e) One readymade CPU mobile pedestal.				
	(f) One Molded Key Board Tray with channels etc.,				
	(g) One Three Drawer Unit made with 18mm MDF Exterior Grade Board and 12mm MDF Exterior Grade Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 18mm x 12m MDF Exterior Grade edge lipping etc.,				
	(i) All the unexposed faces to have 0.8mm Laminate finish.				
	(j) Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
2.4	<b>SINGLE WINDOW COUNTERS:</b>	6		Each.	
	Providing, making and placing in position Single Window Counters along with necessary partitions as per item 1.2 above (The partitions will be measured and paid as per item 1.2 i.e., Half Height Partitions) with following specifications and per dimensions specified. The front side of the Single Window Counter to have 100mm Skirting with Glossy laminate (silver color) at bottom.				
	(a) The overall size of each Single Window Counter to be 1650mm - 1500mm x 900mm - 975mm x 750mm + 1050mm x 450mm x 750mm.				
	(b) Tabletop of main table and side table to have 25mm Block Board to have extra thickening with 18mm x 50mm MDF Exterior Grade Board and front vertical fascia to have 12mm x 43mm MDF Exterior Grade Board lipping cladded with 6mm thick acrylic solid surface for the entire table top and the front fascia and remaining all exposed faces to have 1mm Glossy Laminate as specified. The acrylic solid surface to continue in the front side with curvature from the front table top to the modesty panel in front with cove lighting provision.				
	(c) All other members to be with 18mm MDF Exterior Grade Board / 2 Nos. of 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and all exposed faces of the table to have 6mm thick acrylic solid surface as specified in the drawing to be used.				
	(d) All the edges of 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping.				
	(e) One readymade CPU mobile pedestal.				
	(f) One Molded Key Board Tray with channels etc.,				
	(g) One Three Drawer Unit made with 18mm MDF Exterior Grade Board and 12mm MDF Exterior Grade Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(h) One Side Table with shutters made with 25mm block board top and 18mm MDF Exterior Grade Board for all other members with necessary hardware viz., ' W ' hinges, SS handles, locks, SS tower bolts, etc., and 18mm x 12mm beech wood edge lipping etc.,				
	(i) All the unexposed faces to have 0.8mm Laminate finish.				
	(j) Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	The cost to include the " L " shaped Single Window Counter and to include all materials, hardware, labour for a neat and finish job as per drawings and directions etc., complete.				
<b>2.5</b>	<b>12MM TOUGHENED GLASS DIVIDERS FOR SINGLE WINDOW COUNTERS:</b>	6		Each.	
	Providing, making and fixing in position 12mm thick toughened clear float glass in the front side of half height partitions of Single Window Counters of approximate size 1150mm x 400mm - 100mm in tapered shape. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.				
<b>2.6</b>	<b>12MM TOUGHENED GLASS ON TRANSACTION SIDE FOR SINGLE WINDOW COUNTERS:</b>	6		Each.	
	Providing, making and fixing in position 12mm thick clear float glass in the front side of approximate size 1650mm x 450mm with a central cut out of 200mm x 175mm. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.				
<b>2.7</b>	<b>WRITING DESK:</b>				
<b>2.7.1</b>	<b>FLOOR MOUNTED WRITING DESK:</b>	1		Each.	
	Providing, making and placing in position Wall Mounted Circular Writing Desk 900mm dia x 750mm with following specifications.				
	(a) A Octogonal support boxing is to be made 450mm at floor level tapering upwards to 600mm at 900mm from floor made in 12mm MDF Exterior Grade Board clad with 1mm Glossy Laminate. A top to be provided at 900mm level from floor to be made with 25mm Block Board clad with 1mm Glossy Laminate which will have verticals made with 12mm MDF Exterior Grade Board clad with 1mm Glossy Laminate upto the table top level of 1050mm from floor level.				

Signature of the contractor

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	<p>(b) The Writing Desk Circular Top to have 12mm dia toughened clear float glass with 25mm champered bull nosing around.</p> <p>(c) All members to be with 12mm / 18mm MDF Exterior Grade Board and all exposed faces to have 1mm Glossy Laminate as specified.</p> <p>(d) All the edges of 12mm / 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping.</p> <p>(e) All the unexposed faces to have 0.8mm Laminate finish.</p> <p>The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.</p>				
<b>2.7.2</b>	<b>WALL MOUNTED WRITING DESK:</b>	1		Each.	
	<p>Providing, making and placing in position Wall Mounted Writing Desk 750mm x 300mm x 450mm with following specifications.</p> <p>(a) The entire unit is to be made with 18mm MDF Exterior Grade Board cladded with 1mm Glossy Laminate as per drawing.</p> <p>(b) The Writing Desk to have 12mm thick toughened clear float glass with 25mm champered bull nosing around at top fixed with SS supports.</p> <p>(c) All members to be with 18mm MDF Exterior Grade Board and all exposed faces to have 1mm Glossy Laminate as specified.</p> <p>(d) All the edges of 12mm / 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping.</p> <p>(e) All the unexposed faces to have 0.8mm Laminate finish.</p> <p>The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.</p>				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
<b>3.0</b>	<b>OTHER WORKS:</b>				
<b>3.1</b>	<b>PLASTIC EMULSION PAINTING:</b>	150		Sq.M.	
	Cleaning the surface of the wall & then applying one coat of altex putty followed by one coat of primer & then applying second coat of putty to give smooth finish exactly in line and level & then finally applying a minimum of two coats of NO VOC or LOW VOC Plastic Emulsion Paint of approved shade to give a neat finish including cost of all materials necessary scaffolding etc., complete for walls & ceiling.				
<b>3.2</b>	<b>ROLLER BLINDS:</b>	10		Sq.M.	
	Providing and fixing in position of Roller Blinds of approved Fabric (Fabric Cost - RS. 1,000/- per Meter) of Hunter Douglas / Mac / Vista make or approved equivalent of approved shade etc., as directed.				
<b>3.3</b>	<b>DESIGNER FILM WORK:</b>	33		Sq.M.	
	Providing and fixing in position Designer Film with ellipse design on all glasses as per drawings and heights mentioned. The Designer Film is of Harmony / 3M or equivalent approved make. The rate is for a finished item of work etc., complete as directed.				
<b>3.4</b>	<b>ACP CLADDING:</b>	40		Sq.M.	
	Supplying and fixing aluminium composite cladding with skin material 0.5 mm thick aluminium sheet cover material natural polyethylene aluminium cladding panel fixed with extruded aluminium basis frame (50x25x1.5mm) angle cleats, weather sealants, rivets, GI brackets all as approved, using suitable bolts on structural steel work including necessary accessories complete in all respects including all labour charges etc., complete for finished item of work but excluding cost of structural steel fabrication, scaffolding charges, if any, ACP Cladding - 4 mm thick.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
3.5	<b>ACRYLIC LOGO:</b>	1		Each.	0
	Providing SBI Logo , SBI Letters in 900 mm dia & TRIVENI COMPLEX BRANCH Letters size 2400X300 mm made with 6mm Inky Blue color acrylic sheet with provision for back lighting as per drawings and directions etc., complete.				
3.6	<b>VITRIFIED TILE FLOORING IN BRANCH AND ELOBBY</b>				
	Providing and laying vitrified floor tiles 600X600 mm (10/12 thickness to be specified by the manufacturer) Double Charged ,with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid with base of CM(1:6), LATICRATE on existing floor by hacking the existing floor including Skirting if any required during laying, and grouting the joints with white cement and matching pigments etc., complete. BASIC RATE OF THE TILE SHALL BE RS 600 per SQ.M Excluding GST.	#REF!		SQ.M	
	The rate shall be inclusive of all the material ,labour, hardware, transportation necessary required for the complete execution of the item as directed by the architect.				
3.10	<b>TEMPORARY FURNITURE</b>	1		LUM	
	Removing existing furniture and re fixing in new location with all electrical & lan Provision for temporary purpose.				
	The rate shall be inclusive of all the necessary material, required hardware, labour, transportation, necessary for the complete execution of the item.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
3.11	DEEP CLEANING	1		LUM	
	Deep cleaning of the premises after completion of all works before handing over the site. The scope of work is inclusive mechanical cleaning, disposal of all any left over debris from electrical and air conditioning works etc complete as directed by the Bank.				
3.12	Modification & Up gradation of existing 2(two) toilets of 4'x5' size in all respects including provision all new tiles ,fixtures, walter / sewear lines , change of door location and provision of new door etc complete in all respects as directed by bank.	1		1	
3.13	Remodifiacion of main entance to the baranch & ATM by removing the existing steps and making proper ramps with graninte top etc complete in all respects as directed by Bak.	1		1	
	TOTAL				
3.14	BUY BACK	-1		1	
	Removing and Buy back of Existing Furniture in the Branch where it is and as it is condition. All that items what ever banch decideds to remove. Etc.,				
	GRAND TOTAL				
	Singature of the contractor				

Signature of the contractor