


ANNEXURE-III					
					
BILL OF QUANTITIES					
NAME OF WORK: AIR-CONDITIONING WORK AT NEW PREMISES OF BAGBASHA BRANCH, DHARMANAGAR, TRIPURA					
No.	Particular	Qty	Units	Rates	Amount
1.0	AIR CONDITIONING				
	Air conditioning work to include providing, fixing, testing, commissioning of outdoor & indoor. The outdoor units to be installed on M.S. frame fixed on outside. Any expenses involved in clearance that may have to be taken & shall be included in the rate. The work includes all necessary civil, minor carpentry works. The brands to be HITACHI, CARRIER-AIRCON DAIKIN, VOLTAS, BLUESTAR , (A.C to be Inverter Technology & 5-Star only)				
a	Providing, fixing, Testing and Commissioning 5-star Inverter technology 1.0 Ton High Wall Mounted split AC with R410/R32 refrigerent (with 5 mt. Refrigerent pipe) including Out Door and Indoor Units, All Refrigerent Pipes (up to 5 mt. Refrigerent length) including their Insulations, 25mm dia PVC Drainage pipes in Walls / ceiling including chasing walls and making them NEAT later. Item includes hanging indoor units and install outdoor units on a MS Stands at appropriate locations, necessary connections and testing and taking drains out complete as directed by Bank's Engineer (In existing ATM Room).	2.00	Nos		
b	Providing, fixing, Testing and Commissioning 5-star Inverter technology 1.5 Ton High Wall Mounted split AC with R410/R32 refrigerent (with 5 mt. Refrigerent pipe) including Out Door and Indoor Units, All Refrigerent Pipes (upto 5 mt. Refrigerator length) including their Insulations, 25mm dia PVC Drainage pipes in Walls / ceiling including chasing walls and making them NEAT later. Item includes hanging indoor units at appropriate locations and testing and taking drains out as directed by Bank's Engineer.	4.00	Nos		
c	ADDITIONAL charges for refrigerant Piping over and above the standard pipe length. The cost to be inclusive of insulation etc. The pipes are NOT to rest on FALSE ceiling. They are to be laid either by hanging from ceiling with proper supports or fixed on the walls/ceiling with proper clamps .	48.00	R.Mtr		

No.	Particular	Qty	Units	Rates	Amount
d	Supplying and laying of PVC pipe with proper insulation and necessary proper clamping Piping over and above the standard pipe length. The cost to be inclusive of insulation etc. The pipes are NOT to rest on FALSE ceiling They are to be laid either by hanging from ceiling with proper supports or fixed on the walls/ceiling with proper clamps	25.00	R.Mtrs		
e	Providing and fixing MS Cages for AC Condensing Units to be hanged Outsie/ fixed on roof/ walls by grouting. The Cages to have shuttered openings which are lockable. All the cages to be painted in white synthetic enamel after preparing base with primer coating.	6.00	Nos		
f	Providing and fixing Stabilisers for AC with 3 step relay and TDR with Input Voltage range: 160V-280V and Output : 230 V.				
(i)	3.0 KVA	2.00	Nos		
(ii)	4.0 KVA	4.00	Nos		
(iii)	5.0 KVA	0.00	Nos		
g	Providing & fixing timer switch for switching power alternatively between two ACs, Timer will be Analogue dial type adjustable TIMER switch which is adjustable over 24 hrs with 4-6-8 hours intervals & is to have 1 NO+1NC (20A) contact. Timer will have its own backup battery & will be enclosed in 16 gauge MS box with acrylic lid together with suitable connector block. (ABB/ MDS / L&T)	1.00	Nos		
	TOTAL OF AIR CONDITIONING PART "A"				
	Plus GST extra as applicable				
	COMPREHENSIVE AMC COST AFTER WARRANTY				
1.0	Comprehensive AMC cost after warranty PA:				
i	1.5/2.0 TR High Wall Split AC existing AC	4.00	Nos		
ii	1.0 TR High Wall Split AC	2.00	Nos		
iii	Votlage Stabilisers 3.0 KVA/4.0KVA/5.0KVA	6.00	Nos		
	UNDERTAKING: We hereby confirmed that we agree to carryout AMC as per the schedule provided by Bank at our quoted rates.				
	TOTAL OF AMC COMPREHENSIVE COST "B"				
	Plus GST will be paid extra as applicable				
	TOTAL QUOTED AMOUNT INCLUDING AMC (PART "A" + PART "B ")				
	Note: The Rate quote for AMC will be valid for 5 years and vendor has to execute the agreement for 5 years at the quoted price for the Branch				