

Bill of Quantities FOR INTERIOR WORKS –DSH AND RACC at FIRST FLOOR OF MAIN BRANCH AND GREAMSPET BRANCHES OF					
Banks Uniform Layout Policy Colour Scheme to be followed.					
All contractors are requested to understand the uniform layout policy colour scme and the specifications of the SBI before quoting the rates. They are also advised to see and understand some branches where Interior already done and approved by the bank.					
Item No.	Description	Qty.	Unit	Rate	Amount
	DSH works to be done in the first floor of main branch, Chittoor. RACC works to be done in the first floor of Greampet branch, Chittoor.				
1	Dismantling of old low ht or full ht partitions and stacking at site of any make and any type etc complete.	11	Sq.M		
2	<u>FULL HEIGHT PARTLY GLAZED PARTITIONS:</u> Providing & fixing in position metal stud dry wall partition with the following specifications: A) supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick metal studs @ 600 mm c/c and 51 X 32 mm metal tracks at floor, middle, door and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. The rate should include necessary strengthening with studs/tracks or channel at doors and other openings. B) 9 mm BWR plywood fixed on both sides with 25 mm dry wall screws. C) 1 mm laminate on both sides (Banks uniform color layout color scheme) up to false ceiling level. D) 6 mm thick clear float glass with etching design as directed between 1200 X 2000 mm level in specified areas fixed with 85 X 15 mm Teak wood jamb and 12 X 12 mm teak wood beading. E) All Teak wood members to have melamine polish finish. Doors in partitions wherever required to be provided with 35 mm thick solid core ISI approved alround beach wood lipping, alround fixed in a concealed door frame of best quality beach wood three sides of sections size of 75x75 mm or as advised by the engineer in charge. Flush door shutters to be fixed with 1 mm laminate (banks uniform layout color scheme) on both sides and 8 mm clear float glass with etching design as directed with 50 X 15 mm teak wood jamb alround the glass opening and 12 X 12 mm teak wood beading for fixing of glass on both sides including necessary hardware viz: door stopper, door silencer, Door set lock, handles, brass hinges of approved make & quality, melamine spray polish finish to all beech wood members etc. complete as directed. F)Door Closer of heavy duty 'Godrej' make or equivalent to be fixed. Length X height up to false ceiling will measured for payment. Plywood area all over to be sprayed with an ti termite solution before use in the work.	10	Sq.M		

3	Low Height Partition: Providing & fixing metal stud low height partitions with following specifications. a) Supporting system comprising of best locally available make 51 X 35 mm metal studs at 600 mm c/c and 51 X 32 mm metal tracks at floor, middle and at 1200mm level with joints staggered. The rate should included necessary strengthening with studs/tracks or channels at openings. b) 9mm plywood bwr grade with 1mm laminate (as per banks uniform colour scheme) on both sides. c) 85x15mm Teak wood capping on top and sides of openings. d) 12mm glass of 12"height on top of low height partition (total height to be 4'6" to 5') with necessary beach wood beading and etching work wherever required also to be fixed. The beech wood members to have melamine polish finish. Anti termite solution to be sprayed before using the ply wood in the work.	110	Sq.M		
4	Roller Blinds:- Supplying & fixing in position of Roller Blinds of "Vista Lavor" (model and shade will be as approved from the product broucher of vista lavlor by the bank).	20	Sq.M		
5	Wicket Gate: Providing & fixing Wicket Gate made out of same construction of low height partitions of approved shade on both sides with all necessary hardware such as hinges, tower bolt etc. complete. The edges shall be finished with beech wood beading polished.	7	Sq.M		
6	Wall Panelling with ply and 1mm laminate(5' HT ONLY): Providing & fixing metal stud wall panelling with the following specification: a) Supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick metal studs @ 600 mm c/c and 51 X 32 mm metal tracks at floor, middle, door level and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. b) 9 mm BWR plywood fixed on one side with 25 mm dry wall screws for the entire height of panelling. c) 1 mm laminate (dark for bands, light for body) up to false ceiling level. e) All beech wood members to have melamine polish finish. Length X height up to false ceiling will be measured for payment. plywood to be used in the work to be sprayed with anti termite solution. banks uniform layout policy color scheme to be followed.(Location and extant of partition shall be strictly as advised by the engineer in charge)	100	Sq.M		
7	COLUMN PANELLING with PLY AND 1MM THICK LAMINATE: for Column Panelling with frame work, ply wood, lamiante as mentioned in wall panelling work above.	10	Sq.M		
8	Storage Units: A) Providing, making and placing in position low height storage units upto 750 mm height or height as directed and 450 mm deep made with 18/19 mm plywood front sides and middle shelf and back side with 9 mm BWR ply covered with 1 mm laminate (dark for bands and light for body) at all exposed surfaces. The top shall have 25 mm mdf board 'post-formed' edge with pf lamination, Inner/unexposed surfaces to painted with two or more coats of enamel paint with putty finish including melamine polish finish for all wooden members. The rate to include cost of all necessary hardware viz., cabinets hinges, locks, handles, tower bolts etc. The unit should have beech wood beading 25 X 40 mm at top and edge lipping 20 X 6 mm complete. All internal areas to be sprayed with anti termite solution and finished with 0.8 mm thick laminte of half white shaede.	30	Sq.M		

9	OFFICERS TABLES (Size 1500 X 900 X 750 mm, Side table 1100X450X750mm): Providing, making & placing in position executive table and side table with the following specifications: a) Table top and all over /other members to be made in 18/19 mm BWR plywood and 1mm laminate, all edges to have 20 X 6 mm teak wood lipping. b) One drawer cum shutter unit with necessary hardware viz: drawer channels,handles, locks etc. c) One ready made mobile CPU pedestal. d) One plywood key board tray with channels to be provided e) One foot rest f) Side table made with 25 mm BWR ply and 1mm laminate all over and other members with necessary hardware viz., cabinet hinges, handles, locks, tower bolts, etc. and 25 X 40 mm beech wood beading and 20 X 6 mm beech wood lipping etc. g) All the exposed surfaces to have 1 mm laminate to match with other parts of the cabin of approved shade and brand. 6Mm th laquerred glass for the modesty panel (infront of tables). All wooden members to have melamine polish. All internal area of the drawers, leg rooms to be finished with 0.8 mm thick half white laminate. Special locks to be fixed which can opened with single key.	30	Each		
10	MODIFICATION OF EXISTING TABLES or similar objects : (table size shall be approximately 1550x900x750mm) Modifying the existing table after re conditioing and covering the all over ie, all four sides and leg room inside with 4mm ply wod and 1mm lamiante as per uniform layout polciy design, new matching beadings of teak wood, new set of channel drawers, new key board, new set of all hardware. The inside the drawers should be painted two coats of paint over a coat of primer or fixing 0.8 mm lamiante etc complete. Modesty panel to be as per unifor colour policy of the bank.	2	Each		
11	TEGULAR Grid False Ceiling:- Providing and fixing in true horizontal level false ceiling grid system of Armstrong World Industries/ Daikin / CEPro etc. The suspension system shall be TEGULAR revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess color, black or white revealed. Silhouette main runners and cross tees to have mitered ends with “birds mouth “ notches to provide mitered cruciform junctions. Main runners to be spaced at 120mm c/c fixed by using 2mm pre-straightened GI wire. Main tee, rotary stitched of size 15mm x 44mm x 3600mm at every 1200mm c/c maximum and 1200mm cross tee of size 15mm x 44mm x 1200mm at every 600mm c/c maximum and 600mm cross tee of size 15mm x 44mm x 600mm at every 1200mm c/c maximum and 19mm x 19mm x 3000mm wall angle all-round the wall to form grid size of 600mm x 600mm and suspending the grid using 2mm pre-straightened GI wire and 6mm nylon rawl plug at every 1200mm intervals at the main tee and laying of dunne premier micro look mineral fiber tiles manufactured by Armstrong World Industries of size 600mm x 600mm x 15mm over the formed grid etc., complete as directed.	200	Sq.M		

12	12MM THICK TOUGHENED GLASS BRANCH MAIN DOOR :Providing and fixing Main door using <u>12mm clear</u> float toughened Glass (entire elevation area of the main door shall look glass with patch fittings only, no wooden or plywood sections/panels). The cost to include all hardware required viz., Dorma or approved equivalent make floor springs, patch fittings etc its accessories, top pivot, center lock, 900mm glass door handle etc.shall be provided. 3M privacy film to be pasted as per design and directions. The rate is for a finished item of work etc., complete as directed.Height shall be measured up to false ceiling or actual glass height.. Supporting work to be/ extended up to rcc slab level shall not be paid for separately.	24	Sq.M		
13	TEXTURED PAINTING: Painting using best branch abd design of textured paint over a coat of pltty, primer, two coats of enamel/ premier emulsion paint for textured design etc complete.	120	Smt		
14	VITRIFIED TILE FLOORING(First floor of both premises, including skirting) Providing and fixing best quality vitrified floor tiles of banks approved brands of size 600x600, 10 mm size of approved make in all colors, shades in flooring, skirting, risers of steps and dado and jointing with white cement admixed with pigments cement with tiles laid on base mortar 1:5(1 cement : 5 coarse sand) up to 30mm thick in grading / or using laticrete of best quality. Basic rate of tiles selected shall be about 55/-sft to Rs 60/- all inclusive.(Mazda beize shade of johnson brand of double charged vitrified tile). Dismantling charges of old flooring, to be included included in the quoted rate. Same shade but anti skid type of tiles to be used for steps and landing areas of the staircse.	200	Smt		
		GRAND TOTAL			
		Discount if any(prefarably mention in % of total)			
		Net total			

Note: GST EXTRA.

Contractor's Signature with Seal & Date