



SBI INFRA MANAGEMENT SOLUTIONS PVT.LTD.

CIRCLE OFFICE, THIRD FLOOR, STATE BANK OF INDIA, SYNERGY BUILDING, C-6, G-BLOCK, BANDRA KURLA COMPLEX, BANDRA EAST, MUMBAI-400051

PART – B: FINANCIAL BID

TENDER ID: MUM202003012
DATE : 09.03.2020

TENDER FOR:

PROPOSED INTERIOR WORK FOR MAIN BRANCH AKOT

TENDER SUBMITTED BY:

NAME : _____

ADDRESS : _____

DATE : _____

TENDER INVITED BY:
Vice President & Circle Head,

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
-------	-------------	-----	------	------	--------

SBI Infra Management Solutions Pvt. Ltd; 3rd floor, Circle Office, State Bank of India, Synergy building, C-6, G-Block, Bandra -Kurla complex, Bandar East, Mumbai-400051.

S. No.	Particulars	Quantity	Unit	Rate	Amount
1	False Ceiling: Providing & fixing in position 12 mm thick gypsum board false ceiling fixed with 16 gauge galvanized frame supported from and fixed to RCC slab with Anchor bolts. The ceiling should contain approx. 40 % of the ceiling area of 12mm thick Mineral Fibre ceiling Board of Armstrong or equivalent approved make with framework, runners, cross runners & suspenders from the existing ceiling as per the manufacturers details and specification and 600X 600mmX 15mm thick mineral fibre ceiling (600*600 mm) - beuti sky or other approved pattern and stepping. All the joints to be properly sealed with jointing tape and finished with approved jointing material. The item includes making cut-outs and providing necessary frame work for light fitting, grill diffusers and ducts etc. which have to be made with frame of perimeter channels of size 20mm x 30mm x 0.55mm. thick supported suitably and angle bead is to be used at steps to get straight line finish etc. complete. The item rate shall also include preparation of surface with sanding, and 3 coats of Acrylic Emulsion paint in approved shade over a coat of primer / putty including necessary work etc. complete as per Bank Engineer's instruction.	300	Sq M		
2	Single window counter : Providing & fixing in position single window counter as per design, made of 18 mm / 19mm thick MR grade ply structure. The work top is to be made of 18 mm / 19mm thick MR grade ply structure. Thereafter, a doublelayer of flexi-ply (12 mm + 6 mm thick) ((the bottom of this niche to have provision of cove lighting with LED strips) is to be fixed with necessary fittings to the plywood structure and laminated glass in approved shade, . All exposed external surface finished with 1 mm high gloss laminate and internal surfaces finished with 0.8 mm laminate of approved shade. The work is to be completed with providing of foot rest, key board tray with telescopic arrangement. vertical glass of 12 mm to be fixed at the front of SWO with one horizontal glass (if required) of approx 150mm with itching and crystal finish etc. complete as per instructions of EIC. Design and detail of the counters shall be as per Bank's new uniform colour, layout & elevation policy available with Bank's Engineer.	6	Rmt		
3	Low / medium height partition: Providing and fixing in position low / medium height partition made of 50 x 50 x 1.2mm medium duty aluminium hollow square pipes framed at 0.6 m to 0.45 m c/c both ways covered with 6 mm MR grade ply and 1mm thick laminate of approved shade & make, both sides including necessary opening / outing for receiving cheques & other papers, and to receive 10 mm th. Float glass including all necessary opening for electric / telephonic conduits etc. as per requirement. (Glass area in the partitions will be deducted in the measurements of partition).	20	Sqm		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
4	Glass partition: Providing and fixing 10 mm thick glass with etching as per design for low height partitions held with SS clits (D brackets). All exposed glass edges with rounded moulding and crystal polish. All exposed woodwork to be finished in 3 coats of French polish/ melamine polish.	6	Sqm		
5	Full height glazed/Partly glazed / partly panelled partition with plywood and laminate : Providing and fixing in position partly glazed & partly panelled partition made of 50 mm x 50mm x 1.2mm medium duty aluminium hollow square pipes framed at 0.60 m. to 0.45 m c/c both ways covered with 6 mm MR grade ply and 1mm multi-colour laminate of approved shade and make with 6 mm thick glass panel with etching as per design and / or necessary beading patti including 3 coats of french polishing including door shutters as per architectural design with heavy duty hinges handles / handles / locks etc. of approved make.	40	Sqm		
6	Full height glazed/Partly glazed / partly panelled partition with plywood and one side laminate one side veneer : Providing and fixing in position partly glazed & partly panelled partition made of 50 mm x 50mm x 1.2mm medium duty aluminium hollow square pipes framed at 0.60 m. to 0.45 m c/c both ways covered with 6 mm MR grade ply and 1mm multi-colour laminate of approved shade at one side and finished in 4mm thk approved veneer finished with melamine polish to other side and 8 mm mm thick glass panel with etching as per design and / or necessary beading patti including 3 coats of french polishing including door shutters as per architectural design with heavy duty hinges handles / handles / locks etc. of approved make.	25	Sqm		
7	Full height panelled partition for server room: Providing and fixing in position partly glazed & partly panelled partition made of 50 mm x 50mm x 1.2mm medium duty aluminium hollow square pipes framed at 0.60 m. to 0.45 m c/c both ways covered with 6 mm MR grade ply and 3mm aluminium composite panel of approved shade necessary beading patti including 3 coats of french polishing including door shutters as per architectural design with heavy duty hinges handles / handles / locks etc. of approved make.	5	Sq m		
8	Providing and fixing in position 3mm aluminum composite pannel of approved shade on existing plywood partition covered with 6 mm MR grade ply with necessary fittings and pasting material of approved shade with necessary fittings, silicon sealant and pasting material etc. as per requirement and instructions of Bank's Engineer.	35.00	Sq m		
9	Providing and fixing counter type desk made of 18/19 mm thick ply for top , sides, with a cabinet with a drawer & shutter finished with 4 mm thick veneer to outer facae and 0.8 mm laminate inside, as per specifications including provision for CPU base and footrest	1.5	Rmt		
10	Providing and fixing frosted film of 3 M/ LG make of approved design pattern, shade and colour to glass panels.	2	Sqm		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
11	Providing and applying acrylic emulsion paint of approved quality, shade and colour in 2 or more coats to achieve desired result including applying one coat of primer of cement paint, preparing the surface by cleaning the dust/dirt by watering/brushing the surfaces, filling in cracks/crevices ,scaffolding at all levels, necessary lead, lifts etc. complete	500	sq m		
12	Providing and Laying vitrified tiles of approved make and quality of required size for flooring and skirting in required position laid on bed of C.M.1:4 including cement float, filling joint with white / colour cement slurry, cleaning, curing, complete. 600 mm x 600 mm. size (Basic rate = Rs. 70/- per Sqft) The item rate shall be inclusive of removing the existing flooring & skirting.(for repair purpose)	300	sq m		
13	Constructing 9"thk. Brick masonry wall Providing & Constructing 6" thick brick wall masonry in cement Mortar (1:4) including (1:2:4) R.C.C.Patti of size 11cm X 15cm at bottom & 2 Nos. M.S. bars at to properly bend & bound at ends along with form work,scaffolding,racking out joint, both side neeru plaster finish, clean / level the surface, curing carting away debris out of compound, cleaning the site etc. complete as per instructions of Architect. RCC lintels of 100 mm thickness to be provided at each interval of 2.1 m during brickwork.	3	Cu Mtr		
14	Providing general cement plaster 12 mm in cement mortar (1:4) in all positions including curring, scaffolding, cleaning, carting away debris out of the compound, cleaning etc. complete as per the instructions of the architect.	10	Sq mt		
15	Providing & fixing Pantry Platform 750 mm wide out of 20 mm thk. Black granite supported over 12 mm thk. cement board including double moulding on the edges to granite, SS Nirali Sink (550 x 450), with 25 x 50 mm size Aluminium pipes TW inserted for framing below counter, including water supply CPVC pipes & bib-cocks, etc. complete. (Item includes dismantling of existing platform).	1.8	RMT		
16	Providing and fixing granite stone to treads and risers of staircase and entrance including all necessary material and labour.	10	Sq MTR		

	S U M M A R Y :		
	Total of Interior Work	Rs.	
	Less discount (if any)	Rs.	
	Total cost of work Tendered	Rs.	
	Add SGST @ 9%	Rs.	
	Add CGST @ 9%	Rs.	
	FINAL AMOUNT INCLUDING GST	Rs.	

SEAL AND SIGNATURE OF THE TENDERER

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
-------	-------------	-----	------	------	--------

Total Amount
 Rupees in words: _____

 Signature & Seal of Contractor
 Date: _____