

**INDICATIVE PRICE BID FOR THE CONSTRUCTION OF UNION/ ASSOCIATION OFFICE AND CANTEEN AT SBI, AO BUILDING,  
THRISSUR**

Item No	Quantity	Particulars	Unit	Rate	Rate in words	Amount
1	5.00	Providing and laying ready mix concrete M 20 including cost of all form work watering, curing etc complete but excluding cost of reinforcement for beam ,shade & lintel.	m <sup>3</sup>			
2	525.00	Reinforcement for RCC work bent tied and placed in position plain grill requiring bending in cold using tor steel including cost of binding wire.	Kg			
3	30.00	Solid block works of approved qty of size 30x20x15cm & of compressive strength not<35 kg/cm <sup>2</sup> in foundation and plinth in C.M. 1:6 Extra for solid block work in super-structure above plinth level including staging if required.	m <sup>3</sup>			
4	11.50	Supplying & fixing powder coated aluminum openable Doors using aluminium 34 series z,j,gullia in glazing clips section S,S friction hinges locking handles rubber beedings etc glazed with 5 mm clear glasses.	m <sup>2</sup>			
5	5.50	Supplying & fixing powder coated aluminum supersliding windows using aluminium 22 series, two track, EDPM rubber beading, 5 mm thick clear glass (Modi/Saint Gobain), TPI bearing sliding wheels handle with lock and all other accessories etc complete.	m <sup>2</sup>			
6	111.00	Flooring with vitrified tiles (Size60cmX60cm) minimum basic value should be @ Rs. 650/m <sup>2</sup> ) over a bed of C.M. 1:6,(1 Cement 6 course sand) 20mm thick and cement grouted and fixing the tiles on it with a minimum joint space using joint filler of approved quality and color etc. complete.	m <sup>2</sup>			
7	7.00	Dadoing walls with best quality premium colored/white tile size-20cmx30cm,or nearest size minimum basic value should be @ Rs.320 /m <sup>2</sup> ) over a bed of cement mortar 1:3, 9 mm thick add necessary cement grout and fixing the tiles to correct line and levels etc complete.	m <sup>2</sup>			
8	261.00	Plastering with Cement Mortar 1:5, (1 cement 5 sand) 12mm thick one coat floated hard and traveled smooth to inside walls including all staging work watering,curing etc complete.	m <sup>2</sup>			
9	170.00	Plastering with Cement Mortar 1:4, (1 cement 4 sand) 12mm thick one coat floated hard and traveled outside walls including all staging workw atering,curing etc complete.	m <sup>2</sup>			

**INDICATIVE PRICE BID FOR THE CONSTRUCTION OF UNION/ ASSOCIATION OFFICE AND CANTEEN AT SBI, AO BUILDING, THRISSUR**

Item No	Quantity	Particulars	Unit	Rate	Rate in words	Amount
10	262.00	Finishing New cement plastered wall with one coat primer, 2 coat of putty and painted with 2 coat of plastic emulsion paint after cleaning the surface .	m <sup>2</sup>			
11	175.00	Painting the exterior wall with one coat two coats of exterior grade emulsion paint (Apex or equivalent ) after cleaning the surface	m <sup>2</sup>			
12	29.00	Painting with synthetic enamel paint 2 coat over a priming coat to new wood work and iron work after cleaning the surface.	m <sup>2</sup>			
13	10.00	Drilling holes in the slab level concrete beam of required numbers and the direction of engineer to a depth of 100 mm and removal of dust etc., and clearing the holes to receive the dowel rods				
		Fixing and erecting the 16 mm dia beam rods to the sill beam in prepared holes using lockfix of Fosroc or equivalent as directed by engineer in charge for beam reinforcement	No			
14		<b>WATER PROOFING TREATMENT</b>				
	182.00	Providing and applying water proof treatment with Bostik boscolastic as per the manufactures specifications, after necessary surface preperation,crack filling with polyurethane sealant, filling and making good rough patches,chasing out V shape grooves around periphery as well as incoming and out going pipe lines,filling them up with Bostik Boscocem 475 modified mortar, saturating the surface and brush applying waterproof coating etc.,complete with all materials and labour etc complete.	m <sup>2</sup>			
15		<b>Screed concreting</b>				
	10.00	Providing and laying cement concrete of 1:2:4 (1 cement, 2 sand, 4 graded stone) with 6 mm nominal size aggregate for providing required slope in the roof, including watering, curing, etc complete.	m <sup>3</sup>			
16		<b>Sheet roof</b>				
	62.00	Providing and laying truss work and trafford sheeting (0.4 mm thick) over the stair case area applying two coats of enamel paint over a coat of zinc chromate primer including materials and labour charges etc complete	m <sup>2</sup>			

**INDICATIVE PRICE BID FOR THE CONSTRUCTION OF UNION/ ASSOCIATION OFFICE AND CANTEEN AT SBI, AO BUILDING,  
THRISSUR**

Item No	Quantity	Particulars	Unit	Rate	Rate in words	Amount
17	25.00	Providing and fixing 160 mm dia PVC Semi-circular rain water pipe (gutter/pathy) made out of 160 mm PVC pipe to the existing roof level below profile sheet with necessary fixing arrangement etc all complete as per the direction of Engineer-in-charge.	M			
18	20.00	Providing and fixing 75 mm unplasticised Rigid PVC rain water pipes with necessary fixing arrangement etc all complete as per the direction of Engineer-in-charge.	M			
<b>TOTAL Amount</b>						
<b>GST @ 18%</b>						
<b>TOTAL Amount (including GST)</b>						