

BOQ & SPECIFICATIONS FOR PROPOSED INTERIOR FURNISHING WORK FOR DABRA BRANCH (GWALIOR REGION)

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
INTERIOR WORK					
1	FULL HEIGHT FULLY GLAZED 12.0MM TOUGHENED GLASS PARTITION.				
	Providing & fixing at Fully glazed partition to be made up of 200mm or (as per site top & bottom sections) to be made up with 19.0mm commercial board, the middle portion of the partition shall have fully glazed 1900mm (h) 12.0 mm Toughened glass to be fixed to top & bottom frame with help of wooden beadings, the wooden portion of the partition shall have 1.0mm thick Laminated finish on both the sides of approved shade & finish . The wooden beadings to have melamine polish. The cost shall include all labour, materials, contingencies, transportation etc complete.	18.00	SQM		
2	FULL HEIGHT PARTLY GLAZED PARTITION				
	Providing & fixing at site partly glazed partition with 50 x 75 x 1.2 mm Aluminum box frame with spacing at 600- 900c/c horizontally & vertically, to be sandwiched with 8.0mm Commercial ply from both the sides and finished with 1.0mm thick approved shades of laminated finish, The middle portion to have 8.0mm plain float mm. glass to be fixed to be fixed in partition above 3'0" and upto 7'0" level to be fixed with 1.25" x 1" wooden beadings. The cost shall include all labor, materials, strictly as per the given design & drawing etc complete.	28.00	SQM		
3	FLUSH DOOR'S FOR PARTLY GLAZED/ SOLID PARTITION WITH FRAME				
	Providing & fixing at site Door for partly glazed partition, door shall be of 32.0mm Commercial grade flush door with 1.0mm lamination on both the sides, and central portion to have 8.0mm plain float glass to be fixed with help of teak wood beadings. The Door is to be fixed to existing wooden partition/wall with heavy duty 5" Stainless Steel hinges, and shall have godrej Or equivalent mortice lock. All the edges of the door to be covered with 35 x 12 mm Teak wood beadings, The cost shall include Frame of 2nd class BTC/ Teak wood Frame of 100mm x 50 mm, all labor, materials, mortice lock, tower bolt inside, door stopper strictly as per the given design & drawing etc complete.	6.00	SQM		
4	SOLID PARTITION				
	Providing & fixing at site partly glazed partition with 50 x 75 x 1.2 mm Aluminum box frame with spacing at 600- 900c/c horizontally & vertically, to be sandwiched with 8.0mm Commercial ply from both the sides and finished with 1.0mm thick laminated finish on both the sides, The cost shall include all labor, materials, strictly as per the given design & drawing etc complete.	3.50	SQM		
5	HALF HT. PARTITION				

	Providing and fixing at site 1200(h) half height partition with 50 x 75 x 1.2 mm Aluminium box frame at 600 to 900 mm c/c. or as per the drawing to be erected . The frame is to be sandwiched with 8mm thick Commercial ply to be fixed from both sides .The partition is to be finished with 1.0 mm thick approved colour laminate of standard make. The partition shall have 12.0 mm thick plain Glass of height 200-300mm on top portion of the partition, teak wood beadings, The teak wood beadings to be finished with melamine polish. of size 40 x 20mm with natural polish to match the partition. All other exposed edges of sections are to be properly covered with 8mm ply & laminated finish, The cost of partition shall include necessary fittings, labour, contingencies etc complete strcitly as per the given design & drawings.	30.00	sqm		
6	ALUMINIUM DOOR WITH FRAME FOR UPS & SERVER :				
	Providing and fixing at site door to be made up approved shade of powder coated aluminum sections (heavy duty) as top & bottom sections with 6.0mm thick plain FLOAT glass in between, the glass panel shall have round polished edges. The external frame of the door shall be of size 100 x 50 x 2.0mm powder coated aluminum Box section section to be fixed in walls / as per site with anchor fasteners and heavy duty mechanical screws. The door shutter shall be in aluminum sections 85.0 x 44.5 x 2.0mm for top, and sides and 114.3x 44.5x 3.0mm in bottom rail, inclusive of with standard aluminum clips to be made strictly as per the drawing. and pivot arrangement ,with SS handles, all necessary fittings, all labour, materials, etc complete. (to be fixed in sever & UPS room)	4.20	SQM		
7	<u>FRONT & TOP TOUGHNED GLASS FOR COUNTER</u>				
	Providing and fixing over the SWO counter over Front & top with 12.0 MM toughened glass of height 450mm, and top size of 300mm width, the glass shall have necessary rounding finish/ bevelled edges as per the requirement, The Glass is to be fixed with side partition with help of Teak wood beadings and members, The wooden members to have mealamine polish, the cost shall include all materials, labour, transportation to site, fixing etc complete.	4.50	sqm		
8	<u>WICKET GATE</u>				
	Providing and fixing at site wicket gate in the existing partition to be made up well seasoned hard wood/ 32mm flush door with 8.0 mm commercial ply, to be laminated on both faces with 1.0 mm thick laminate of approved shade, The cost of the gate shall include SS hinges, door closer , tower bolt, locking arrangement etc. complete.	2.00	sqm		
9	<u>VERTICAL BLINDS</u>				
	Providing and fixing at site vertical blinds 100mm wide vertical blinds with extruded powder coated head rail housing control units, spacers, runners, tilt rod with reduction gear mechanism, tilt control for rotation for rotation of 180 degree louvers made of approved fabric/ colour scotch guard coating & bottom mechanism of powder coated galvanised steel with required components.	13.00	sqm		
10	<u>MAIN ENTRANCE/ BM DOOR WITH 12.0MM TOUGHNED GLASS & Patch Fittings</u>				

	Providing and fixing at site Main entrance/ other doors "fully glazed" of 12.0mm toughened glass to be fixed with patch fittings including locks, with 600mm SS brush finished "D" Type door handle. The cost shall include all the fittings, Door handles, locks all materials, transportation fixing , all labour, contingencies etc complete but excluding cost of Floor Spring.	4.50	sqm		
11	<u>FLOOR SPRING</u>				
	Providing and fixing at site heavy duty Hydraulic floor spring for 12.0mm thick toughened glass door with patch fitting of Godrej/ Doorma Make only, to be fixed at site, inclusive of all labour, materials, contingencies etc complete.	2.00	NOS		
12	<u>FIXED GLAZING AT FRONT WITH 12.0MM TOUGHNED GLASS & Patch Fittings</u>				
	Providing and fixing at site 12.0mm toughened glass fixed glazing at front to be fixed with SS patch fittings at the site including filling of silicon sealant at all edges, gaps, wherever necessary as per the site condition, all materials, labour etc complete.	7.60	SQM		
13	<u>COLUMN/ WALL PANELING WITH LAMINATED FINISH</u>				
	Providing and fixing at site column/ wall paneling with 50 x 19mm aluminum pipe section to be fixed with spacing between 300-400mm c/c vertically and top & bottom horizontally, as per the requirement to be finished with 8.0mm commercial Grade ply finished with 1.0mm laminate. of approved colour to be fixed in given pattern in two shades of approved colour and shade is to be fixed as per the given design & pattern. The top of the wall panelling to have 25 x 50mm teak wood beading on top to be finished with melamine polish, the cost shall include all materials, labour etc complete.	80.00	sqm		
14	<u>HDF PANEL WALL PANELLING (including 12.0mm Back Ply)</u>				
	Providing and fixing at site wall paneling with 50 x 25mm aluminium box section placing at every 300mm c/c to be fixed over the wall as per the site requirement to be finished with 1 2.0mm BWP Grade ply & 8.0mm Commercial Grade HDF Panel to be fixed at site over the 12.0mm ply with grooved pattern, to be finished with 1.0 mm laminates of approved colour and shade, is to be fixed as per the given design & pattern all exposed members to be duly painted to match the existing shades of paneling The cost shall include all materials, labour etc complete.	17.00	sqm		
15	<u>ETCHING FILM</u>				
	Providing and fixing at site approved design & pattern of etching film to be 3m 7725--325 Pressure sensitive film for permanent graphic fixed at site over the glazed area as per the given design & drawing including all materials, wastage etc complete.	30.00	SQM		
16	<u>FALSE CEILING (GYPSUM)</u>				

	Providing and fixing gypsum false ceiling. in 12.5mm thick Gypboard (POP) plain false ceiling with corner POP molding & GI suspended from RCC slab/ Beam as approved by Bank/ Architect including G.I. Parameter Channels of size 0.55 mm thick having one flange of 20mm and another flange of 30mm and web of 27mm along with parameter of ceiling,screw fixed, to the brick wall / partition with the help of nylon sleeves and screws at 600mm C/C. The suspended G.I. Intermediate channels of size 45 x 0.9 mm thick with two flanges of 15mm each from the soffit at 1200mm C/C with GI cleats and steel expansion fasteners. Ceiling sections of 0.55mm thick having web of	125.00	sqm		
	51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to intermediate channel with help of connecting clips and in direction perpendicular to intermediate channel at 457 mm C/C. 12.5mmTapered edge Gypboard channel at 457mm C/C in both the directions screwed fixed to the ceiling section with 25mm dry wall screws at 230mm C/C screw, fixing is done mechanically with drilling machine and suitable attachment. Finally the boards are to be jointed and finished with jointing compound, paper tape andtwo coats of top Coat, suitable for Gypboard (As recommended practice of India Gyp.) For light fittings incutouts etc are to be made with a frame of parameter channels of size 20 x 27 x 30 x 0.5mm thick supported suitably. Angle beads, edge bends, control joints as required to be provided. The quoted rates to include allthe above items, ceiling to be painted with minimum two coats of plastic emulsion paint including base preparation. etc. complete.				
17	FALSE CEILING (ARMSTRONG)				
	Providing and fixing of false ceiling at all heights of 600mmx600mmx12mm Armstrong mineral fiber ceiling tiles of type IBIZA RH-90 laid on Armstrong prelude XL exposed grid systems with 9mm wide T Section flanges colour white. The frame work comprise of main runner spaced at 1200mm centers securely fixed to the structural soffit approved hangers at 1200mm maximum centers. Hangers (GI wire) to be fixed by approved roof plug and screws etc. The last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall. flush fitting 1200mm along cross tees (with double stitching) to be interlocked between main runners at 600mm c/ c to form 1200x600mm modules. Cut cross tees longer than 600mm to be supported independently. 600mmx600mm modules to be formed by fittings 600mm long flush fitting cross tees centrally between the 1200mm cross tees. Perimeter trim to be Armstrong wall angle secured to walls at 450mm maximum centers.	145.00	sqm		
18	COMPUTER COUNTER				
	Providing & fixing at site 2'-0" wide computer platform in server room to be made in 18 mm thick Commercial Ply to be supported with 18 mm Commercial Ply verticals AT 4' C/c. The computer platform shall have sliding keyboard at every 4'-0" c/c and shall have single drawer at every 4'-0" c/c. All the exposed surfaces 1.0mm thick laminated finish, and all the inner surfaces to have 0.8mm thick laminated finish. All exposed edges shall have 18 mm teak wood beading, duly polished with melamine polish, including all materials, labour etc. complete.	1.50	RM		
19	HALF HEIGHT STORAGE				

	Providing and fixing at site Half height storage cabinet 2'6" High fully covered from all sides and 18" deep including necessary shelves as per the design and specifications with openable shutters made up of 18mm Commercial ply, The rear portion is to be closed with 12.0mm ply, The cabinet is to be finished with 1.0mm thick laminated finish on external surfaces and 0.8mm thick laminated finish on inside surfaces. All the exposed edges to be finish with 20 x 6.0mm teak wood beadings finished with mealamine polish, The cost shall include all materials, handels, magnetic catchers, all labor, accessories etc complete.	22.00	sqm		
20	<u>WRITING DESK</u>				
	Providing & fixing at site Wall mounted writing desk as per design & drawings in the Branch made up of 18mm thick Commercial ply and 1.0mm thick laminated finished, and inside surfaces with 0.8mm laminated finish, to be hanged from the wall having the space for keeping vouchers, top of 12 mm Toughned Glass per design & drawing etc. complete.	1.00	NOS.		
21	<u>NOTICE BOARD</u>				
	Providing & fixing at site notice board of size 4' x 3' to be made up of kail/pine wood frame of size 3" x1.5" teak wooden section The Notice board shall have 19.0mm soft board lining at back with approved shade of cloth, strictly as per the design & drawing etc complete, including all materials, labour etc complete.	2.00	SQM		
22	<u>DROP & COMPLANT BOX</u>				
	Providing & fixing at site drop & complaint box of size 1' x 1'3" to be made up of 19mm commercial board frame, to be finished with 1.0mm thick laminated finish, and 0.8mm thick laminate on inside surfaces, strictly as per the design & drawing etc complete.	2.00	NOS.		
23	<u>DOOR CLOSERS</u>				
	Providing & Fixing Hydraulic Door Closers, godrej or EQ Make to Door Shutter with Frames using necessary Screws, Nuts & Bolts etc. complete.	7.00	NOS		
24	<u>ALUMINIUM CLADDING</u>				
	Providing & Fixing at site 3.0mm thick Aluminum External cladding to be fixed at the site over Aluminum tubular pipes placed between 600 x 750mm in both the directions with two colours, as per the design, all the joints shall be filled by exterior grade of Silicon sealant, the cost shall include all materials, labour etc complete	45.00	Sqm		
25	<u>FRONT SHUTTER COVER BELOW PANTRY PLATFORM</u>				
	Providing and fixing at site front shutter cover in 25.0mm thick Commercial block board with 1.0mm thick laminated finish on external surfaces and 0.8mm thick laminated finish on inside surfaces, the shutters to be fixed to main frame by heavy duty SS Hinges, the cost shall include all handles, magnetic catchers, locks accessories as required etc complete.	2.20	SQM		
	TOTAL INTERIOR WORKS FOR BRANCH (A)				
	<u>FURNITURES WORK</u>				
1	<u>MANAGER TABLE</u>				

a.	Providing at site Chief Manager Table Size- 6'x2'6"x2'6" at site as per design to be made up of 18 mm Commercial ply with top White 12.0 mm Corian finish and sides Blue Laminated Glass. Table top is to be made up of 12mm thick Toughened glass to be fixed with steel studs as per the given design & Table Front 12 mm thick Toughened Glass Modesty panel. The table shall have 1 No. 400mm wide cupboard with 1 No sliding tea tray and three Nos drawers on one side & provision of keeping Computer with Sliding keyboard Tray below it. All drawers are to be provided with telescopic sliding rails. The exposed edges of ply are to be finished with mdf beading/lipping with matching shades. The cost of the table shall include all necessary powder coated fittings. Material, labour etc. complete.	1.00	Nos		
b.	Providing & fixing at site/ rear credenza 3'6" x 16" x 2'6", which is an independent unit with storage almirah with openable shutters to be made up of 18mm Commercial ply to be finished with 1.0mm laminated finish . The top of the credenza to have "Corian finish". The inside portion shall 085.mm thick white laminated finish. All drawers are to be provided with telescopic Sliding Rails. The cost shall include all necessary fittings, Knobs, locks etc. complete strictly as per the given design & drawing.	1.00	No		
2	<u>SINGLE WINDOW TRANSACTION COUNTER</u>				
	Providing and fixing at site SWT counter of size-5'X2'6" to be made up of 18mm Commercial ply and finished of approved shade & colour Acrylic Surface tops 12.0mm " Corian" for counter top, Blue Lacquered Glass/ Blue Shade high Gloss PU coating on Fascia & Light Blue transparent Glass between single windows. The inside of counter shall have 0.8mm white laminated finish. Three Nos drawers are to be made at right side with heavy duty ISI Marked telescopic sliding rail. The drawers shall have self closing locks of godrej make. The counter shall have computer sliding Key Board tray to be fixed in it. provision to be made to keep CPU shelf as per the drawing to be placed below the corner of the table. All exposed edges to be ply to be finished with wood/ nuwood beading to finished to match the colour of laminate, the cost shall include all materials, labor contingencies etc complete, strictly as per the given drawing	5.00	nos		
3	<u>SALES / OFFICER TABLE</u>				
	Providing and fixing at site table size 5'X2'6" as per the design and shape to be made up of 18mm Commercial ply with 1 nos. cupboard below it having tea tray, sliding drawer unit (with sliding rails) . Table top is to be made up of Teak veneer with High gloss PU finish on table top, White laminate on sides and modesty panel. The table shall have computer with sliding keyboard as per design & specifications, all exposed surfaces to be finished with 1.0mm laminated finish and pattern of other color Laminate . The cost shall include all accessories such as sliding rails, drawer locks etc complete. The table is to be made with two different shades of laminate in skirting and design, including all materials, labor etc complete strictly as per the drawing.	11.00	Nos.		
4	<u>SIDE CREDENZA</u>				

	Providing & fixing at site rear credenza 3'3" x 16" x 2'6", which is an independent unit with storage almirah with openable shutters to be made up of 18mm Commercial ply to be finished with 1.0mm laminated finish. The top of the credenza to have "Corian finish". The inside portion shall 0.8mm thick white laminated finish. All drawers are to be provided with telescopic Sliding Rails. The cost shall include all necessary fittings, Knobs, locks etc. complete strictly as per the given design & drawing	16.00	Nos.		
5	GRAHAK MITRA TABLE				
	Providing and fixing Grahak Mitra Table size- 4'X 2'3"X3'6" as per given Design, Drawing in made 18mm thk.BWP Ply & finished white Corian of approved make for table top and sides. Table Front 12.0 mm thick Blue toughened Glass with approved colour & on additional raised panel 12mm.thk. BWP ply. With approved colour laminate fixed with approved make and shade / design etc. complete. (Low height partitions abutting the counters will be paid separately).	1.00	Nos.		
	TOTAL FURNITURE WORKS FOR BRANCH (B)				
	CIVIL WORKS				
1	POP PUNNING				
	Scraping of old paint/ distemper wherever necessary from the existing walls, and applying of 4.0 to 8.0 mm thick lime punning over it to give a smooth leveled finish, the final coat of punning to have one coat of oil based Cement primer the cost shall include all labor , materials, etc complete.	142.00	SQM		
2	ACRYLIC EMULSION PAINT				
	Applying one coat of cement premier and applying two or more coats of Acrylic emulsion Royale/ Velvet touche to be applied over the punning area with roller to give desired smooth finish, including one coat of Birla Putty properly sand papered to give a neat smooth & silky finish, the cost shall include all materials, labour etc complete.	142.00	SQM		
3	SYNTHETIC ENAMEL PAINT				
	Two or more coats of approved shade synthetic enamel including one base coat of steel/ wooden primer over the existing wooden/ steel surfaces, with brush after cleaning & scrapping by wire brushing. Including all materials, labour etc complete.	50.00	SQM		
4	OIL BOND DISTEMPER				
	Two or more coats of Acrylic oil bond distemper with brush over the existing wall surfaces, after scrapping the existing finish, applying one coat of cement premier and one coat of putty to repair the wall as per the site condition including all materials, labour etc complete.	422.00	Sqm		
5	TEXTURED PAINT				
	Applying approved shade, pattern and surface textured paint over the wall, to give an even shade/ pattern, including all materials, labour etc complete, over the existing POP punning wall surface	10.00	sqm		
6	ALUMINIUM FIXED/ SLIDING WINDOWS GLAZING				

	Providing and fixing at site Powder coated framed FIXED / SLIDING SHUTTERS with 5.0mm glass aluminum sliding windows, to be fabricated at the site as per the given design & drawing, the external frame shall be of 100 x 50mm Box section as frame and the sliding windows shall have standard sliding two trac sliding channels, the sliding shutters shall have rubber gasket, locking arrangement all materials, labor accessories etc complete.	5.00	SQM		
	TOTAL FOR CIVIL WORK (C)				
	<u>INTERIOR WORK FOR E-LOBBY</u>				
1	<u>SOLID PARTITION WITH DOOR</u>				
	Providing & fixing at site full solid partition with 50 x 75 x 1.2 mm Aluminium box frame with spacing at 600c/c horizontally & vertically, to be sandwiched with 8.0mm HDF/ BWP ply same from both the sides and finished with 1.0mm thick approved shades of laminated finish, The door shall have side frame made up of 19.0mm BWP Ply/ with necessary beadings at edges, The door shall be of 32.0mm flush door with 1.0mm lamination on both the sides, to be fixed to partition with heavy duty 4" SS hinges, and shall have cylindrical lock. The cost shall include all labor, materials, strictly as per the given design & drawing etc complete.	12.60	SQM		
2	<u>INTERNAL GLASS PARTITION</u>				
	Providing and fixing at site 12.0mm toughed glass internal partition of size 1050 x 1350mm with S.S patch fittings including with approved pattern of etching to be fixed at the site, the cost shall include all materials, labor etc complete.	1.10	sqm		
3	<u>MAIN ENTRANCE DOOR WITH 12.0MM TOUGHENED GLASS & Patch Fittings</u>				
	Providing and fixing at site Main entrance/ other doors "fully glazed" of 12.0mm toughened glass to be fixed with patch fittings including locks, with 600mm SS brush finished "D" Type door handle. The cost shall include all the fittings, Door handles, locks all materials, transportation fixing , all labour, contingencies etc complete but excluding cost of Floor Spring.	2.60	sqm		
4	<u>FLOOR SPRING</u>				
	Providing and fixing at site heavy duty Hydraulic floor spring for 12.0mm thick toughened glass door with patch fitting of Godrej/ Doorma Make only, to be fixed at site, inclusive of all labour, materials, contingencies etc complete.	1.00	NOS		
5	<u>FIXED GLAZING AT FRONT WITH 12.0MM TOUGHENED GLASS & Patch Fittings</u>				
	Providing and fixing at site 12.0mm toughened glass fixed glazing at front to be fixed with SS patch fittings at the site including filling of silicon sealant at all edges, gaps, wherever necessary as per the site condition, all materials, labour etc complete.	3.20	SQM		
6	<u>FALSE CEILING (GYPSUM)</u>				

	Providing and fixing gypsum false ceiling. in 12.5mm thick Gypboard (POP) plain false ceiling with corner POP molding & GI suspended from RCC slab/ Beam as approved by Bank/ Architect including G.I. Parameter Channels of size 0.55 mm thick having one flange of 20mm and another flange of 30mm and web of 27mm along with parameter of ceiling,screw fixed, to the brick wall / partition with the help of nylon sleeves and screws at 600mm C/C. The suspended G.I. Intermediate channels of size 45 x 0.9 mm thick with two flanges of 15mm each from the soffit at 1200mm C/C with GI cleats and steel expansion fasteners. Ceiling sections of 0.55mm thick having web of	4.70	sqm		
	51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to intermediate channel with help of connecting clips and in direction perpendicular to intermediate channel at 457 mm C/C. 12.5mmTapered edge Gypboard channel at 457mm C/C in both the directions screwed fixed to the ceiling section with 25mm dry wall screws at 230mm C/C screw, fixing is done mechanically with drilling machine and suitable attachment. Finally the boards are to be jointed and finished with jointing compound, paper tape andtwo coats of top Coat, suitable for Gypboard (As recommended practice of India Gyp.) For light fittings incutouts etc are to be made with a frame of parameter channels of size 20 x 27 x 30 x 0.5mm thick supported suitably. Angle beads, edge bends, control joints as required to be provided. The quoted rates to include allthe above items, ceiling to be painted with minimum two coats of plastic emulsion paint including base preparation. etc. complete.				
7	FALSE CEILING (ARMSTRONG)				
	Providing and fixing of false ceiling at all heights of 600mmx600mmx12mm Armstrong mineral fiber ceiling tiles of type IBIZA RH-90 laid on Armstrong prelude XL exposed grid systems with 9mm wide T Section flanges colour white. The frame work comprise of main runner spaced at 1200mm centers securely fixed to the structural soffit approved hangers at 1200mm maximum centers. Hangers (GI wire) to be fixed by approved roof plug and screws etc. The last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall. flush fitting 1200mm along cross tees (with double stitching) to be interlocked between main runners at 600mm c/ c to form 1200x600mm modules. Cut cross tees longer than 600mm to be supported independently. 600mmx600mm modules to be formed by fittings 600mm long flush fitting cross tees centrally between the 1200mm cross tees. Perimeter trim to be Armstrong wall angle secured to walls at 450mm maximum centers.	3.00	sqm		
8	COMPUTER PLATFORM				
	Providing & fixing at site 2'-0" wide computer platform in server room to be made in 18 mm thick Commercial Ply to be supported with 18 mm Commercial Ply verticals AT 4' C/c. The computer platform shall have sliding keyboard at every 4'-0" c/c and shall have single drawer at every 4'-0" c/c. All the exposed surfaces 1.0mm thick laminated finish. All exposed edges shall have 18 mm kail/pine wood/ nuwood beading,duly polished with natural polish, including all materials, labour etc. complete.	1.00	RM		
9	WRITING DESK				

	Providing & fixing at site Wall mounted writing desk as per design & drawings in the Branch made up of 18mm thick Commercial ply and laminated finished to be hanged from the wall having the space for keeping vouchers, top of 12 mm Toughned Glass per design & drawing etc. complete.	1.00	NOS.		
10	<u>DOOR CLOSERS</u>				
	Providing & Fixing Hydraulic Door Closers to Door Shutter with Frames using necessary Screws, Nuts & Bolts etc. complete.	1.00	NOS		
11	<u>ALUMINIUM CLADDING WORK</u>				
	Providing & Fixing at site 3.0mm thick Aluminum l cladding to be fixed at the site over Aluminum tubular pipes placed between 600 x 750mm in both the directions with two colours, as per the design, all the joints shall be filled by exterior grade of Silicon sealant, the cost shall include all materials, labour etc complete	42.00	Sqm		
	TOTAL INTERIOR WORKS FOR E- LOBBY (D)				
	TOTAL AMOUNT (A+B+C+D) EXCLUDING GST				

GST SHALL BE PAID EXTRA AS APPLICABLE

SEAL/SIGN OF THE CONTRACTOR/FIRM