



SBI INFRA MANAGEMENT SOLUTIONS PVT.LTD.

**CIRCLE OFFICE, THIRD FLOOR, STATE BANK OF INDIA, SYNERGY BUILDING,
C-6, G-BLOCK, BANDRA KURLA COMPLEX, BANDRA EAST, MUMBAI-400051**

PART – B: FINANCIAL BID

TENDER FOR:

PROPOSED AC WORK FOR ADB BRANCH, AMRAVATI

TENDER SUBMITTED BY:

NAME : _____

ADDRESS : _____

DATE : _____

TENDER INVITED BY:

**Vice President & Circle Head,
SBI Infra Management Solutions Pvt. Ltd; 3rd floor, Circle Office, State Bank of India, Synergy
building, C-6, G-Block, Bandra -Kurla complex, Bandra East, Mumbai-400051.**

ARCHITECT :

**Ashfaque Ahmed Consultancy Services Lvt.Ltd.,
289, New Colony,Sadar Nagpur – 440001
Tel : 9823054655 / 0712-2595752 / 25833493 E-Mail : craftteam9@yahoo.co.in**

Tender paper of AC Work**SBI Bank,ADB Branch, Amravati.**

Sr. No.	Description	Quantity	Unit of measure	Unit Rate(Rs.)	Amount(Rs.)
	PART-A				
1	Supply of Airconditioners				
1.1	Supply of Air Cooled wall mounted split Air conditioners complete with outdoor and Indoor unit, cordless remote with LED Display which shall be sleek, synthetic washable filter, with energy efficient hermetically sealed compressors as per original specification of Manufacturers of Blue Star / Diakin / Carrier / Hitachi/Mitsubishi.				
	1.5 TR (Minimum 3 Star rating)	2	Nos.		
	1.0 TR (Minimum 3 Star rating)	2	Nos.		
1.2	Supply of Air Cooled ceiling mounted four way air discharge for even cooling, multispeed fan motor. The blower shall be balanced and designed for silent operation, filter shall be synthetic and washable type arrange for convenient cleaning & replacement, Built-in automatic drain pump, the drain pan shall be fabricated out heavy sheet metal and insulated, cassette type Airconditioners with energy efficient hermetically sealed rotary/scroll compressors as per original specification of Manufacturers of Blue Star / Diakin / Carrier / Hitachi/Mitsubishi				
	2.0 TR	11	Nos.		
	TOTAL Part A (without GST)				

	PART-B				
1.1	Lifting,shifting ,Installation, Testing, & Commissioning as per site condition of Hi wall split unit with first charge of refrigerant and oil.(For hi-wall unit 4 mtr. of Refrigerant piping both run & cable is included & multiple run of Refrigerant piping,cabling & drain etc between in door unit to out door unit shall be considered as single length for the purpose of measurement.)	4	Nos.		
1.2	Lifting,shifting ,Installation, Testing, & Commissioning of Cassette type split unit with first charge of refrigerant and oil.(For cassette unit 5 Mtr. of Refrigerant piping both run & cable is included)				
	2.0 TR	11	Nos.		
2	Supply ,Installation testing and commissioning of Refrigerant Copper piping insulated with Thermo foam 6 mm thick with between evaporator and condensing units for the cassette Units of the following sizes				
	Split A/C- 1/4" - 1/2" dia (insulated)	20	Rmts.		
	Cassette A/C-3/4"-3/1" dia (insulated)	80	Rmts.		
3.1	SITC of condensate water drain piping 25 mm Dia in UPVC for split units . The pipes shall be insulated with nitrile rubber (6 mm Thick) (Make:Finolex/Supreme/Prince/)	50	Rmts.		
3.2	SITC of condensate water drain piping 40 mm Dia in UPVC for Cassette type units . The pipes shall be insulated with nitrile rubber (6 mm Thick) (Make:Finolex/Supreme/Prince/)	80	Rmts.		
4	Supply ,Installation testing and commissioning of Electrical Cable of 4 corex4 sq.mm copper cable of appropriate size as approved by manufacturing standard between evaporator and condensing units for the split & Cassette type units.(Make:Finolex/Supreme/Prince/)	80	Nos		
5	Supply ,Installation testing and commissioning of Electrical Cable of 3 corex2.5 sq.mm copper cable of appropriate size as approved by manufacturing standard between evaporator and condensing units for the split & Cassette type units.(Make:Finolex/Supreme/Prince/)	30	Mtr		

6	Providing and installing Sequential timer for indoor units.	1	Nos		
7	SITC of MS stand of minimum 5 mm Thickness (Black painted) with Vibration Isolator Rubber Pads for condensing units of Hiwall split outdoor units	4	Nos		
8	SITC of MS stand of minimum 5 mm Thickness (Black painted) with Vibration Isolator Rubber Pads for condensing units of	11	Nos,		
9	Dismantling of existing AC with its all accessories and parts in complete.	1	Job		
10	Transporation, Necessary civil work : Trenching work / Making & remaking of holes in walls, final finishing the same in all respects etc.	1	Job		
11	Supply, installation, testing & commissioning Real Time Electronic cyclic timer Switch (DW219BLK of MK) for Server room AC Units for one working & one standby. The timer shall be programmable for upto 4/8 hours cyclic period with Auto & Manual modes, The rate to include all components, timers, controlling MCB, Powder coated M.S. housing, power wiring with Elmax make or equ. terminals for incoming /outgoing connections etc-	1	No		
TOTAL of PART B (without GST)					
PART A(Without GST)					
PART B(Without GST)					
GRAND TOTAL (PART A & PART B)					

IN WORDS:

S U M M A R Y :

Total of AC Work	Rs.	
Less discount (if any)	Rs.	
Total cost of work Tendered	Rs.	
Add SGST @ 9%	Rs.	
Add CGST @ 9%	Rs.	
FINAL AMOUNT INCLUDING GST	Rs.	

Total Amount

Rupees in words:

Signature & Seal of Contractor

Date

|

|