

**PRICE BID OF AC WORKS FOR STATE BANK OF INDIA PROPOSED
HALOL BRANCH, VAO-4 , DIST. PANCHMAHAL**

DUCTABLE AC UNITS FOR SBI HALOL BRANCH

NOTE : ALL CHARIS OR CHASES, HOLES IN WALLS / COLUMNS / SLABS MADE BY THE AC CONTRACTOR FOR INSTALLATION OF AC/COPPER PIPE/DRAIN PIPE ETC. THE FILLING OF THE SAME IS IN THE SCOPE OF THE AC CONTRACTOR INCLUDING ALL NECESSITY MATERIAL AND LABOUR.

THE CONTRACTOR SHOULD QUOTE THROUGHOUT THE TENDER FOR A PERTICULAR MAKE ONLY WITH R407/410 GAS BASED MODEL WITH THERMITICALLY SEALED SCROLL / ROTARY.

PRICE BID For Ductable Type Air conditioners System

SUPPLY (PART A) DUCTABLE BOQ FOR SBI HALOL BRANCH

Item No.	Description	Unit	Qty.	Unit Price	
				Rate (Rs.)	Amount (Rs.)
1	<u>Supply of Ceiling Suspended Ductable Type air conditioners</u>				
	<u>HITACHI/ CARRIER/DAIKIN MAKE - WITH R407/410 GAS</u>				
	Ductable A.C. Units (Air cooled) (INDOOR & OUTDOOR UNIT)				
	Ceiling Suspended air cooled type Ductable Type Air conditioner unit complete with the following components-(Bidder to offer Higher/Same Size of units & Suitable				
	Indoor unit comprising of , cooling coil, Centrifugal blower, Blower motor, drain tray, 20 Micron HDPE washable filters, Microprocessor based control unit, electrical junction box etc.				
	Outdoor unit comprising of Scroll type hermetically sealed compressor, condenser coils, propeller / axial fans, pressure switches / cutouts etc.				
a	Capacity :5.5 TR (working area common)	NO	2		
	5.5 TR R407/410 Gas				
b	Buy back of old Ductable AC units (INDOOR & OUTDOOR UNIT)				
	Removing & unloading from exising site and carry away from site. Inclusive of all type of expenses.				
	Capacity :5.5 TR (working area common)	NO	2		
TOTAL EQUIPMET PRICE WITHOUT GST (PART A)					

INSTALLATION (PART B) ANCILLARY WORK FOR PACKAGE TYPE UNIT					
Item No.	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	<u>Installation ,Testing & Commissioning</u>				
1	Shifting, Installation, Testing & Commissioning, gas charging etc complete				
	of Ceiling suspended ductable type Air conditioners INCLUDING Refrigerant GAS TOP UP / CHARGING AS REQD. (with R 407/410 Environment friendly Gas)				
	CAPACITY : 5.5 TR	NO	2		
2	supply and installation of flexible Canvas connection for each machine.	NO	2		
3	Made out of 22G Soft copper pipe inter connecting indoor unit including necessary cable	Rmt	30		
TOTAL INSTALLATION CHARGE WITHOUT GST (PART B)					
SUPPLY OF MACHINES + INSTALLATION		PART A + PART B			

- NOTE (1) ALL RATES SHOULD BE INCLUDE OF ALL TAXES EXCLUDING GST.
APPLICABLE GST WILL BE PAID EXTRA.
(2) THE CONTRACTOR SHOULD CHECK ELE. APPROVED MAKE LIST BEFORE QUOTE.
(3) THE CONTRACTOR SHOULD DEPUTE ONE PERSON AT SITE FROM START OF
(4) THE CONTRACTOR SHOULD WORK ACCORDING TO THE FINAL LAYOUT.
(5) THE TOTAL AMOUNT MAY VERY DEPENDING UPON ACTUAL QUANTITY
(6) CONTRACTOR SHOULD SUBMIT THE CERTIFICATE OF AC / WIRES / CABLES
(7) ALL RATES INCLUSIVE OF ALL TYPE OF LEADS & FREIGHTS ETC.