

## **BILL OF QUANTITIES**

## NAME OF WORK: AIR CONDITIONING WORKS( INCLUDING AMC FOR 5 YEARS OF AIR CONDITIONERS) AT MANGSANG BRANCH

| SI.N<br>o. | Description  | UOM                    | Qty. | Rate (Rs.)<br>(Exclusive of GST | Amount (Rs.)<br>(Exclusive of GST) |
|------------|--|------------------------|------|---------------------------------|------------------------------------|
| 1          | Supply of 1.5 TR Capacity Hi Wall mounting<br>5-star rated Inverter Split AC with cordless remote<br>and Copper Condensor Coil. AC Make,<br>Voltas/Bluestar /Carrier/Daikin /LG/Godrej/Hitachi   | No.                    | 2    |                                 |                                    |
|            | Installation charges of the <b>1.5 TR</b> Hi-Wall Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.  | No.                    | 2    |                                 |                                    |
| 3          | For 1.5 TR Hi-Wall type split air conditioners: Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages. | RM                     | 20   |                                 |                                    |
|            | Supply and Installation of 4 KVA Stabilizer for 1.5 TR<br>Split Acs  | Nos.                   | 2    |                                 |                                    |
| 5          | Comprehensive Annual Maintenance Contract of above mentioned <b>2 Nos</b> . of 1.5 TR Hi-Wall type split air conditioners after expiry of defect liability period of 1 year from the date of installation.   | year                   | 5    |                                 |                                    |
|            | GST will be extra as applicable  | Grand Total(In Rupees) |      |                                 |                                    |