

| BOQ for Interior works for Stressed Asset Management Branch, LHO | | | | | |
|---|---|------------|-------------|-------------|---------------|
| Sl | Description | Qty | Unit | Rate | Amount |
| 1 | Providing & fixing full height partitions with 8mm bison board along with putty and two coats of emulsion paint on one side and 6mm ply with 1mm thk laminate on the other, fixed to solid partitions made of aluminium framework @ 2'c/c. Partition will be finished as per the existing design, colour scheme and specifications complete. -for Record Room | 86 | Sqm | | |
| 2 | Fire proof door for Record room with same specifications as above but with necessary hardwares complete. | 1 | Nos | | |
| 3 | Fire proof door for Cash room :Providing and fixing hollow metal two hour fire rated doors as per IS 3614 part-1 and Part-2 for stability and Integrity,Pressed galvanized steel shoul confirm to IS 277 . | 1 | Nos | | |
| 4 | Cutting and patching up of false ceiling as directed including putty and painting complete. | 30.00 | Sqm | | |
| 5 | Providing and fixing Cash counter of 1500mmx840mmx750mm finished with 1.0mm thk laminate for outside surfaces and inside surfaces to be painted with enamel paint. The rate should include keyboard tray, foot rest and CPU stand. | 1 | Nos | | |
| 6 | Providing & fixing low height partitions for cash counter along with 35mm door: The partition to be made of aluminium framework @ 2'c/c fixed with 6mm ply and 1mm thk laminate pasted on the visible surfaces, with glass and etching work complete. Partition will be finished as per the existing design, colour scheme and specifications complete. | 5 | Sqm | | |
| 7 | Removing existing partition and carting away from the site. | 14 | Sqm | | |
| | Total | | | | |
| GST to be considered extra | | | | | |