



SBI INFRA MANAGEMENT SOLUTIONS PVT. LTD.
(A Wholly Owned Subsidiary of SBI)
CIRCLE OFFICE
SBI LOCAL HEAD OFFICE, 4TH FLOOR, III/1, PT. J N MARG
BHUBANESWAR-751001

Tender ID: BHU201904007

Date: 25.04.2019

NAME OF WORK :Furnishing of Temple Road Branch, SBI, Puri

NAME OF BIDDER/ FIRM

Address of the Firm

GST Reg. No. With HSN / SAC Code.

PAN NO:

Phone/Mobile no.

E-Mail ID

Sl.No	Description of work	Unit	Quantity	Rate	Amount
1	Removing the existing PVC flooring from the floor and keeping at first floor canteen area for relaying including disposal of unserviceable materials as per local bye-laws	sqm	240.00		0.00
2	Chasing the existing IPS/PCC floor manually including removing adhesives, cleaning etc., making the surface neat and clean rough surface to receive the tiles and disposal of rubbish outside the building premises.	sqm	240.00		0.00
3	Dismantling the existing plaster at first floor damp area and repairing the same with cement plaster of mix 1:3 (C:CS) admixed with water proofing compound including curing etc complete	sqm	60.00		0.00
4	Providing and laying PVC flooring removed from the ground floor at 2nd floor canteen area including cleaning with chemicals, cutting as per site conditions and laying with good quality adhesives in line level etc complete	sqm	80.00		0.00
5	P&F 12mm plain glass with edges polish and fixing with D clips or teak wood beading as per site conditions	sqm	7.00		0.00
6	Cleaning the existing glass panels with chemicals and damp soft cloth including removal of frosted films	no	12.00		0.00
7	Dismantling the elevated customer top of each counter and the modesty panel elevated materials to make the plain surface including removing the existing laminates and preparing the surface complete.	no	7.00		0.00
8	Providing and laying premium quality joint free double charged vitrified tile of size 600x600mm as per sample approved by engineer in charge laid using tile adhesive of Sika/ Fosroc/ Mycrete of 3 to 6mm thickness backing in proper line and level and in pattern as per drawing including surface preparation, cleaning the joints etc complete. A spacer 2mm to 6mm shall be provided with approved gap as per direction of engineer in charge) and filled with epoxy admixed with colouring pigment. The surface shall be cured sufficiently. Work shall be executed at any level and height.. Rate includes P&L PCC 1:2:4 wherever required to make the surface in line and level. (make: Somany/ Kajaria/ Johnson/ vrmora or as approved). Tile adhesive can be used in place of mortar as per site conditions	sqm	210.00		0.00
9	Finishing the wall surface with putty of Birla/ Asian. Berger with thickness of 3 to 6mm to make the surface in line and level including gyp ceiling. For applying putty in gyp ceiling, uniform thickness of putty will be maintained which may be 2 to 3mm as per site condition and level of undulation.	sqm	400.00		0.00
10	Roller Finishing the wall surface with two or more coat of wall primer followed by two or more coats of acrylic based royal shine paints of asian or equiv of berger/ ICI/ with approved shade and colour. Including gyp ceiling.	sqm	400.00		0.00
11	Dismantling existing grid ceiling and removing the rubbish materials outside the building premises. The GI channels shall be dismantled as per site conditions and users requirement and as directed by architect	sqm	85.00		0.00
12	Providing and fixing Gypsum false ceiling of India Gypsum / sainty gobain make which includes GI perimeter channels of size 0.55mm thick having one flange of 20mm and another flange of 30mm thick and web of 27mm along with perimeter of ceiling, screw fixed to brick work/ partition with the help of Nylon sleeves and screws at 610mm centers. Then suspending GI intermediate channels of 45mm (0.9mm thick with two flanges of 15mm thick each) from the soffit at 1220mm centers with ceiling angle of width 25mmx10mmx0.55mm thick fixed to soffit with GI cleat and steel expansion fasteners, ceiling section of 0.55mm thick having knurled web of 51.50mm and two flanges of 26mm each lips of 10.50mm are then fixed to the intermediate channel with the help of connecting clips and in direction perpendicular to the intermediate channels at 457mm centers.	sqm	100.00		0.00

13	Modular false ceiling with armstrong make Rh-95 and tegular edge 600x600 x15mm as specified by manufacturer. Installation to comprise main runner at 1200 centers fixed to structural outfits. First and last Armstrong suspension system should not be greater than 6000 from adjacent wall. 600x600 cross tees shall be provided between 1200 tees. M6 anchor fastener with verticle hangers made of galvanised steel 26x26x25x1.2mm , a pre straight hanger wire 2.68mm dia, adjustable hookss clipss of 0.8mm thick spring steel of 2.68mm shall be used.	sqm	75.00		0.00
14	Providing and fixing 32mm thickness flush door of Sylvam/ Globe/ century finished with teak wood lipping on all edges , three hinges for each door, one door stopper, one door closer of godrej make, one one motise lock of godrej make per doorfinished with 1mm thickness laminates of approved shade and colour (solid and glazed with 5mm thickness glass.	sqm	6.00		0.00
15	P&F door closere to doors two speed of godrej make	no	1.00		0.00
16	Providing and fixing sal wood frame work fixed to the walls or side partition as per site conditions with holdfasts including polishing the surface , rebating etc complete	cum	0.05		0.00
17	Dismantling the SWO counters completely including side units nearby to safe room and disposal the same outside the municipal limits	no	2.00		0.00
18	Dismantling one counter table near to entrance partly for making fla door of 18' wide including providing and fixing one flap dooe of 2' x18' with hinges, laminated finish and providing on verticle support of 19mm BB to the table duly laminated on expsed side and lipping on edges etc complete	no	1.00		0.00
19	Dismantling the existing partitions including all accessories like glass, hands and stacking the serviceable materials and disposal of unserviceable materials as per local bye laws	sqm	30.00		0.00
20	P&F good quality handles of approved shape and design pattern of make Godrej/ Dorma/ Haffle / equiv to the toughned glass doors	pair	2.00		0.00
21	P&F 12mm thick TOUGHNED glass partition with patch fittings at floor, top and side walls for full height Cabins. The glass shall be saint Gobain/ TATA while patch fittings shall be Godrej/ equiv. A sealant of wacker/ DOW crunning shall be provided in between glass panels. The glass panels shall be rigidly fixed to walls, floors and ceiling runners in proper alignment	sqm	3.00		0.00
22	P&F verticle blinds of d-décor or equiv as approved by engineer-in-chrage wwith colour and shade as approved along with all accessories	sqm	20.00		0.00
23	P&F 12mm thick TOUGHNED glass door with edge polish and finishing with plastic cover on edges including making holes for patch fiting with suitable patch fittings etc required as per site conditions. The glass shall be saint Gobain/ TATA while patch fittings shall be Godrej/ equiv.	sqm	0.00		0.00
24	P&F frosted film of 3-M/ LG make of approved design pattern, shade and colour to glass panels	sqm	10.00		0.00
25	P&F door floor spring of Dorma/ Godrej as approved to the toughned glass door	no	1.00		0.00
26	Removing the existing laminates of column panelling and providing and fixing 3.00 m thick MDF board on all sides with a groove at top and bottom and finishing with 1mm thick laminates of approved shade and colour with fevicols and etc complete	sqm	70.00		0.00
27	Server room table: Providing and fixing server room table made of 19mm BWR grade block board as table top with drawer units. The sides shall be 19mm block board. The drawer size shall be 450wide x500mm deep with two verticlas of 19mm BB. The drawer shall have telescopic ebco make sliding channels, handles, locks etc. All exposed surface shall be finished with 1mm thick lamiante. Table shall have one pvc key board tray of ebco make per 5' running length. All inside surface shall be polished. All edges shall be finished with teak lipping and specially table edge shall be finished with half round teak wood lipping PU Polish.	rm	2.00		0.00
28	Removing the existing BM table 6'x3' including side units carefully and refixing the same at new locations as per drawing including making necessary repairs to drawers, locks, key board channels and removing the laminates and fixing the all exposed surface with 3mm MDF board and finished with 1mm thick laminate of approved colour and teak wood lipping on edges duly polished etc complete	no	1.00		0.00
29	Removing the existing officerrrs table with side units carefully and refixing the same at new locations as per drawing including making necessary repairs to drawers, locks, key board channels and removing the laminates and fixing the all exposed surface with 3mm MDF board and finished with 1mm thick laminate of approved colour and teak wood lipping on edges duly polished etc complete	no	1.00		0.00
30	Repair to doors of aluminium, flush doors as per site conditions while laying floor tiles which includes removal of doors and shortend the height by cutting the members and providing and fixing additional members etc complete and re fixing the doors with hinges, and other accessories to make the door good	no	7.00		0.00

31	Providing and fixing low height partition glazed partition made with aluminum hollow box section of 50mmx25mmx 1.2mm wall thickness fixed with each sides of 6mm thick BWR grade ply and finished with 1mm thickness laminate of approved shade (with colour and shade as approved by engineer in charge/ architect (solid/ teak wood / texture premium quality). The partition shall be fixed to floors and walls with screws rigidly. 8mm thick glass shall be provided at 3' level duly supported by teak wood lipping polished and as directed at site by engineer in charge.	sqm	4.00		0.00
32	Full height partition: Providing and fixing solid and glazed partition made with aluminum hollow box section of 50mmx25mmx 1.20mm duly fixed with each sides of 6mm thick BWR grade ply and finished with 1mm thickness laminate of approved shade (with colour and shade as approved by engineer in charge/ architect (solid/ teak wood / texture premium quality). The glass panel shall be 8mm thick duly supported by teak wood lipping PU polished.	sqm	30.00		0.00
33	Full ht partition with cement board Full height Partition : Providing and fixing partition made with aluminum hollow box section of 50mmx50mmx with wall thickness of 1.0mm duly fixed with each sides of 6mm thick cement board of everest make exterior grade. The surface shall be finished with 2mm thickness putty, primer and white paint as approved by engineer in charge/ architect	sqm	0.00		0.00
34	Repairing the partition of SWO counter including removing laminates, 12mm glass including clips. Teak wood lipping if any to make it surface preparation for fixing the mdf board and providing and fixing 3mm MDF board Exterior grade on all exposed surface duly finished with 1mm thickness laminates of approved shade and colour including re fixing the glass panels.	sqm	25.00		0.00
35	Wall panelling with MDF board: Providing and fixing 19mm BWP grade Block board and finished with 3mm thick MDF board of exterior grade of century/ green/ action tesa/ marino finished with 1mm thick laminate. This shall be provided in all window opening all around	sqm	0.00		0.00
36	SWO Counter with white laminate (UNICORE of green lam/ marino) top and blue laminate in modesty panel: Providing and fixing 6mm flexible ply on existing SWO counter of 900 wide table top, sides and front modesty panel including side units. The table top and half of modest panel shall be finished with 6mm thickness flexible ply and 1mm thick unicolor off white/ white as approved laminate. Front modest panel shall be finished with curved edge. Balance ht of front fascia shall be finished with 1mm thick blue laminate of Century/green/ marino premium quality. A provision of lighting system shall be provided in front fascia in the offset provided in between laminate and corian surface. 12mm ply shall be provided on front facias with support at table edge top and at 15" level to which laminate shall be finished. All other exposed surfaces shall be finished with frosty laminate and inside surface of table shall be polished. 1mm thick UNICORE laminate shall be provided on table top, sides and side units.	mo	7.00		0.00
37	Storage units 450mm deep: Providing and fixing 450mm deep (Inside clearance) made with 19mm block board on all four sides and 6mm backing ply. Vertical separators shall be provided at each 3' Centers with leaf of each shutter is 18" wide. Ebco/ hettich make auto closing hinges shall be provided. All inside surface shall be finished with white laminates. Exposed surface of shutter shall be finished with wood shade laminate of approved shade and top surface shall be finished with frosty white laminate unicolor of 1mm thickness.	sqm	5.00		0.00
38	Exterior painting matching with existing colour including priming the surface with wall primer of one or more coats and finished with two or more coats of weather shield apex paint of Asian/ berger as approved by eic including scaffolding etc complete.	sqm	300.00		0.00
39	Synthetic enamel painting including applying one or more coats of primer on steel surface and wood primer on wooden surface and finished with two or more coats of synthetic enamel paint of approved colour and shade	sqm	100.00		0.00
40	P&F exterior putty on all uneven surfaces to make the surface in level	sqm	200.00		0.00
41	Cleaning the existing laminates, floors, toilets with chemicals and other places of the branch as directed by Branch / engineer etc to the satisfaction of branch	job	1.00		0.00
42	Labour charge for shifting the heavy weight almirahs, fire cabinets to an desired locations on same floors and repositioning the same as per direction of Branch	job	1.00		0.00
43	P&F 19mm block board MR grade (Century/ Green/ kitply at counter top, side units including cutting and fixing the same as per existing set up so that height shall be maintained after fixing the floor tiles in floors. This item is a provisional item and will be executed after discussion with BM and staff.	sqm	30.00		0.00
44	Providing and fixing godrej night latch for two doors	no	2.00		0.00
	Total excluding GST			TOTAL	0.00

	<p>Recommended Materials:</p> <ol style="list-style-type: none">1. Ply / Block board: Century / Marino / Green BWP grade,2. Laminate: Century/ Marino/ Green (Unicore, texture, solid, wood shade, glossy etc as approved),3. MDF Board: Century/ Marino/ Green/ Action tesa4. hardwares: Godrej/ ebco/hettich5. Glas: Modi/TATA. Saingobain, (6). Upvc: Prominace/ fenesta/ rehau as approved, (7): Flush door: Century/ Sylvam, Green, Duro, (8): veneer: duro/ or equiv as approved6. Painting: Asian / Berger / ICI Dulux
--	--