Renovation of SME Paltan Bazar Branch, Guwahati BOQ for Electrical Installation Works

SI.No.	Description	UOM	Qty.	Rate (Rs.) (Exclusive of GST on work contract)	Amount (Rs.) (Exclusive of GST on work contract)
1	Sub-main line:-				
	Wiring in MS conduit of IS specification of Proper				
	size with core PVC insulated stranded copper wire				
	11KV grade (Finolex/Havells/Polycab/ RR Kabel/				
	Richa/KEI or equivalent) and with supply ,installation,				
	commissioning of all the materials required including				
	proper termination, connection in complete as				
	required from main DB to various DBs:-				
i)	with 3nos 4sq.mm (1ECC)	RM	30		
ii)	with 3nos 6 sq.mm (1ECC)	RM	60		
2	Supplying, installing and commissioning of PVC				
	Armored cable complete with proper cable glands				
	and two nos. of 8SWG GI wire (Havell's/Richa/RR				
	kebel/KEI or equivalent) alongwith all the other				
	materials required including proper connection in				
	complete as required from main Panel, Power				
	Distribution Board to various DBs .				
i)	With 3.5 core x 25 sq. mm cable	RM	40		

Sl.No.	Description	UOM	Qty.	Rate (Rs.) (Exclusive of GST on work contract)	Amount (Rs.) (Exclusive of GST on work contract)
3	Computer/Raw Power point wiring in MS conduit of				
	IS specification of proper size with 3nos 2.5sq.mm				
	single core PVC insulated stranded copper wire 1.1KV				
	grade(Finolex/Havells/Polycab/ RR Kabel/ Richa/KEI				
	or equivalent) and with all material supply				
	installation and commissioning complete from				
	CDB/PDB(Raw) .The wiring shall be carried out on				
	surface above false ceiling by chiseling the existing				
	surface and plastering the same with cement etc.				
	after fixing the MS conduit with all accessories like				
	saddles screws, bends T-joint etc. 2 coats of painting				
	Matching to the surface including supply installing,				
	testing, commissioning of modular plate type switch				
	and socket (Legrands / MK or equivalent) for				
	computer terminal on sheet steel enclosure				
	(cadmium plated),duly fitted with screw to the steel				
	conduit and fixed to the wall partition furniture with				
	all interconnection and proper earthing .All the				
	opening shall be covered with blank plate and be				
	sealed to make the box vermin proof.B48(maximum				
	three points in single circuit)				
i)	With 3nos 6A socket with single 16A switch.	No.s	10		
ii)	With 2nos 16A socket with individual switch.	No.s	5		
	Complex tradellation tradition and committee of				
4	Supply ,installation ,testing and commissioning of				
	distribution board manufactures made sheet steel				
	enclosure With the following MCBs (DB, MCB and				
	MCCB Make - Legrands/ Havells/L&T/SIEMENS or				
	equivalent) and connecting the same to the system.				
	DB with 25 A DP RCCB, 30mA for AC VTPN Double Door Distribution Board with 100A 4	No.s	3		
"'	Pole MCCB (36kA) as incomer and 4 Nos. 32A SP				
	MCB's at outgoing	Set	1		
			_		
5	Supply installation testing and commissioning of LED				
	batten Single Tube light fittings with 17W with glare				
	free light distribution wall mounted at ceiling/false				
	ceiling level/. Make :-				
	Bajaj/Havels/Phillips/Wipro/Crompton or equivalent	Nos	4		

SI.No.	Description	иом	Qty.	Rate (Rs.) (Exclusive of GST on work contract)	Amount (Rs.) (Exclusive of GST on work contract)
6	Supply, installation testing and commissioning of recessed type LED luminaire with complete PMMA Difuser with 35W LED lamp (size 2"X 2"). Make :- Bajaj/Havels/Phillips/Wipro/Crompton or equivalent		34		
7	Supply and installation of Wall Mounted fan 400 mm Metallic body and metallic Blade ,1400 rpm Havels / Crompton/bajaj/usha/orient make		16		
8	Supply and installation of 5 Meter roll 55W, IP20 Flexible LED Strip surface mounted alongwith required LED Driver as back lighting. Havells or equivalent make. Wall Mounted fan 400 mm Metallic body and metallic Blade, 1400 rpm Havels / Crompton/baiai/usha/orient make		34		
	Wiring for light/fan/exhaust fan points using 3 X 1.5 1.1 kV grade PVC insulated stranded copper conductor wire(Finolex/Havell's/Richa/RR kebel/KEI or equivalent) for phase, neutral and earth in 25 mm dia heavy duty MS conduit along with associated accessories like MS junction boxes, bends, saddles, screws et. concealed in wall, floor, under flooring, below false ceiling or on surface as well as suspended from ceiling with 25mm X 3 mm MS flat suspenders duly painted above false ceiling from individual light/Fan/Exhaust Fan point outlet. etc. to individual modular type switch boards, 10 Amp modular plate type switches etc.(MK/Legrands/Havel's or equivalent), as required complete including circuit wiring with 3 X 2.5 sqmm. 1.1 kV grade PVC insulated stranded copper conductor wire and as per site requirement and as instructed by SBIIMS Engineer.				
i)	one light/fan controlled by one switch GST on work contract will be extra as applicable.	No.s	35	Grand Total	

SBIIMS, Guwahati Circle