

EXPANSION OF RBO I KOZHIKODE TO FUTURE EXPANSION AREA
(EXSTING BRANCH PREMISES)

Name & address of Contractor					
SCHEDULE OF WORKS					
SI No	Description of work	Qty	Unit	Rate(INR)	
1	Providing and fixing work station with cubical table of size 1500mmx1500mm to detail as per the drawing and table top of 18mm commercial ply with stiffners, finished with 1 mm thick laminate of approved make and shade and beach moulding to shape along the edges. Foot rest cum CPU stand of required length with same 18 mm. MS Powder coated Keyboard tray and 50mm Dia MS wire manager of approved quality . One set of 3 drawers with 18 mm marine ply of approved make at bottom, sides and rear with necessary edge bands, telescopic drawer slides, locking arrangement, 100 mm long brush finish S.S. handles, etc. complete.	4	Nos		
2	Supplying and fixing side tables with 19mm marine plywood finished with 1mm decorative laminate over it on all exposed faces, 25mm thick marine ply with 1 mm thick laminate on top having underside covered with balancing laminate and 3 mm pvc edge banding on all exposed edges as per the <u>sketch</u> enclosed. Side hung shutter in both the panels using 18 mm Plywood and finished with 1mm laminate of approved color and shade, including all necessary TW lipping, Box Type hinges, Locking arrangement, 100 mm long S.S brush finish handles, tower bolt, ball catch etc.,.complete. 12 mm glass with edges polished to be provided for the table top The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.				
(ii)	100 x 40 x 75cm ht.	2	Each		

3	Supplying and installing double skin wooden partitions 120cm height around the clerical counters with 63.5x38.1x1.2 mm thick hollow Aluminium Sections of make Indal/Jindal for horizontals at floor level and 75cm ht. and verticals @ 75 cm c/c and 8 mm marine ply on both sides finished with 1mm laminate and with as per the <u>sketch</u> enclosed including providing necessary doors 40mm thick with Godrej night latch fixed at 45 cm ht. from floor level, tower bolts, etc. as per the layout plan. Between 750 mm and 120mm level, 12 mm thick glass with etching pattern (permanent) fixed with necessary D brackets of make Dorma or equivalent of SS finish. The glass opening 'Jamp' portion is to be finished with beachwood beading	18	Sq.M		
4	Supplying and fixing low level storage units made of 12 mm marine plywood finished with 1mm decorative laminate over it on all exposed faces, top with 18mm thick marine ply with 1 mm laminate and edgeband in all exposed edges including providing one shelf, necessary locks, handles, etc. as per the <u>sketch</u> enclosed. All the exposed edges of plywood are to be finished with 2 mm thick PVC edge band and all the inside portion finished with primer and 2 coats of enamel paint. One shelf to have minimum 40 cm height. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.				
(i)	units 75cm height and 45 cm wide	5.2	RM		
5	Supplying and fixing heavy duty hydraulic floor spring for entrance doors. (Dorma, Ebco, Hardwyn or approved equivalent with ISI mark) . The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	1	Each		

6	Supplying and fixing hydraulic door closers on doors. (Ebco, Dyna, Godrej or approved equivalent with ISI mark) . The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	1	Each		
7	Painting over the walls with one coats of plastic emulsion paint of approved make and shade with one coat primer after rubbing and finishing the surface. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	40	SqM		
8	Supplying Officer tables as per the <u>sketch</u> enclosed with 18 mm thick marine ply table top laminated with 1 mm thick laminate of approved make as in item no.1 Foot rest cum CPU stand of required length with same 18 mm. MS Powder coated Keyboard tray and 50mm Dia MS wire manager of approved quality . One set of 3 drawers with 18 mm marine ply of approved make at bottom, sides and rear with necessary edge bands, telescopic drawer slides, locking arrangement, 100 mm long brush finish S.S. handles, etc. complete.				
	All concealed faces of marine ply finished with two coat of enamel paint and exposed faces with 3 mm thick PVC edge band to the satisfaction of the Bank. The inside faces of drawer should be waxed and finished with varnish of app color and shade. the table modesty shall be fixed with 8mm thick of Aqua blue shade of saint Gobain (or) equivalent toughened glass panel fixed on the 18mm thick front vertical marine plywood and finished with 1mm thickness laminate. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.				
i)	180 x 90 x 75cm ht.	1	Nos		
ii)	160 x75 x 75cm ht.	1	Nos		

9	Double Skin solid Partition :-Providing and fixing Double skin solid partition . The frame work is with hollow Aluminium sections of size 63.5mmx38.1mmx1.2mm of make Indal/Jindal @ 60 cm c/c both vertically and horizontally, finished with 8mm marine ply (IS 303)and 1 mm laminate of approved make on both side. Above 270 cm the partition are to be firmly fixed to the ceiling . The partition upto false ceiling only be measured. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	25	SqM		
10	Toughened glass door: _Providing and fixing Toughened glass door with handle for the Entrance/ Bms Cabin with 12mm toughened glass and patch fittings. Necessary etching pattern to be provided. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge. (Floor Spring provided as separate item)	2.3	SqM		
11	Dismantling the existing wooden partition and low height storage and finishing the edges with necessary laminate and beach wood beeding for providing an entrance(toughened glass door) to the proposed premises without causing any inconvenience or damages for functioning of the office as directed by Engineer in charge. Rate includes of all cost and conveyance of materials required for proposed work.	1	LS		
	Total				
	GST @ %				
Total amount					

Amount in words: