

Tender Schedule : Proposed Interior works at our Kanigiri Branch, Prakasam Dist.

S.No	Item. / Particulars	Qty	Unit	Rate	Amount
1	Full height partitions:				
	Providing and fixing partitions with following specifications:				
	(a) Supporting system comprising of gypsteel / boral make 51mm X 35mm metal studs of 0.55mm thick at 600mm c/c and 51mm x 32mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical number stud touch with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings.				
	(b) 9 mm bwr grade ply with 1mm laminate on both sides up to 900mm level as per drawing.				
	(c) 5mm thick clear float glass with etching as per design between 900mm to 2100 mm level in specified areas as per drawing fixed with 100mm x 15mm beech wood jamb and 12mm x 12mm beech wood beading.				
	(d) 9 mm bwr grade ply and 1mm laminate between 2100mm to top of partition as per drawing.				
	(e). All beech wood members to have melamine spray polish finish	110	sqm		
2	Doors in partition				

	<p>Providing and fixing 30mm thick solid core flush shutter with 100mm x 25mm beech wood jamb around and 12mm x12mm button beading fixed with 1mm laminate on both sides and 8mm clear float glass with etching fixed as per drawing with 50mm x 18mm beech wood jamb around glass opening and 12mm x 12mm beech wood beading for fixing of glass on both sides, including necessary hardware viz, everite door closer, door stopper, door silencer, dorset mortise lock &amp; handles, hinges (all of approved make and quality), melamine spray polish finish for all beech wood members, etc., complete as directed.</p>				
		17	sqm		
3	Half height partitions				
	Providing and fixing half height partition with following specifications:				
	(a) Supporting system comprising of gypsteel/boral make 51mm x 35mm metal studs of 0.55mm thickness at 600 mm c/c and 51mm c 32mm metal tracks at floor, middle and 1220 level with joints staggered to avoid through joints. The rate should also include necessary strengthening with studs / tracks or channels at openings.				
	(b) 9 mm bwr grade ply with 1mm laminate on both sides as per drawings. Wicket gate is to be provided with godrej night latch, handles etc.				
	(c) All beech wood members to have melamine spray polish finish				

	d) 12mm thick clear float glass with etching as per shape and design shown in drawing in specified areas along with 50x15mm beech wood capping				
	e) The total height of the partition including glass with etching is 1500 mm. Partitions behind SWO shall be with doors & providing night latch to them				
		35	sqm		
4	Wall & column panelling :				
	Providing and fixing wall panelling with following specifications:				
	(a) Supporting system comprising of gypsteel / boral make 51mm x 35mm metal studs of 0.55mm thick at 600mm c/c and 51mm x 32mm metal tracks at floor, middle door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom.				
	(b) 9 mm bwr grade ply with 1mm laminate is to be fixed on one side upto bottom of false ceiling. Grooves are to be provided while fixing the laminate as directed by bank / architect.	4	sqm		
5	False ceiling				

	<p>Providing and fixing in true horizontal level false ceiling grid system with suspension system shall of Trulok Silhouette revealed profile grid systems with 15mm wide flanges incorporating a 3mm or 6mm central recess color, black or white revealed. Silhouette main runners and cross tees to have mitred ends with " birds mouth" notches to provide mitred cruciform junctions. Main runners to be spaced at 120mm c/c fixed by using 2mm pre-straightened GI wire.</p>				
	<p>Main tee, rotary stitched of size 15mm x 44mm x3600mm at every 1200mm c/c ,maximum and 1200mm cross tee of size 15mm x 44mm x1200mm at every 600mm c/c maximum and 600mm cross tee of size 15mm x 44mm x600mm at every 1200mm c/c maximum and 19mm x 19mm x 3000mm wall angle around the wall to form grid size of 600mm x 600mm and suspending the grid using 2mm pre-straightened GI wire and 6mm nylon rawl plug at every 1200mm intervals at the main tee and laying of venus three of daiken ceiling systems of size 600mm x 600mm x 15mm over the formed grid etc., complete as directed.</p>				
		285	Sqm		
6	<p>Officer table with side table – (1830mmx900mmx750mm + 1200mmx450mmx 750mm)</p>				
	<p>Providing, making and placing in position Executive Table and Side Table with following specifications and dimensions given above.</p>				

	(a) Tabletops made in 25mm particle board with post forming with edge rounding is to be provided.				
	(b) All other members 19mm bwr grade ply with 1mm laminate on both sides.				
	(c) One drawer unit with 3 nos drawers with necessary hardware viz., sleek telescopic drawer channels, handles, locks etc.,				
	(d) One ready made CPU stand of approved make with castors.				
	(e) One Moulded Key Board Tray with channels etc.,				
	(f) One Side Table with 19mm bwr ply with 1mm laminate on both sides for other member and shutters made with, except table top 25mm particle board post formed round edges with necessary hardware viz., cabinet hinges, handles, locks, tower bolts, etc.				
	(g) Footrest with proper support is to be provided.				
		2.00	each		
7	Officer table with side table - (1550mm X 900mm X 750mm + 1200mm X 450mm X 750mm)				
	Providing, making and placing in position officers Table and Side Table with following specifications and dimensions given above.				
	(a) Tabletops made in 25mm particle board post formed pre laminated with edge rounding is to be provided.				

	(b) All other members 19mm bwr ply with 1mm lamination to be used.				
	(c) One drawer unit with 3 Nos. drawers with necessary hardware viz., sleek telescopic drawer channels, handles, locks etc.,				
	(d) One ready made CPU stand of approved make with castors.				
	(e) One Moulded Key Board Tray with channels etc.,				
	(f) One Side Table with shutters made with 25mm particle board post formed round edge top and 19mm bwr ply with 1mm lamination on both sides for other members with necessary hardware viz., cabinet hinges, handles, locks, tower bolts, etc.				
	(g) Footrest with proper support is to be provided.	2.00	each		
8	Officer table with side table - (2430mm X 900mm X 750mm + 1200mm X 450mm X 750mm)				
	The specifications same as item No:7 except the size and shape. The table should be made in a semi circular shape with two 19mm ply a for tops and rest as per the item No: 7				
		1.00	each		
9	Running Table for Systems:				
	Providing & Fixing table of size 750mm deep x 750mm height ( 2'-6" deep, 2'-6" high) and in running length forming as shown in the drawing and comprising of the following:				

	All members of the table are to be made of 19mm bwr ply with 1mm lamination. Except 25mm particle board post formed with edge rounding for table top.				
	The drawer box shall have a drawer made out of 19mm bwr ply with 1mm lamination and a cup-board with middle shelf and a shutter made out of 19mm bwr ply with 1mm lamination. The draw is to be provided with sleek telescopic drawer sliding channels.				
	The shutter shall be fixed with concealed Earl behari hinges, lock, handles, etc. as approved by Architect or bank				
	Moulded metal Key Board Trays with channels, CPU ready made stands, wire managers etc. are to be provided.				
		3.00	RM		
10	Low height storage units				
	Providing and fixing 450mm deep and 900mm high (or as per site conditions) low height storage units. The basic structure including bottom, sides, shelves and shutters shall be made out of 18mm bwr ply except the top which shall be made of 25mm post formed round edge top. All exposed edges of the ply shall be covered and finished with 1mm laminate. All the exposed sides, top and the shutters shall be finished with 1.00mm laminate of approved colour duly fixed with fevicol.				

	All exposed bwr ply edges are to be provided with teakwood/beech wood lipping polished as directed. The backing shall be 12mm bwr ply. Two middle shelves made out of 18mm bwr ply shall be fixed at height as directed by the Consultant. The shutters shall be fixed with brass hinges, a 'Godrej' multipurpose cupboard lock, 4"size tower bolts and handles etc. as approved by the consultant. All internal portions of the storage rack to be finished with synthetic enamel paint of approved shade and two coats over a coat of wood primer & putty finish. Skirting to be fixed at the bottom of the rack with 1.00mm laminate as shown in the drawing.				
		24.0	Sqm		
11	Providing,making and fixing in position Writing Desk of overall dimensions 600mm x 400mm made in 18mm ply with 1mm laminate for top and 18mm plywood with 1mm laminate for other members. All the edges of 18mm plywood to have 18mm x 6mm beech wood edge lipping with melamine spray finish etc., completed as directed.	3.0	no.		
12	Single Window Unit				
	Providing and fixing in position Single window Unit to accommodate four staff counters and one passing officers counter with following specifications:				
	(a) 6 Nos Half height Partitions of 1220mm height and various lengths as per drawing same as item 2 above but top 300mm to have 12mm glass as directed by bank / architect, complete as per drawing. (Each length 2250mm)				



	<p>(b)4 Nos 1520mm x 1050mm tables for SWO &amp; 1 nos. 1650/1520mm x 1050mm table for officer &amp; 5 nos. 450mm x 1200mm side tables made with 19mm bwr grade ply finished with 1mm laminate on both sides for other members with following accessories. Table tops for table &amp; side table are to be provided with 25mm post forming as directed wherever necessary.</p>				
	<p>©5 nos drawer unit with 3nos drawers including all hardware viz, sleek telescopic drawer channels, handles,etc,. The rate should also include fixing of automatic drawer locks to all draws.</p>				
	<p>(d) 5 Nos Ready made CPU stand of ebco make are to be provided.</p>				
	<p>(e) 5 Nos Key Board tray made with 19mm ply with telescopic channels etc., complete.</p>				
	<p>(f) 5 Nos Side tables with shutter unit including necessary hardware viz., cabinet hinges, handles tower bolts, locks etc., complete.</p>				
	<p>(g) All table tops to have rounded edges as shown in the drawing.</p>				
	<p>(h) 12mm thick glass of 450mm high on top of table has to be fixed with necessary beadings and brass brackets as shown in drawing.</p>				
	<p>1) For Officer table</p>	<p>1</p>	<p>Each</p>		
	<p>2) For SWO tables</p>	<p>4</p>	<p>each</p>		

	Note: Rate has to be quoted for SW tables only. The partition rate will be paid under half height partitions				
13	Dismantling of the brick masonry wall/ RCC/ vitrified tiles at the site and disposal of the debris to a distance of 2 KM including cost and conveyance of all labour and materials, incidental and operational charges, VAT, hire charges of T & P etc., complete for finished item of work as directed by the Engineer-in-Charge. The cutting of flooring has to be done carefully with cutters so as not to damage the tiles beyond required width of excavation.				
		2	Cum		
14	<b>Brick masonry for walls in superstructure with CM (1:6)</b> prop: (1cement : 6 sand) using second class bricks from approved source having minimum crushing strength of 40 Kg/Sqcm. including cost and conveyance of all materials like cement, sand, bricks, water etc., to site, including seigniorage charges, sales & other taxes on all materials and such as labour charges, like mixing cement mortar, scaffolding charges, constructing masonry, lift charges, curing, VAT etc., complete for finished item of work.				
		1	Cum		

15	<p><b>Plastering 15mm thick in two coats for internal faces of new walls</b> with base coat of 9mm thick in CM(1:6) and top coat of 3mm thick in CM(1:4) with dubara sponge finishing including cost and conveyance of all materials like cement, sand, water etc., to site, including seigniorage charges, sales &amp; other taxes on all materials, and all operational, incidental charges on materials and including cost of all labour charges for mixing mortar, finishing, scaffolding, lift charges, curing, VAT including cutting Grooves as directed by Engineer-in-charge etc., complete for finished item of work</p>				
		10	Sqm		

16	<p><b>Flooring with edge cut vitrified tiles</b> of premium quality of approved colour and shade by Engineer-in-charge of size <b>600 mm x 600 mm , 8mm to 10mm thick</b> , with design as per the approved flooring pattern as directed by the Engineer-In -Charge set over a base coat of CM (1:4) prop. 12mm thick over CC bed already laid including neat cement slurry of honey like consistency spread at the rate of 3.3 kgs per Sqm. and filling the joints with white cement paste mixed with pigment of matching shade including cost and conveyance of all materials like cement, sand, water, ceramic tiles, white cement etc., to site, including cost of seigniorage charges, VAT on all materials, cost of base coat and all labour charges for mixing of cement mortar, laying tiles to required slope as directed &amp; curing etc., complete for finished item of work. <b>The cost of stone should not be less than Rs65.00 per sft</b></p>				

	Preparing the surface, cleaning the existing internal walls with wire brush, Providing and applying two coats of Plastic emulsion paint of asian paints of approved colour and quality over and including a coat of primer including preparation of surface ( existing paint and wall surface is to be scrapped and removed before applying birla wall care putty) with birla wall care putty etc. complete for internal walls as directed by bank / architect. All cuttings done in the walls for electrical cables are to be closed before preparation of surface.				
		285	Sqm		
17	Plastic emulsion paint				
	Preparing the surface, cleaning the existing internal walls with wire brush, Providing and applying two coats of Plastic emulsion paint of asian paints of approved colour and quality over and including a coat of primer including preparation of surface ( existing paint and wall surface is to be scrapped and removed before applying birla wall care putty) with birla wall care putty etc. complete for internal walls as directed by bank / architect. All cuttings done in the walls for electrical cables are to be closed before preparation of surface.				
		480.0	Sqm		
18	Texture paint				

	Preparing the surface, cleaning the existing internal walls with wire brush, Providing and applying two coats of Texture paint of asian paints of approved colour and quality over and including a coat of primer including preparation of surface ( existing paint and wall surface is to be scrapped and removed before applying birla wall care putty) with birla wall care putty etc. complete for internal walls as directed by bank / architect. The rate is also inclusive multi colour gun spray painting of same quality as directed by the Engineer. All cuttings done in the walls for electrical cables are to be closed before preparation of surface.				
		80.0	Sqm		
19	Supply,cleaning all surfaces,of dust & dirt,sand papering and applying ready mixed synthetic enamel paint of approved shade of Asian make over a coat of Zinc chromate primer with metal paste(putty) for surfaces of doors,windows,ventilators,grills and all type of iron work including cost of all material,labour,scaffolding and other charges etc.complete for ground and first floors				
		50.00	Sqm		
20	Vertical blinds				

	Supplying and fixing of vertical blinds of local make of approved range with louver made of polyester base fabric of width 100mm. The louvers are to be treated with Scotch guard The vertical blinds should be provided with head channel, end control unit, tilt rod, tiller chain, carrier, spacer, bottom mechanism, cord, cord weight, installation bracket etc. complete as per company specification as approved by Architect/Bank.				
		30.00	Sqm		
21	Total Amount				

List of Materials to be used in the Interior works subject to the approval of samples by the Bank's Engineer.

S. No	Material	Brand of Manufacturer
1	BWR Ply wood confirming IS 303 grade	Green ply/ Blue apple/ Archid ply
2	Laminate confirming to IS : 2045 -1995	Formica/ Green lam / Heritage
3	Glass	Modi float/ Saint gobain
4	Hard ware	Efficient gadget/ Earl behari/ (EBCO) Hardwin/ Etalica
5	Flush door confirming to IS 2202 part 1 - 1991.	Green ply/ true wood/ Kit ply
6	GI support system for false ceiling	Rondo/ Indian gypsum/ Boral
7	GI dry wall partition system	Rondo/ Indian gypsum/ Boral
8	Plaster boards	Rondo/ Indian gypsum/ Boral
9	Screws	GKW nettle fold or approved equivalent
10	Adhesives	Fevicol, Movicol
11	Paint	Asian/ Nerolac
12	Floor spring/ door closure except for toughened glass	Everite/ EBCO

13	Vitrified flooring	Asian/ Kaneria/ Johnson/ jet granite
14	Venation blinds	MAC/ Vista
15	False ceiling	Armstrong/ Daiken
16	Hinges	Clip on hinge of nickel chrome plated finish of ebco make
17	Handles	Brass/ gold finish of dorset/ godrej
18	Cement	K.C.P/RASI/L&T

**GENERAL AND TECHNICAL CONDITIONS:**

1. The contractor shall use only the above mentioned materials. All other materials shall confirm to the specifications laid down. The tenderer shall take this into account while quoting the rates.
2. The contractor shall visit the site before quoting. No claim will be entertained on this later.
3. No material should be used / stacked in the site other than the specified after obtaining approval from Consultant / Bank's Engineer.
4. IT, VAT , will be deducted as applicable.
5. The rates quoted shall be inclusive of cost of all materials, labour, taxes, levies/octroi, transportation, wastage etc.
6. Tender without EMD will be rejected. Security Deposit at 8% will be deducted from each running bill subject to a maximum of 5% of work value including EMD. 50% of the total security deposit will be released on virtual completion and balance 50% on satisfactory completion of defect liability period of 6 months.
7. Necessary contractors all risk insurance policy should be taken before commencement of work
8. The work has to be completed within 45 days time from the date of handing over the site.
9. The work has to be carried out after office hours only and the work shall be carried in such a way that no inconvenience is caused to the customers of the branch. Working area should be kept neatly by contractors every day.
10. Liquidated damages @0.5% per week subject to a maximum of 5% will applied for delay in completion of work.
11. The work should be started with immediately from issue of work order/Bank's instructions. Contractors representative should be present in site during the execution of work.
12. Rates should include cost of material, labour, curing, necessary scaffoldings, shifting the furniture and keeping them back, cleaning the floor, disposing of the debris at the specified place etc.

Place :

Signature

Date :

(Name and Address of the

Contractor with Seal)