

SCHEDULE OF FINAL BILL OF QUANTITIES, S V COLON BRANCH, SAROOR NAGAR, HDERABAD					
S. No	Item/Particulars.	Unit	Rate/Unit	Quantity	Amount (Rs.)
1.1	FULL HEIGHT PARTITIONS:				
1.1.1	FULL HEIGHT PARTITIONS: (WITH GLASS)				
	Providing and fixing metal stud dry wall partition with : (a) Supporting system comprising of Frame Work/ Rondo/ Boral make 51mm x 35mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tacks or channels at doors and other openings. (b) 9mm plywood fixed on both sides with 25mm dry wall screws for the entire height of the partition and 1mm Laminate on all sides. c) All beech wood members to have melamine spray polish finish. as per drawings and directions etc., complete and the following: (a) 8mm thick clear float glass with etching / 3M film for privacy in strips from 900 mm to 2100 mm level as shown in drawing fixed with 80mm x 15mm beech wood jamb and 12 mm x 12mm beech wood beading on both sides. (b) All beech wood members to have melamine spray polish finish. (c) The cost to include all hardware required along with 3M privacy film to be pasted as per design and drawing. The size of each glass will be as per site conditions. The rate is ;for a finished item of work etc., complete as directed.	Sft		245.00	
1.1.1.3	LOW HEIGHT PARTITIONS - BOTH SIDES LAMINATE:				
	Same as item 1.1.1 above, up to the height of 1370mm from finished floor level, to a neat finish as per drawings and directions etc., complete and the following: (a) 80 mm x 15 mm beech wood capping on top of the partition on all the exposed sides. (b) All beech wood members to have melamine spray polish finish to give high glazing. c) The partition to be embed with 12mm thick clear toughened glass up to the height of 450mm with high polished edge finish with aqua blue of Saint Gobin Glass. d) The cost to include all hardware required etc., as per site conditions.	Sft		298.00	
1.3	MAIN DOOR:				
	Providing, making and fixing in position Main Door made of 12mm toughened glass of approximate overall size 2700mm x 2700mm with following specification etc., complete as directed. (There are two openings of the above mentioned size on either sides of the office area on First Floor.)(a) Entrance door (2 Nos.) - Providing, fixing in position Single dorma Patch fitting glazed entrance Double door (Size: 1600mm x 2100mm) using 12mm toughened glass edge polished. The Door to consist of floor spring (BTS 75V) , Upper patch (SM 1020A), Bottom patch(SM 1010), Lock Keeper Plate (SM 1052E), Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm (TG9357 EQ-S), corner Lock (SM 1049E) etc., complete as per drawing.(b) There will be tow doors on either sides having two openable shutters on either sides. The above listed hardware will be 4 Nos. of all mentioned types for the entire work.(c) The sides to have 12mm toughened glass fixed on Dorma Patch fittings.(d) Two 12mm toughened glasses to be fixed on either sides of the door of approximate size 7500mm x 2700mm using Dorma patch Fittings - Corner fittings (SM1090) at bottom and top with locking arrangement of approved make.(e) The top of the main door to have 12mm toughened glass of approximate size 1500mm x 600mm to be fixed using Dorma patch fitting - 2 Nos. Side Connectors (SM1092) at top and 2 Nos. Patch for Over panel / Side panel (SM 1040) between the top glass, side vertical glass and top of the main door. (as per site conditions)	Sft		35.00	

1.4 A	WALL PANELLING:				
	Providing and fixing metal stud Wall Paneling with following specifications:				
	a) Supporting system comprising of frame work / Rondo / Boral make 51mm x 35mm metal studs at 600mm c/c and 51mm x 32mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom.b) 9mm Plywood fixed with 25mm dry wall screws for the entire height of the paneling.c) Panelling to have 1mm Laminate approved make as specified level as shown in drawing.d) Providing 15mm thick jamb for door and window openings or suitable depth as per site conditions.e) All beech wood members to have melamine spray polish finish.	Sft		1,150.00	
1.4B	COLUMN PANELLING				
	Do as above	Sft		70.00	
1.5	FALSE CEILING:				
1.5.1	PLAIN FALSE CEILING:				
	Providing and fixing Concealed Grid suspended ceiling system of 12.5mm th., Gyp Board of Boral Plaster / Saint gobain boards fixed to Frame Work / Rondo / Saint gobain / Boral Metal System concealed grid key lock suspended ceiling system consisting of 5mm suspension rod, adjustable spring loaded suspension clip, top cross rail of 3000mm long of 0.55BMT and furring channel 4000mm long made or 0.5mm BMT the top cross rail to be suspended from ceiling at every 1200mm and furring channel to be fixed to top cross rail at every 600mm to make a grid of 1200 x 600mm All the above components are to be made of galvanized steel. The rate to include plastic Emulsion painting as per item 3.1 below for a neat finished work. Further the rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing or these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed.	Sft		1,085.00	
1.6	STORAGE UNITS:				
1.6.A	Storage Units – Laminate Finish: Providing, making and placing in position low height storage units upto 750 mm height or height as directed and 450 mm deep made with 18/19 mm plywood front sides and middle shelf and back side with 9 mm BWR ply covered with 1 mm laminate (dark for bands and light for body) at all exposed surfaces. The top shall have 25 mm mdf board 'post-formed' edge with pf lamination, Inner/unexposed surfaces to painted with two or more coats of enamel paint with putty finish including melamine polish finish for all wooden members. The rate to include cost of all necessary hardware viz., cabinets hinges, locks, handles, tower bolts etc. The unit should have beech wood beading 25 X 40 mm at top and edge lipping 20 X 6 mm complete.	Sft		115.00	
1.7	SERVER ROOM WORK TABLE:				
	Providing, making and placing in position worktables made in 19mm plywood / block board with beech wood edge lipping, 40mm x 40mm beech wood beading for table top and 75mm x 50mm hardwood foot rest, including key board tray and vertical supports at approximately every 1200mm length - the exposed faces to have 4mm th., teak veneer, the wooden members to have PU spray polish finish and the unexposed faces to have minimum three coats or enamel paint with putty etc., complete as directed. The table to have a three drawer unit for every 1200mm length as per drawing.				

2.0	LOOSE FURNITURE:				
2.1	SINGLE WINDOW TRANSACTION COUNTERS:				
	Providing, making and fixing in position Single Window Transaction Counters in Banking Hall with following specifications:				
	a) Each Counter having approximate size of table 1500mm x 900mm corian top table and 1 No. up-to size of 450mm x 1200mm side table with 12mm thick. Toughend for customer facia other specifications as per drawing and directions etc., complete. b) The unit is to be made with 19mm plywood for verticals clad with 1mm laminate from both sides as specified. c) All edges of plywood to have 20mm / 25mm x 6mm beech wood lipping unless stated otherwise. d) Each drawer unit with 3 Nos. drawers (With specified separators for different currency notes for top drawer) including all hardware viz., drawer channels, handles, etc., The rate should also include fixing of self locking system for first drawer and drawer locks for other drawers. e) Pre-fabricated metal CPU trolley and foot rest. f) Pre-fabricated metal ready made Key Board tray with channels etc., complete. g) Side table with one drawer unit unit and SD stationery unit including necessary hardware viz., cabinet hinges, handles, tower bolts, locks etc., complete. The unit is made with 19mm Plywood top and sides for other members with 6mm thick Dupont make acrylic solid surface or as specified by engg-in-charge as per drawing. h) The modesty panel of the counter to have a 19mm thk ply with 1mm Laminate as per the drawing etc., complete as directed.	Rft		22.00	
	i) All unexposed faces to have minimum two coats of synthetic enamel paint with putty finish or hand polish. j) All beech wood members and surface or laminate/veneer to have PU spray polish finish. k) All necessary hardware viz., drawer channels, handles, set locks etc.,				
2.2	INVESTMENT POINT COUNTER: GRAHAK/ MITRA				
	Providing, making and placing in position worktables made in 19mm plywood / block board with beech wood edge lipping, 40mm x 40mm beech wood beading for table top and 75mm x 50mm hardwood foot rest, including key board tray and vertical supports at approximately every 1200mm length - the exposed faces to have 4mm th., teak veneer, the wooden members to have PU spray polish finish and the unexposed faces to have minimum three coats or enamel paint with putty etc., complete as directed. The table to have a three drawer unit for every 1200mm length. The table shall have modesty panel with high gloss PU coating in combination of blue and white shade as per drawing/directed.	No		1.00	
2.3	TABLE FOR BRANCH HEAD:				
	Branch Head Corian Top table and with side table of approximate size – 1800mm x 900mm x 750mm + 1200mm x 450mm x 650mm with 4mm th., Teak Veneer of approved make/shade on all exposed faces with minimum three coats of PU spray polish to a finished item of work, as per item 2.1/drawings and directions etc., complete for a finished item of work, The cost also to include front 12mm clear float glass modesty panel finished item of work as per drawing and directions etc., complete the item with all standard hardware.	1 no		1.00	

2.4	OFFICER TABLES:				
	Providing, making and placing in position Officer's table and side table with above specifications and dimensions 1500 x 750 x 750 mm + 900 x 450 x 750 with one side drawer and one side 1 shelf and shutter as above and as per drawing or directed.	1 no		1.00	
3.0	OTHER WORKS:				
A	<u>Cheque Writing Table:-</u> Supplying & fixing cheque writing table as per drawing or as directed.	No		1.00	
B	<u>Roller Blinds:-</u> Supplying & fixing in position of Roller Blinds of "Vista" or "Touch".	Sft		200.00	
C	<u>Complaint/Suggestion box</u>	No		1.00	
D	<u>Rack for Brochures and Product information</u>	No		1.00	
E	Notice Board	No		1.00	
			TOTAL		

(Rupees

Onl)

Contractor's Signature with Seal

Date :