

STATE BANK OF INDIA					
BOQ FOR INTERIOR WORKS OF ASC CENTER BRANCH - PARTIAL RENOVATION					
SI No.	Item description	Unit	Qty	Rate	Amount
	INTERIOR WORKS				
1	FULL/HALF HEIGHT FULL/PARTLY GLAZED PARTITIONS:				
1.1	Providing & fixing partly Glazed partly panelled / full height partitions comprising of the following:				
1.2	Aluminium vertical members out of 2" x 2" size rigidly fixed at 2'0" centre to centre upto 3'0" height from floor level upto 7'0" level except in glass subject to sizes of glass as per site condition and rigidly fixed. Aluminium member to be minimum 1.2mm thick (16				
1.3	Aluminium horizontal members out of 2" x 2" size to be provided at 2'0" c/c from floor level to 3'0" and from 7'0" upto false ceiling level and at underside of beam/slab levels as per site conditions except in glass portion and rigidly fixed to vertical members. Aluminium member to be minimum 1.2mm thick (16 gauge).				
1.4	6mm BWR ply panels fixed on both sides on the above framework as per directions with groove & removable type panels at skirting and 2'6" levels for electrical / computer junction boxes.				
1.5	1mm thick laminate sheets fixed on visible surfaces at both sides as per directions. Basic rate is Rs.50 per sqft				
1.6	6 mm thick clear glass panels as per design fixed with all round wooden beadings out of 1-1/2" x 3/4" beading as per design (size of the glass panels will be subject to site				
1.7	T.W door frame out of 4" x 1 1/2" side, top and bottom & lock frame shall be out of 6" x 1 1/2" with bottom partition with 6mm commercial ply with 1mm thick laminate, top area will be glazed with 6mm thick glass with teak beading out of 1/2" x 3/4" .				
1.8	Door shutter forming integral part of the partition and fixed along with it to be made out of 30 mm solid core commercial flush shutter with both side fixed with 1mm thick laminate and 1-1/4"x 1/2" TW lipping all-round, including rebate as required and fixing of all fixtures fastenings, door closure, mortice lock, handle etc., as required. Basic rate is				
1.9	All wooden beadings to be well polished in approved shade with melamine spray finish.	Sft	50.00		
2	Providing and fixing 3'x7' 32mm thk BWP door with beech wood frame along with door closer, cylindrical lock, door stopper with all necessary hardware complete	Sft	21.00		
3	PANELLING over existing				
3.1	Providing and fixing 6mm BWR ply with laminate on columns/wall surface with adhesive, nails, screws, for levelling, etc. complete pasted with 1mm thk laminate with all grooves, adhesive, nails, screws, etc complete. Basic rate is Rs.50 per sqft	Sft	200.00		
4.1	Providing and fixing fully glazed 12mm thick Toughened glass partition at Entrance to hold approximately 600mm wide 2 panelled glass shutter fully glazed made out of 12mm thick clear glass to be etched design with necessary handles selected design with pivot arrangements complete etc.	Sft	42.00		
4.2	Providing and fixing fully glazed 12mm thick entrance Toughened glass door comprising of 6'0" x 7'0" glass shutter fully glazed made out of 12mm thick clear glass to be stickered with necessary handles selected design with locks, floor spring, pivot arrangements complete etc.	Sft	60.00		
5.1	Providing new UPS partition with Fibre cement board with painting complete fixed to aluminium section frame of 2"x2" at 2' spacing both ways with door including handle and locks (without door closer)	Sft	100.00		
5.2	Providing and fixing 6mm FCB with painting complete on inside surface of server room	Sft	320.00		
6	GYPSUM FALSE CEILING				
6.1	Supplying & fixing totally flush made to shape false ceiling with gypsum board out of the following material including finishing with joining compound, paper tape, one coat of primer and two coats of approved quality and shade plastic emulsion paint as per approved samples complete including preparing the framework, channels, etc.,				
6.2	12 mm thick gypboard fixed to metal frame				
6.3	All as per manufacturer's specification including all fixtures & fastenings complete.				

STATE BANK OF INDIA					
BOQ FOR INTERIOR WORKS OF ASC CENTER BRANCH - PARTIAL RENOVATION					
SI No.	Item description	Unit	Qty	Rate	Amount
6.4	NOTE: Rate to include making cutouts, providing additional framework and all necessary arrangement to fix recessed type light fixtures, cameras, spot lights smoke detectors etc.,	Sft	3100.00		
6.5	Providing and fixing 2'x2' Grid tile false ceiling with silhouette channels complete	Sft	800.00		
	REMOVING AND BUYBACK				
1	Removing and buyback for existing Alumium partition	Sft	200.00		
2	Removing and buyback of existing entrance door with partition	Sft	80.00		
3	Removing existing false ceiling and carting away from site	Sft	2500.00		
			Grand total		