

TENDER SCHEDULE FOR e-LOBBY AT CHITTINAGAR BRANCH

S.No.	Description of work	Unit	Qty.	Rate (Rs.)	Amount (Rs)
1	Supply and fixing 4 mm thick ACP panels for panelling to walls with 25mmx38mmx1.5mm thick aluminium sections for framing at 600mm intervals horizontally and vertically as per manufactures specification. The rate shall include cost of all material and labour etc. The panels should be pre-fabricated panel made out of light weight concrete core composed of Portland cement, binders siliceous and micaceous materials aggregate with tongue and groove arrangement with two 4mm thick fibre reinforced cement facing sheets. The grooves and joints in the panels should be filled with suitable fillers. The rate shall include cost of necessary fixing material like cleats etc.	Sqm	75		
2	Providing and fixing in true horizontal level false ceiling grid system with suspension system shall of Trulok Silhouette revealed profile grid systems with 15mm wide flanges incorporating a 3mm or 6mm central recess color, black or white revealed. Silhouette main runners and cross tees to have mitred ends with " birds mouth" notches to provide mitred cruciform junctions. Main runners to be spaced at 120mm c/c fixed by using 2mm pre-straightened GI wire.	Sqm	25		
	Main tee, rotary stitched of size 15mm x 44mm x3600mm at every 1200mm c/c , maximum and 1200mm cross tee of size 15mm x 44mm x1200mm at every 600mm c/c maximum and 600mm cross tee of size 15mm x 44mm x600mm at every 1200mm c/c maximum and 19mm x 19mm x 3000mm wall angle around the wall to form grid size of 600mm x 600mm and suspending the grid using 2mm pre-straightened GI wire and 6mm nylon rawl plug at every 1200mm intervals at the main tee and laying of venus three of daiken ceiling systems of size 600mm x 600mm x 15mm over the formed grid etc., complete as directed.				
3	TOUGHENED Glass (12mm thick) Partition with DOOR				

	<p>Providing & fixing 12mm toughened plain glass with single/double leaf Door with all necessary accessories to fix firmly to the floor, side walls, roof with patch fittings of Gogrej/e-zone or equivalent make as per the directions of the Bank's Engineer.</p> <p>Doors are to be fixed with Corner Fitting with Top Pivot, Top Patch, Bottom Patch fittings of Godrej/e-zone make. Door Hardware with SS finish locks , handles, Floor Spring as per sample approved by Bank.</p>				
A	PARTITION WITH 12MM TOUGHENED GLASS	Sqm	18		
B	DOORS IN THE TOUGHENED PARTITIONS	Sqm	5		
4	SHUTTER BOXING				
	<p>Providing and fixing shutter boxing with 19 mm thick plywood as an additional support to the glass fixing firmly from ceiling/walls with necessary brackets/frame work, in addition to the frame work of ACP in order to fix the toughened glass/doors. Measurement will be given only for the face of the glass contact area.</p>				
		sq.m	5		
5	BISON BOARD PARTITION				
	<p>Supply and fixing of Bison board of 8mm thick to the partitions and 4mm/6mm thick bison boards to the door ,inside the UPS room with necessary frame work & hinges and applying two coats of enamel paint over putty. Complete item as directed by the Bank's Engineer</p>				
		sq.m	12		
	Total amount excluding GST				
	Signature of the Contractor				