

PROPOSED INTERIORS FOR STATE BANK OF INDIA,

OLD BOWENPALLY BRANCH, HYDERABAD.

SCHEDULE OF QUANTITIES AND DETAILED SPECIFICATIONS.

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
I.	INTERIOR WORKS:				
1.0	FIXED FURNITURE:				
1.1	FULL HEIGHT PARTITIONS:	35		Sq.M.	
	Providing and fixing metal stud dry wall partition with following specifications:				
	(a) Supporting system comprising of 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs at 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings.				
	(b) 12mm HDF Board fixed on both sides with 25mm dry wall screws for the entire height of the partition.				
	(c) Partition from floor level upto 2350mm level to have 100mm bottomline expression skirting (aqua blue color) at bottom + from 100mm to 300mm level to have 1mm High Gloss Laminate (aqua blue color) + from 300mm level to 950mm level to have 1mm High Gloss Laminate (white color) + from 950mm level to 1100mm level 1mm High Gloss Laminate (aqua blue color) + from 1100mm level to 2250mm level to have 1mm Textured High Gloss Laminate (white color) + from 2250mm level to 2350mm level 1mm High Gloss Laminate (aqua blue color) on both sides as shown in drawing.				
	(d) Partition to have 8mm clear float glass fixed with 85mm x 15mm around jamb and 12mm x 12mm button beading on both sides of the glass, to a neat finish as per drawings and directions etc., complete.				
	(e) Partition above 2350mm level to have NO VOC or LOW VOC plastic emulsion paint finish on both sides as shown in drawing.				
	(f) All beech wood members to have minimum two coats of LOW VOC or NO VOC duco paint finish.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(g) All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
1.2	HALF HEIGHT PARTITIONS:	22		Sq.M.	
	Same as item 1.1 above, but for height of 1100mm from finished floor level, to a neat finish as per drawings and directions etc., complete and the following:				
	(a) 6mm thick acrylic solid surface capping of 75mm on top, 50mm bands of 6mm acrylic solid surface on both sides of the partitions horizontally and vertically upto skirting as per drawings and directions etc., complete.				
	(b) Partition from floor level upto 1100mm level on both sides to have 100mm bottomline expression skirting (aqua blue color) at bottom + from 100mm to 300mm level to have 1mm High Gloss Laminate (aqua blue color) + from 300mm level to 950mm level to have 1mm High Gloss Laminate (white color) + from 950mm level to 1050mm level 1mm High Gloss Laminate (aqua blue color) + from 1050mm level to 1100mm level to have 6mm thick acrylic solid surface on both sides as shown in drawing.				
	(c) The cost to include all materials and hardware required etc., as per site conditions. The rate is for a finished item of work etc., complete as directed.				
1.3	DOORS IN PARTITIONS:				
1.3.1	50MM DOORS IN PARTITIONS:	5		Sq.M.	
	Providing and fixing 50mm thick solid core flush shutter with 85mm x 15mm beech wood jamb around and 12mm x 12mm button beading fixed 1mm Laminate as specified on both sides and 8mm clear float glass with 3M privacy film fixed as per drawing with 65mm x 15mm beech wood jamb around the glass opening and 12mm x 12mm beech wood beading for fixing of glass on both sides.				
	The rate to include necessary hardware viz., door stopper, door buffer, pair of " H " type handles, Mortise Dead Lock and Euro Profile Cylinder - Key and Knob 70mm SS, SS 2 ball-bearing hinges - (127mm x 76mm x 2.5mm), concealed door closer (all of approved make and quality), ZERO VOC or NO VOC duco paint finish for all beech wood members, etc., complete as directed.				
1.3.1	35MM DOORS IN PARTITIONS:	2		Sq.M.	

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	Providing and fixing 35mm thick solid core flush shutter with 85mm x 15mm beech wood jamb alround and 12mm x 12mm button beading fixed 1mm Laminate as specified on both sides and 8mm clear float glass with 3M privacy film fixed as per drawing with 50mm x 15mm beech wood jamb around the glass opening and 12mm x 12mm beech wood beading for fixing of glass on both sides.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	The rate to include necessary hardware viz., door stopper, door buffer, pair of " H " type handles, Mortise Dead Lock and Euro Profile Cylinder - Key and Knob 70mm SS, SS 2 ball-bearing hinges - (127mm x 76mm x 2.5mm), door closer (all of approved make and quality), ZERO VOC or NO VOC duco paint finish for all beech wood members, etc., complete as directed.				
1.4	FIXED GLASS WORKS: (12MM TOUGHENED GLASS WORK WITH MAIN ENTRANCE DOOR AND GLASS PARTITION DOORS)	30		Sq.M.	
	Providing, making and fixing in position Fixed 12mm / 10mm toughened glass as fixed glass from Floor to available Ceiling level along with Main Entrance Door and for Partitions. The glass is to be fixed with patch fittings and all the edges of the glass have to be polished for a smooth finish. The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.				
1.5	12MM TOUGHENED GLASS MAIN ENTRANCE DOOR AND PARTITION DOORS:	8		Sq.M.	
	Providing, making and fixing in position Fixed 12mm / 10mm toughened glass openable shutters work as per specifications given below and for the openings mentioned. Main Entrance Glass Work comprising of Door opening of approximate size 1800mm x 2250mm - 2400mm in two pieces, and Partition Doors of approximate size 900 - 1000mm x 2250mm - 2400mm. The entire work to be done as per site conditions with following specifications etc., complete as directed.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	<p>(a) Entrance door - Providing, fixing in position glazed entrance Double door and Single door with patch fitting or approved make (Double Door approx. Size: 1800mm - 1500mm x 2400mm - 2250mm and Single Door approx. Size: 900mm - 12mm x 2400mm - 2250mm) using 12mm / 10mm toughened glass edge polished. The Door to consist of Heavy Duty Floor spring, Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Corner Lock and the side fixed glass to have 2 Nos. Bottom Patch and 2 Nos. Upper Patch for each door to a neat finish etc., complete as per drawing.</p> <p>(b) The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.</p>				
1.6	WALL PANELLING:				
1.6.1	WALL PANELLING IN BANKING HALL:	60		Sq.M.	
	<p>Same as item 1.1 above, but for Wall Panelling. The basic frame work to comprise all cladding specified only from one side to a neat job as per drawings and directions etc., complete.</p> <p>(a) Providing 15mm thick jamb for door and window openings of suitable depth as per site conditions.</p> <p>(b) All beech wood members to have NO VOC or LOW VOC duco paint finish.</p>				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
1.6.2	WALL PANELLING WITH SPECIAL HIGH GLOSS LAMINATE FOR E-LOBBY:	30		Sq.M.	
	Same as item 1.4 above to be cladded with 1mm Laminate (Laminate Base Rate Rs - 600/- Sq.M.) from one side to a neat finish as per drawings and directions etc., complete.				
1.7	COLUMN PANELLING:	35		Sq.M.	
	Providing and fixing metal stud column panelling with following specifications:				
	(a) Supporting system comprising of 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs at 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings.				
	(b) 12mm HDF Board fixed on all four sides with 25mm dry wall screws for the entire height of the partition.				
	(c) Column Panelling from floor level upto 2350mm level to have 100mm bottomline expression skirting (aqua blue color) at bottom + from 100mm to 2350mm level to have 1mm High Gloss Laminate on two longer sides of the column as shown in drawing.				
	(d) Column Panelling to have 6mm toughened lacqured glass in aqua blue color fixed with 12mm x 12mm button beading on two shorter sides of the column, to a neat finish as per drawings and directions etc., complete.				
	(e) Column Panelling above 2350mm level to have NO VOC or LOW VOC plastic emulsion paint finish on all four sides as shown in drawing.				
	(f) All beech wood members to have minimum two coats of				
	(g) All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				
1.8	LACQURED GLASS WORK FOR E-LOBBY:	8		Sq.M.	

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	Providing and fixing in position 8mm toughened lacquered glass (colour - Black or blue) for glass partition. The work to include making necessary template for all the glasses and then cutting the glass to correct size, making all the necessary holes, cuts etc., and then toughening the same. The cost to include all hardware required viz., single corner patch, bracket etc., The approximate size of each glass will be 1950mm x 450mm to 1200mm as per site conditions. The rate is for a finished item of work etc., complete as directed.				
1.9	FALSE CEILING:				
	Providing, making and fixing in position the following types of different false ceilings with different materials as specified below for a finished item of work as per drawings and directions etc., complete.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
1.9.1	GRID FALSE CEILING:	55		Sq.M.	
	<p>Providing & Fixing of Mineral Fibre Acoustical Suspended Ceiling System with 15mm Tiles and Exposed GRID. The tiles should have Humidity Resistance (RH) of 90% - 99%, NRC 0.5, Light Reflectance \geq87%, Thermal Conductivity $k = 0.052 - 0.057$ w/m K, Colour White, Fire Performance UK Class 0 / Class 1 (BS 476 pt - 6 &7) in module size of 600 x 600 x 16mm , suitable for Green Building application, with Recycled content of 30% - 45% .</p> <p>The tile shall be laid on Microline / Silhouette profile grid system with 15mm - 16mm white flanges incorporating a 6mm central reveal in white/black colour and with a web height of 38mm and a load carrying capacity of minimum 8 Kgs/M2 & minimum pull out strength of 100 Kgs. Microline / Silhouette, Main Runners & Cross Tees to have mitred ends & "birdsmouth" notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 90 grams per M2 and need to be installed with Suspension system as per manufacturers details.</p> <p>The Instalation to comprise main runner spaced at 1200mm centres securely fixed to the structural soffit using US Boral / Gyproc / Armstrong suspension system (specifications below) at 1200mm maximum centre. The First/Last suspension system at the end of each main runner should not be greater than 450mm from the adjacent wall.</p> <p>Flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm centre to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees. Perimeter trim to be Wall angles of size 3000mm x 19mm x 19mm, secured to walls at 450 mm maximum centres.</p>				
1.9.2	PLAIN FALSE CEILING:	85		Sq.M.	

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	<p>Providing and fixing Concealed Grid suspended ceiling system of 12.5mm Gypsum Boards / Standard Plaster Boards fixed to ceiling Frame Work as per manufacturers instructions and details for a concealed grid key lock suspended ceiling system consisting of following:</p> <p>(a) 27 x 37 x 1.6mm Soffit Clip, 5mm suspension rod / 25 x 10 x 0.5mm Ceiling Angle, adjustable spring loaded suspension clip / 2.64mm dia Connecting Clip, 20 x 28 x 30 x 0.5mm Perimeter Channel, Top Cross Rail of 3000mm long of 0.55BMT Furring Channel / 15 x 45 x 15 x 0.9mm Intermediate Channel and 4000mm long made of 0.5mm BMT the Top Cross Rail / 80 x 26 x 0.5mm Ceiling Section to be suspended from ceiling at every 1200mm and Furring / Intermediate Channel to be fixed to Top Cross Rail / Ceiling Section at every 600mm to make a grid of 1200 x 600mm.</p>				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(b) All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				
	(c) Further the rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed.				
1.9.3	VERTICAL FACES IN FALSE CEILING:	15		Sq.M.	
	Same as item 1.9.2 above but for vertical faces in false ceiling as per drawing including cut outs for AC grilles etc., complete as directed.				
1.9.4	VENEER FALSE CEILING:	10		Sq.M.	
	Same as item 1.9 below but for 12mm Plywood instead of Gypsum Board / Standard Plasterboard cladded with 4mm Veneer (Veneer Base Rate RS - 1,500/- Sq.M.) with minimum three coats of melamine spray polish to a finished item of work as per drawings and directions etc., complete.				
1.9.5					
1.10.1	WORK TABLE: (WITH 6MM ACRYLIC SOLD SURFACE TOP)	3		Sq.M.	
	Providing, making and placing in position worktables made in 18mm HDF Board for all members except table top and 25mm block board for table top and Ready Made Foot Rest, Key Board Tray and vertical supports at approximately every 1350mm length. The Work Table top and front fascia to have 6mm thick acrylic solid surface and remaining all exposed faces to have 1mm High Gloss Laminate as specified. The wooden members to have NO VOC or LOW VOC duco paint finish and the unexposed faces to have minimum three coats of LOW VOC or NO VOC enamel paint with putty etc., complete as directed. The table to have a three drawer unit for every 1350mm length as per drawing. All faces of HDF Board to have 6mm beech wood lipping. The cost to include all materials, labour, necessary hardware viz., drawer channels, " W " hinges, SS handles, set locks etc., to a neat job as per directions and directions etc., complete.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
1.10	WORK TABLE: (WITHOUT 6MM ACRYLIC SOLD SURFACE TOP)	1		Sq.M.	
	Providing, making and placing in position worktables made in 18mm HDF Board for all members except table top and 25mm block board for table top and Ready Made Foot Rest, Key Board Tray and vertical supports at approximately every 1350mm length. The Work Table top to have 1mm Laminate as specified and alround front facia to have 12mm thick beech wood lipping along with minimum two coats of NO VOC or LOW VOC duco paint finish and remaining all exposed faces to have 1mm High Gloss Laminate as specified. The wooden members to have NO VOC or LOW VOC duco paint finish and the unexposed faces to have minimum three coats of LOW VOC or NO VOC enamel paint with putty etc., complete as directed. The table to have a three drawer unit for every 1350mm length as per drawing. All faces of HDF Board to have 6mm beech wood lipping. The cost to include all materials, labour, necessary hardware viz., drawer channels, " W " hinges, SS handles, set locks etc., to a neat job as per directions and directions etc., complete.				
1.11	STORAGE UNITS:	10		Sq.M.	
	Providing, making and placing in position Storage Units with horizontal partitions of 1200mm high abutting wall and 750mm high as back credenza or abutting partition made in 18mm HDF Board to all members except table top and 25mm block board for table top. The top and front facia of the storage unit to have 6mm thick acrylic solid surface. All other exposed faces of the unit to have 1mm High Gloss Laminate as specified and NO VOC or LOW VOC enamel painting with putty finish on all unexposed faces including NO VOC or NO VOC duco paint finish for all wooden members and all necessary hardware viz., 'W' or wing hinges, locks, handles, tower bolts etc., and beech wood beading 40mm x 40mm at top and beech wood edge lipping 20mm x 6mm etc., as per drawings and directions etc., complete.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
2.0	LOOSE FURNITURE:				
2.1	BRANCH HEAD TABLE:	1		Each.	
	<p>Providing, making and placing in position Executive Table and Side Table of approximate size 2100mm x 900mm x 750mm + 1050mm x 450mm x 750mm with following specifications.</p> <p>(a) Main Table and side Table top and to be made in 25mm block board with 6mm thick acrylic solid surface. The front side of the table to have a inverted " C " made with 2 x 18mm thick HDF Board cladded with 6mm acrylic solid surface on the front and the verticals towards the modesty panel. The modesty panel to have 19mm HDF Board cladded with 1mm Laminate as specified.</p> <p>(b) The " L " shaped table top on the back side to have 50mm edge alround and to be cladded with 6mm acrylic solid surface.</p> <p>(c) All other members to be with 18mm HDF Board and all exposed faces of the table to have 6mm acrylic solid surface OR 1mm HD Gloss Laminate as specified above to be used.</p> <p>(d) All the edges of 18mm HDF Board to have 20mm x 6mm beech wood edge lipping.</p> <p>(e) One readymade CPU mobile pedestal.</p> <p>(f) One Molded Key Board Tray with channels etc.,</p> <p>(g) One Three Drawer Unit made with 18mm HDF Board and 12mm HDF Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 20mm x 6mm beech wood edge lipping etc.,</p> <p>(h) One Side Table with shutter unit of 400mm made with 18mm HDF Board and 19mm plywood with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and 20mm x 6mm beech wood edge lipping etc.,</p> <p>(i) All the unexposed faces to have minimum two coats of NO VOC or LOW VOC enamel paint with putty finish.</p> <p>(j) Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.</p>				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
2.2	OTHER OFFICER's EXECUTIVE TABLES:				
2.2.1	OFFICER's AND SIDE EXECUTIVE TABLES:	2		Each.	
	<p>Providing, making and placing in position Executive Table and Side Table of approximate size 1650mm - 1550mm x 750mm x 750mm + 1050mm x 450mm x 750mm with following specifications.</p> <p>(a) Main Table and side Table top and to be made in 25mm block board with 6mm thick acrylic solid surface. The front side of the table to have a inverted " U " made with 2 x 18mm thick HDF Board cladded with 6mm acrylic solid surface on the front and the verticals towards the modesty panel. The modesty panel to have 19mm HDF Board cladded with 1mm HD Gloss and 1mm Laminate as specified.</p> <p>(b) The " L " shaped table top on the back side along with side tabe to have 49mm edge alround, which is to be achieved by adding a 75mm piece of 18mm HDF Board to the table topl from bottom and this vertical edge is to be cladded with 6mm acrylic solid surface.</p> <p>(c) All other members to be with 18mm HDF Board and all exposed faces of the table to have 6mm acrylic solid surface OR 1mm HD Gloss Laminate as specified above to be used.</p> <p>(d) All the edges of 18mm HDF Board to have 20mm x 6mm beech wood edge lipping.</p> <p>(e) One readymade CPU mobile pedestal.</p> <p>(f) One Molded Key Board Tray with channels etc.,</p> <p>(g) One Three Drawer Unit made with 18mm HDF Board and 12mm HDF Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 20mm x 6mm beech wood edge lipping etc.,</p> <p>(h) One Side Table with shutter unit of 400mm made with 18mm HDF Board and 19mm plywood with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and 20mm x 6mm beech wood edge lipping etc.,</p> <p>(i) All the unexposed faces to have minimum two coats of NO VOC or LOW VOC enamel paint with putty finish.</p>				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(j) Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
2.2.2	PB AND SME OFFICER'S EXECUTIVE TABLE AND SIDE EXECUTIVE TABLE:	1		Each.	
	Same as item 2.1.1 above but for 600mm side Shutter unit instead of 400mm, with 2 drawers and two openable shutters as per drawings and directions etc., complete for a finished item of work.				
2.3	GRAHAK MITRA TABLE:	1		Each.	
	Providing, making and placing in position Grahak Mitra Table of approximate size 1500mm x 800mm - 900mm x 750mm with following specifications.				
	(a) Main Table Top to have 25mm block board with 6mm thick acrylic solid surface. The vertical supports of the table is to be made with two side boxing of 75mm x 800mm x 750mm made with 18mm HDF Board and the front side boxing to 200mm x 450mm x 750mm on either sides and central boxing of 250mm x 600mm x 750mm, all made with 18mm HDF Board clad with 6mm acrylic solid surface on all the exposed sides and top.				
	(b) The front of the table to have a 600mm x 1050mm proud portion with provision for cove lighting at bottom and this central portion to be clad with 6mm thick aqua blue colored lacquered glass.				
	(c) All other members to be with 18mm HDF Board and all exposed faces of the table to have 6mm acrylic solid surface and the drawer unit to have 1mm High Gloss Laminate as specified to be used.				
	(d) All the edges of 18mm HDF Board to have 20mm x 6mm beech wood edge lipping.				
	(e) One readymade CPU mobile pedestal.				
	(f) One Molded Key Board Tray with channels etc.,				
	(g) One Three Drawer Unit made with 18mm HDF Board				
	(i) All the unexposed faces to have minimum two coats of NO VOC or LOW VOC enamel paint with putty finish.				
	(j) Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
2.4	SINGLE WINDOW COUNTERS:	6		Each.	
	Providing, making and placing in position Single Window Counters along with necessary partitions as per item 1.2 above (The partiltions will be measured and paid as per item 1.2 i.e., Half Height Partitions) with following specifications and per dimensions specified.				
	(a) The overall size of each Single Window Counter to be 1650mm - 1500mm x 900mm - 975mm x 750mm + 1050mm x 450mm x 750mm.				
	(b) Tabletop of main table and side table to be made in 25mm block board with 6mm thick acrylic solid surface and double thickness at edges alround. The acrylic solid surface to continue in the front side with curvature from the front table top to the modesty panel in front with cove lighting provision.				
	(c) All other members to be with 18mm HDF Board / 2 Nos. of 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and all exposed faces of the table to have 6mm thick acrylic solid surface OR 1mm High Gloss Laminate as specified in the drawing to be used.				
	(d) All the edges of 18mm HDF Board to have 20mm x 6mm beech wood edge lipping.				
	(e) One readymade CPU mobile pedestal.				
	(f) One Molded Key Board Tray with channels etc.,				
	(g) One Three Drawer Unit made with 18mm HDF Board and 12mm HDF Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 20mm x 6mm beech wood edge lipping etc.,				
	(h) One Side Table with shutters made with 25mm block board top and 18mm HDF Board for all other members with necessary hardware viz., ' W ' hinges, SS handles, locks, SS tower bolts, etc., and 20mm x 6mm beech wood edge lipping etc.,				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(i) All the unexposed faces to have minimum two coats of NO VOC or LOW VOC enamel paint with putty finish.				
	(j) Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	(k) All wooden members to have minimum two coats of NO VOC or LOW VOC duco paint finish.				
	(l) Each Single Window Counter to have half height partitions on either sides as per item 1.1.2 above.				
	(m) Each Single Window Counter to have 12mm thick clear float glass in the front side of approximate size 1650mm x 450mm with a central cut out of 200mm x 175mm. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets.				
	The cost to include the " L " shaped Single Window Counter, two Side Partitions and to include all materials, hardware, labour for a neat and finish job as per drawings and directions etc., complete.				
2.5	12MM TOUGHENED GLASS DIVIDERS FOR SINGLE WINDOW COUNTERS:	7		Each.	
	Providing, making and fixing in position 12mm thick toughened clear float glass in the front side of half height partitions of Single Window Counters of approximate size 1150mm x 400mm - 100mm in tapered shape. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.				
2.6	12MM TOUGHENED GLASS ON TRANSACTION SIDE FOR SINGLE WINDOW COUNTERS:	5		Each.	
	Providing, making and fixing in position 12mm thick clear float glass in the front side of approximate size 1650mm x 450mm with a central cut out of 200mm x 175mm. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.				
2.7	WALL MOUNTED WRITING DESK:	2		Each.	

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	Providing, making and placing in position Wall Mounted Writing Desk 750mm x 300mm x 450mm with following specifications.				
	(a) The entire unit is to be made with 18mm HDF Board clad with 1mm High Gloss Laminate as per drawing.				
	(b) The Writing Desk to have 12mm thick toughened clear float glass with 25mm champered bull nosing around at top fixed with SS supports.				
	(c) All members to be with 18mm HDF Board and all exposed faces to have 1mm High Gloss Laminate as specified.				
	(d) All the edges of 12mm / 18mm HDF Board to have 20mm x 6mm beech wood edge lipping.				
	(e) All the unexposed faces and members of beech wood to have minimum two coats of NO VOC or LOW VOC enamel paint with putty finish.				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
3.0	OTHER WORKS:				
3.1	PLASTIC EMULSION PAINTING:	400		Sq.M.	
	Cleaning the surface of the wall & then applying one coat of altex putty followed by one coat of primer & then applying second coat of putty to give smooth finish exactly in line and level & then finally applying a minimum of two coats of NO VOC or LOW VOC Plastic Emulsion Paint of approved shade to give a neat finish including cost of all materials necessary scaffolding etc., complete for walls & ceiling.				
3.2	ROLLER BLINDS:	5		Sq.M.	
	Providing and fixing in position of Roller Blinds of approved Fabric (Fabric Cost - RS. 1,000/- per Meter) of Hunter Douglas / Mac / Vista make or approved equivalent of approved shade etc., as directed.				
3.3	DESIGNER FILM WORK:	20		Sq.M.	
	Providing and fixing in position Designer Film with elipse design on all glasses as per draswings and heights mentioned. The Designer Film is of Harmony / 3M or equivalent approved make. The rate is for a finished item of work etc., complete as directed.				
3.4					
3.5	CARPET TILES FLOORING:	5		Sq.M.	
	Providing and fixing in position carpet tiles of approved make, for finished item of work etc., complete as directed.				
3.6	VITRIFIED TILES FLOORING:	135		Sq.M.	

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	<p>Providing & laying flooring with Full Body Vitrified Tiles (Double Charged) of approved make, shade and colour of 600mm x 600mm size of 10 / 12mm thickness laid over laid over a flooring bed of 50mm to 75mm thick or more in CM 1:8 proportion including neat cement slurry of honey like consistency spread at the rate of 3.3 Kgs cement per Sq.M. before laying tiles on base coat and filling the joints with white cement or colour cement to match the shade of tiles including cost of base coat, cement slurry, jointing material and cost and conveyance of all materials viz., cement, sand, water, vitrified tiles, white or coloured cement etc., to site, cost of seigniorage charges on materials, labour charges for all operations etc., complete as directed, curing etc., complete for finished item of work. Alternatively approved make Tile adhesive and jointing compound can be used without any extra cost. (Base Rate for body tiles - 900/Sq.M. and Base rate for dark tiles - 1050/Sq.M.)</p>				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
3.7					
3.8	ENTRANCE - VINYL SCRAPER MATTING:	12		Each.	
	Providng, fixing in position 3M™ Nomad™ Scraper Matting 7150, Gray / Red. Entrance coiled vinyl scraper matting designed for heavy traffic applications over the existing flooring to a neat finished job as per drawings and directions etc., complete.				
3.9	REMOVING OF EXISTING COUNTERS, WALL PANELLING, LOOSE FURNITURE, FLOORING, PLUMBING LINES, FALSE CEILING, HVAC DUCTING ETC.,:	1		Sq.M.	
	Dismantling and removing the existing Counters, Wall Panelling, Loose Furniture, False Ceiling etc., along with HVAC Ducts, removing existing plumbing lines if required with proper closing of valves etc., complete and carting away nonservicable material and disposing of all debris to contractors dump yard or approved land fill as directed etc., complete. All servicable items are to be handed over to SBI and to be carted to their stack yard as per directions of SBI etc., complete. Contractor has to quote the price for BUY BACK VALUE OF THE ITEMS.				
	TOTAL			RS.	
	DISCOUNT IF ANY:			RS.	
	NETT TOTAL:			RS.	
	Plz Note: GST should not be included in the above amount				
	Rupees _____ _____ _____ Only.)			RS.	

Signature and Seal of the Contractor.