

Bill of Quantities for Interior Works of AECS "B" layout branch – partial renovation					
Sl.No	Description	Qty	Unit	Rate	Amount
1	Providing and fixing 19mm ply in front of SWO counters over which corean materilas to be placed which shall be paid separately.Provision to be made for LED lighting in front as instructed by Engineer	3.50	sq.m		
2	1mm thick laminated sheets to be fixed with adhesive on visible surface (without ply) at both sides as per directions	250.00	sq.m		
3	Providing and fixing 8mm thk fiber cement board on existing server and UPS room partitions and doors. The surface is to be painted with putty and two coats of emulsion paint as required – in UPS room	9.80	sq.m		
4	Providing and fixing 6mm BWR ply to Aluminium section of 25mmx 50mm with laminate on column/wall surface with adhesive,nails,screws,for levelling etc. Complete pasted with 1mm thk laminate with all grooves, adhesive,nails,screws etc complete.	120.00	sq.m		
5	Providing and fixing 6mm thk solid acylic surface (Corean) panelling onto the plywood surface with all necessary adhesives and including cutting , chamfering,chasing,buffing,polishing,ect.	7.20	sq.m		
6	12mm THICK TOUGHENED GLASS FOR SW FRONT SIDES AND FINS:Providing and fixing 12mm thk best quality toughened glass panel of approved make & size as per the design including polishing of the exposed glass edges , ect.,all ,materials , labour, lead,lift etc.,all in line level complete as per the details drawing.The glass to be pasted with light blue transparent sticker which will be paid together	2.30	sq.m		
7	12mm thk toughened glass with fasting studs in front of BM's table with shimmery blue sticker which will be paid together	0.90	sq.m		
8	6mm thk lacquered glass(without studs) in front of SWO counters	2.00	sq.m		
9	Alteration of existing Cash counter along with door of height 2100mm to 1500mm and carting away from site	1.00	LS		
10	Polishing of exposed beading of partitions,tables,doors,etc after preparing the surface smooth by rubbing with sand paper. (approximately 150 rm)	1.00	LS		
11	Painting of exting walls with two coats of emulsion paint	200.00	sq.m		
12	REMOVING & BUYBACK				
12.1	Removing of existing 19mm thk granite at counters and carting away from site – 1500m(L) * 750mm(D)	-3.00	Nos		
	TOTAL (A)				