

TENDER
STATE BANK OF INDIA
LHO, KOLKATA

Supply and Laying of Paver Tiles & Repairing of Road at SBI Senior Official Residential Complex, Alipore

Sl.No	DESCRIPTION	UNIT	RATE	QNTY	AMOUNT Rs. P.
1.	Taking out the existing damaged concrete upto 50 mm thickness and disposal of the debris by vehicle upto 4-5 km dumping ground as per direction of the Engineer In-Charge. The rate is inclusive of labour, tool & tackles, transportation, supervision and taxes	sqmt		550	
2.	Taking out the existing asphaltic weathering coat comprising of 75 mm thick asphaltic concrete laid over 12 mm thick mastic asphalt and disposal of the debris by vehicle upto 4-5 km dumping ground as per direction of the Engineer In-Charge. The rate is inclusive of labour, tool & tackles, transportation, supervision and taxes	sqmt		750	
3.	Providing and laying PCC (1:1.5:3) cement : sand : stonechips 6 mm down (cleaned), including non-metallic Floor Hardner (chapidur) including polish of the top level. The Rate is inclusive of shuttering, proper leveling of slope for disposal of rain water / surface water to the nearest pit, labour, tools & tackles, transportation, water, electricity and taxes	Cum		30	
4	Supply and laying Heavy Duty Paver Tiles (600 mm x 600 mm) x 16 mm thick, , Acid & Alkali proof as per IS 4457 (make Pavit : Gritty Branca / Silver Shadow and Gritty Crust), water absorption <0.5 %, breaking strength > 7500 N, Modulus of rupture > 37 N/mm ² , to be fixed over a pcc concrete bed 1:1.5:3 or cement mortar 1:4 ratio and filling the joints with tiles admixture / sealant of the same colour, curing, complete as per direction of Engineer In Charge (basic price Rs.115/- per sqft)	sqmt		2800	
5.	Making of RCC Drain of size 300 mm x 200 mm with MS grating on top to receive the catchment rain water and connecting to the nearest drain. The rate is inclusive of shuttering, RCC, labour, curing, reinforcement, etc to complete as per direction of Engineer In Charge	Rmt		600	
	TOTAL				

(Amount in Words : Rupees

Dated :

Signature & Seal of Bidder

