

CIRCLE OFFICE, THIRD FLOOR, STATE BANK OF INDIA, SYNERGY BUILDING,
C-6, G-BLOCK, BANDRA KURLA COMPLEX, BANDRA EAST, MUMBAI-400051

PART – B: FINANCIAL BID

TENDER FOR:

PROPOSED INTERIOR WORK FOR ACHALPUR BRANCH,

TENDER SUBMITTED BY:

NAME : _____

ADDRESS : _____

DATE : _____

TENDER INVITED BY:

Vice President & Circle Head,
SBI Infra Management Solutions Pvt. Ltd; 3rd floor, Circle Office, State Bank of India, Synergy building, C-6, G-Block, Bandra -Kurla complex, Bandra East, Mumbai-400051.

ARCHITECT :

Ashfaq Ahmed Consultancy Services Pvt.Ltd.,
289, New Colony, Sadar Nagpur – 440001
Tel : 9823054655 / 0712-2595752 / 25833493 E-Mail : craftteam9@yahoo.co.in

Tender Copy of Interior Work of SBI Bank, Achalpur.

Sr. No.	Particulars	Qty.	Unit	Rate	Amount
1	<u>False Ceiling</u>				
	Providing and fixing in position 12.5 mm thick gypsum board false ceiling fixed with 16 gauge galvanised frame upported from and fixed to RCC slab with Anchor bolts. The ceiling should contain approx 40%of the ceiling area of 12mm thick Armstrong ceiling (600x600mm) beuti sky or other approved pattern and stepping. all the joints to be properly sealed with jointing tape and finished with approved jointing material. The item includes making cutouts and providing necessary frame work for light fitting, grill diffusers and ducts etc. which have to be made with frame of perimeter chanel of size 20mm x 30mm x 0.55mm. thick supported suitably and angle bead is to be used at steps to get straight line finish etc. complete. The item rate shall also include preparation of surface with sanding and 3 coats of acrylic emulsion painting approved shade over a coat of primer/ putty including necessary work etc.	475	Sq.m		
2	<u>Full Ht Glazed / Partly Glazed/ Partly Paneled Partition</u>				
	Providing and fixing in position partly glazed and partly paneled partition made of 50 mm x 50 mm x 1.2mm medium alluminium hollow square pipes framed at 0.60m to 0.45m c/c both ways covered 6 mm MR grade ply and 1mm multi- colour laminate of approved make and shade and make with 6mm thick glass panel with etching as per design and / or necessary beading patti including 3 coats of french polish including door shutters as per architectural design with heavy duty hinges handles/ locks, etc. of approved make	140	Sq.m		
3	<u>Low / medium height partition</u>				
	Providing and fixing in position low/ medium height partition made of 50mm x 50mm 1.2mm medium duty alluminium hollow sqature pipes framed at 0.6 to 0.45 m c/c both ways covered with 6mm MR grade ply and 1mm thick laminate of approved shade and make, both sides including necessary opening / outing for receiving cheques and other papers and to recieve 8mm thick float glass including all necessary openings for electric/ telephonic conduits, etc. as per requiremnts. (Glass area in hte partition will be deducted in the measurements of the partition)	20	Sq.m		
4	<u>Glass partition</u>				

Sr. No.	Particulars	Qty.	Unit	Rate	Amount
	Providing and fixing 8 mm thick glass with etching as per design for low ht partition held with SS clits (D brackets). All exposed glasses with rounded moulding and crystal polish. All exposed woodwork to be finished in 3 coats of french polish / melamine polish.	16	Sq.m		
5	Single window counter				
a	Providing and fixing in position single window counter as per design, made of 18mm/ 19mm thick MR grade ply structure and laminated glass in approved shade, and front side teak moulding patti, duly finished with three coats of PU. Finish. All exposed external surfaces finished with 1mm laminate and internal surfaces finished with 0.8 mm laminate of approved shade and make with foot rest of 75x38mm 18mm thick ply, with 12 mm thick plain glass of 150 mm deep of counter length at service top adjacent to top with 12mm thick and 380 mm height etching glass at front including making half round opening of 150 mm dia duly finished with crystal polish and having CPU stand of 19 mm thick MR grade ply including cable manager, a key board rest with telescopic movement.	6	Rmt.		
6	System Room Table				
	Providing & fixing server room table with 2'-3" depth using 18mm/12mm/6mm thk. MR Grade ply for all structure work,Table top, shelves, shutter, drawer, keyboard etc with 1mm thk.Laminate finish on exposed side and enamel paint finish on internal side. Locking arrangement should be done to drawers and shutters should have S.S handles of brush finish of 6" ht as approved by consultant. Provision for 3 sets of CPU stand, footrest & keyboard should be given.Wire manager should be provided at the corner of the working top.	1.8	R.mt		

Sr. No.	Particulars	Qty.	Unit	Rate	Amount
7	Door				
i.	Entrance Door				
	Providing & fixing in position Entrance Door of two shutters 4'0" len x 7'0" ht, and side entrance door with 8mm thick float glass with etching design fixed in 40mm x150mm x size CPTW frame from all sides. Brush finished SS handles of 30mm height from both sides including SS tower bolts on internal side (DORMA / HETICH or equivalent) including approved locking arrangement. All woodwork to be finished with three coats of French polish complete etc	10	Sq.m		
ii.	Providing and fixing of Floor spring for main entrance door of approved quality and make (DORMA / GODREJ or equivalent).	4	Nos.		
ii.	Solid Door				
	Providing and fixing factory made solid core flush door in single leaf 30 mm thick, finished with approved 1mm thk laminate on both faces with/ without glazing and venetians in the positions shown on the drawings or as directed, all necessary beads, moulding and lipping, stainless steel fixtures and fasteners with CP/ Brass mortise lock, Stainless steel handles on both sides, stoppers and exposed woodwork finished with french polish complete.	17	Sq.m		
8	Removing of Existing Partiton & other non re-usable furniture & disposal of same as directed out ride municipal limits.		LS		
	TOTAL				
9	Removing Existing re-useable furniture excluding chair carefully and buy back of		LS		
	GRAND TOTAL				

In words:

S U M M A R Y :		
Total of furniture Work	Rs.	
Less discount (if any)	Rs.	
Total cost of work Tendered	Rs.	
Add SGST @ 9%	Rs.	
Add CGST @ 9%	Rs.	
FINAL AMOUNT INCLUDING GST	Rs.	

Total Amount
Rupees in words:

Signature & Seal of Contractor

Date