



AIR-CONDITIONING OF GUMI BRANCH
BOQ for Supply, Installation and Annual Maintenance Contract for 5 years of Air-conditioners

Sl.N o.	Description	UOM	Qty.	Rate (Rs.) (Exclusive of GST)	Amount (Rs.) (Exclusive of GST)
1	Supply of 1.5 TR Capacity Hi Wall mounting 5-star rated Inverter Split AC with cordless remote and Copper Condensor Coil. AC Make, Voltas/Bluestar /Carrier/Daikin /LG/Godrej	No.	8		
2	Installation charges of the 1.0/1.5 TR Hi-Wall Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	8		
3	For 1.0 TR/1.5 TR Hi-Wall type split air conditioners: Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessities and making good all the damages.	RM	40		
4	Supply and Installation of 4 KVA Stabilizer for 1.0 TR/1.5 TR Split Acs	Nos.	8		
5	Comprehensive Annual Maintenance Contract of above mentioned 8 Nos. of 1.5 TR Hi-Wall type split air conditioners after expiry of defect liability period of 1 year from the date of installation.	year	5		
GST will be extra as applicable.		Grand Total(In Rupees)			