

BOQ FOR SITC OF AIR CONDITIONERS- UTRAON BRANCH RBO-5, ALLAHABAD (PRAYAGRAJ)

| S.NO. | ITEM DESCRIPTION | Qty | Rate | Amt. |
|--------------|--|---------|------|------|
| 1. | Supply , installation, testing & commissioning(SITC) of 1.5TR high wall 3 star rated(highest star rating in the category), BEE rated, mounted type air conditioner, wireless remote controlled with auto restart feature complete in all respect with indoor, outdoor unit, <u>copper condenser & copper cooling coil</u> interconnecting piping, wiring/ installation / drain pipe etc. (Upto 3 meters length). Item should also include 4 KVA hi/lo cut off, TDR relay start stabilizer. <u>Make of Air Conditioner:</u> Voltas/Bluestar/Carrier/Hitachi/Daiken <u>Make of Stabilizer:</u> Servel/V Guard/Stambh/Inmag | 04 NOs | | |
| 2 | Additional refrigerant interconnecting copper piping (both) with insulation, drain pipe, wire mesh cover throughout for protection for 1.5TR high wall ACs. Item is for interconnection piping additional to 3 meters which is included in item sl. No2. | 20 Mtrs | | |
| 3 | Suitable angle iron stand for 1.5 Tr. split AC made of minimum section 35x35x4 mm. duly painted with one coat of primer and two coats of enamel paint. The stand will have to be grouted /anchored to wall/ ledge in a safe manner to suit site conditions. (as per sl 2.) | 04 Nos | | |
| 4 | Electrical cabling from indoor to outdoor unit with suitable PVC copper wire for 1.5 high wall ACs. Item is for cabling additional to 3 meters included in item sl. 2. | 50 mtrs | | |
| TOTAL | | | | |

PLACE:

Signature and Seal of Bidder

DATE :