

KUTTIADY BRANCH
(NEW PREMISES)

INDICATIVE PRICE BID

Name of work		Interior furnishing work of branch			
SCHEDULE OF WORKS					
1	SINGLE WINDOW SYSTEM: Providing and fixing of Single window system without partitions as shown in drawings comprising of each counter size 1600 mm to 1800mm length or as per layout and 750 mm height or as per layout with below specifications and provisions: Counter and writing top at front, with counter 1600 mm to 1800 mm length and 900 mm width at about 750 mm height. The Top shall be fixed with 18 mm thick marine plywood of approved make finished with 6 mm thick corian top and with 12 mm thick clear polished glass top as per drawing. The shape of the modesty is as shown in the drawing . For the curved shape three layers of 6 mm flexy plywood is used. The exposed front portion of the table for a height of 40 cm from the bottom is made of Aqua blue shade of saint gobain glass as per the drawing. 18 mm marine ply of approved make for sides and for front shaped support and finished with 1mm laminate of approved color.12 mm thick clear polished float glass to shape with etching is fixed with SS glazed fittings fixed at front above the counter and sides as shown in the drawing.	15	RM		
	Modesty fixed with 8mm thick of Aqua Blue shade of saint Gobain glass fixed at 18mm thick marine ply vertical finished. The sides of the counter, boxing on either side to shape as shown in the drawing with 18 mm marine ply of approved make and to be finished with 1 mm thick laminate of approved color from floor level to 1200 mm level at places shown in the drg. Necessary wicket door shutters are to be provided using 18 mm marine ply and finished with 1mm laminate of approved color and shape as shown in the drawing One set of 3 drawers about 450 mm width, 712.5 mm height and 600mm deep supported with 18mm MDF at bottom, sides and rear.				
	Drawers 3Nos. Of which 2 Nos of equal height and 1No. Drawer at the bottom of 230mm height made out of 12mm thick marine ply for sides, rear , bottom and face of drawers with 18 mm marine ply and finished with 1mm thick laminate on both inside and exposed faces and 2 mm thick PVC edge band of approved color, telescopic drawer slides, locking arrangements with auto closing locks , 100mm long brush finish S.S. handles, etc. complete. Top most cash drawer should be arranged with provision for denomination with 8mm thk marine ply. MS Powder coated Telescopic keyboard tray and MS wire manager of 50mm dia of approved quality . Foot rest cum CPU stand of required length with 18mm thickness marine ply to shape as shown in the drawing.				
	All concealed faces of marine ply to be finished with two coat of enamel paint and exposed faces of 2 mm thick PVC edge band. The inner side of the unit finished with 1mm Laminate. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.. The rate of low height partition is not included and is paid separately				
2	SINGLE WINDOW SYSTEM (With Out Front Glass) The same as above specification without front toughened glass. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	1.65	RM		

3	Supplying and fixing side tables with 19mm marine plywood finished with 1mm decorative laminate over it on all exposed faces, 25mm thick marine ply with 1 mm thick laminate on top having underside covered with balancing laminate and 3 mm pvc edge banding on all exposed edges as per the <u>sketch</u> enclosed. Side hung shutter in both the panels using 18 mm Plywood and finished with 1mm laminate of approved color and shade, including all necessary TW lipping, Box Type hinges, Locking arrangement, 100 mm long S.S brush finish handles, tower bolt, ball catch etc., complete. 12 mm glass with edges polished to be provided for the table top. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.				
(i)	120 x 40 x 60cm ht.	9	Each		
(ii)	100 x 40 x 75cm ht.	5	Each		
4	Supplying and installing double skin wooden partitions 120cm height around the clerical counters with 63.5x38.1x1.2 mm thick hollow Aluminium Sections of make Indal/Jindal for horizontals at floor level and 75cm ht. and verticals @ 75 cm c/c and 8 mm marine ply on both sides finished with 1mm laminate and with as per the <u>sketch</u> enclosed including providing necessary doors 40mm thick with Godrej night latch fixed at 45 cm ht. from floor level , tower bolts, etc. as per the layout plan. Between 750 mm and 120mm level, 12 mm thick glass with etching pattern (permanent) fixed with necessary D brackets of make Dorma or equivalent of SS finish. The glass opening 'Jamp' portion is to be finished with laminate.	50	Sq.M		
5	Supplying and fixing counters 75cm ht. inside the server room/any other room as per specifications in item no.(1), except the provision for curved front modesty, front, side and top glasses and aqua blue glass, having one drawer & cupboard with locks, handles, computer key board tray, etc. and excluding front glass as per the <u>sketch</u> enclosed. Table top to be provided with 18mm marine ply finished with 1 mm laminate of approved make. 3 mm thick PVC Edge band to be provided on all exposed edges. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	3	RM		
6	Supplying and fixing low level storage units of width 45 cms made of 18 mm marine plywood finished with 1mm decorative laminate over it on all exposed faces, top with 18mm thick marine ply with 1 mm laminate and edgeband in all exposed edges including providing one shelf, necessary locks, handles, etc. as per the <u>sketch</u> enclosed. All the exposed edges of plywood are to be finished with 2 mm thick PVC edge band and all the inside portion finished with primer and 2 coats of enamel paint. One shelf to have minimum 40 cm height. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.				
(i)	units 120 cm height	14	RM		
(i)	Units 75 cm height	10	RM		
7	Toughened Glass Partition :-Providing and fixing 12mm Toughened glass Partition with necessary SS cover patch fitting (make – dorma), Patch fitting locks, fixtures, screws, sealants etc wherever required at height of 270/300 cm for entrance area, BM s Cabin etc. Necessary etching pattern to be provided in the glass. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with patch fittings, glue, nails, screw etc. complete as directed by the Engineer in charge.	25	SqM		

8	Toughened glass door: Providing and fixing Toughened glass door with handle for the Entrance/ Bms Cabin with 12mm toughened glass and patch fittings. Necessary etching pattern to be provided. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge. (Floor Spring provided as separate item)	7	SqM		
9	Supplying and fixing heavy duty hydraulic floor spring for entrance doors. (Dorma, Ebco, Hardwyn or approved equivalent with ISI mark) . The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	3	Each		
10	Supplying and fixing hydraulic door closers on doors. (Ebco, Dyna, Godrej or approved equivalent with ISI mark) . The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	5	Each		
11	Supplying and fixing suspended seamless false ceiling with 12 mm thick gypsum board over standard GI sections including perimeter channels as per the specification of 'India Gypsum'. to correct lines and levels finished with two coats of plastic emulsion paint of approved make and shade with roller application including providing <u>necessary openings</u> for electrical fittings, cove lighting as per design , A/c, security device, etc. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	280	SqM		
12	Painting over the walls with two coats of plastic emulsion paint of approved make and shade with one coat primer after rubbing and finishing the surface. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	40	SqM		
13	Painting over the walls with two coats of plastic emulsion paint of approved make and shade after applying two coat putty , rubbing and finishing the surface. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	200	SqM		
14	Supplying and providing panelling for columns with 9mm thick marine ply finished with 1 mm thick laminates including providing beech wood beading over the edges and top. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	50	SqM		
15	Supplying Officer tables as per the <u>sketch</u> enclosed with 18 mm thick marine ply table top laminated with 1 mm thick laminate of approved make and 12 mm thick clear polished glass top as in item no.1 Foot rest cum CPU stand of required length with same 18 mm. MS Powder coated Keyboard tray and 50mm Dia MS wire manager of approved quality . One set of 3 drawers with 18 mm marine ply of approved make at bottom, sides and rear with necessary edge bands, telescopic drawer slides, locking arrangement, 100 mm long brush finish S.S. handles, etc. complete.				

	All concealed faces of marine ply finished with two coat of enamel paint and exposed faces with 3 mm thick PVC edge band to the satisfaction of the Bank. The inside faces of drawer should be waxed and finished with varnish of app color and shade. the table modesty shall be fixed with 8mm thick of Aqua blue shade of saint Gobain (or) equivalent toughened glass panel fixed on the 18mm thick front vertical marine plywood and finished with 1mm thickness laminate. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.				
i)	180 x 90 x 75cm ht.	1	Nos		
ii)	160 x75 x 75cm ht.	8	Nos		
16	Supplying & fixing voucher stand on wall of size 1200mmx0.40 made of 19mm thick ply & laminate with 3 mm thick pvc edge band on al exposed edges, 8mm glass on top and 5mm glass compartments with polished exposed edges as per the sketch enclosed.	1	Nos		
17	Double Skin solid Partition and door:- Providing and fixing Double skin soild partition for UPS Room, Records room, and passage . The frame work is with hollow Aluminium sections of size 63.5mmx38.1mmx1.2mm of make Indal/Jindal @ 60 cm c/c both vertically and horizontally, finished with 8mm marine ply (IS 303)and 1 mm laminate of approved make on both side. Above 270 cm the partition are to be firmly fixed to the ceiling . The partition upto false ceiling only be measured. Necessary handles locks etc. to be provided. The rate is inclusive of cost and conveyance of all materials, labour charges including fixing with glue, nails, screw etc. complete as directed by the Engineer in charge.	30	SqM		
18	Providing and fixing Vertical blinds of Vista or any approved equivalent make and approved Colour.	32	SqM		
	Total				
	GST @ %				
				Total amount	