

**SBI INFRA MANAGEMENT SOLUTIONS PVT LTD(SBIIMS)**  
**(A WHOLLY OWNED SUBSIDIARY OF SBI), CIRCLE OFFICE, PATNA**

**DETAILED ESTIMATE OF CIVIL WORK FOR SORC ROAD AND FENCING WORK**

S.NO.	PARTICULARS	UNIT	QTY.	RATE	AMOUNT
1	Providing and laying in position specified grade of cement concrete including the cost of centring,shuttering,finishing-All work upto plinth level 1:1:5:3(1 cement: 1.5 coarse sand:3 graded stoneaggregate 20 mm nominal size) Including the cost centering struting decentering and dismantalling the old rcc pillar and recasting the same and with full finishing with all complete job.as directed by EIC.	NO	11		
2	Providing and laying in position specified grade pcc of including the cost of centring,shuttering,finishing-All work upto plinth level1:2:4(1 cement: 2 coarse sand:4 graded stoneaggregate 6 mm nominal size) Including the cost centering struting decentering and with all complete job.as directed by EIC.(THICKNESS OF PCC 40MM)	Cu.m	6		
3	Finishing walls with Premium Acrylic Smooth exterior paint with Siliconeadditives of required shade: New work (Two or more coats applied @ 1.43 ltr/10 sqm over and includingpriming coat of exterior primer applied @ 2.20 kg/10 sqm)as directed by EIC.	Sq.m	100		
4	Providing and applying white cement based putty of average thickness 1 mm,of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.as directed by EIC.	Sq.m	100		
5	Painting with synthetic enamel paint of approved brand and manufacture of including all cost required colour to give an even shade : Two or more coats on new work over an under coat of suitable shadewith ordinary paint of approved brand and manufactureas directed by EIC.	Sq.m	600		
6	Structural steel work of MS sheet of 16 gauge riveted, bolted or welded in built up sections,to the angle , including cutting, hoisting, fixing in position andapplying a priming coat of approved steel primer all complete.and angle fixing of size 40x35x5mm where ever required or as directed by eic	kg	4800		
<b>TOTAL</b>					

**SBI INFRA MANAGEMENT SOLUTIONS PVT LTD(SBIIMS)**  
**(A WHOLLY OWNED SUBSIDIARY OF SBI), CIRCLE OFFICE, PATNA**

**DETAILED ESTIMATE OF CIVIL WORK FOR INTERIOR AND EXTERIOR PAINTING WORK OF GUEST HOUSE**

S.NO.	PARTICULARS	UNIT	QTY.	RATE	AMOUNT
1	Providing two or more coats of oil bound acrylic distemper paint, 1st quality Asian paints / ICI Du-lux/ Berger/Nerolac or equivalent approved brand over a coat of cement primer to give an even shade over newly plaster of parish finished walls & ceil-ings as per direction of Bank. (including the cost of scaffolding)	Sq.m	2413		
2	Finishing walls with Premium Acrylic Smooth exterior paint(1st quality Asian paints / ICI Du-lux/ Berger/Nerolac or equivalent approved) with Siliconeadditives of required shade: New work (Two or more coats applied @ 1.43 ltr/10 sqm over and includingpriming coat of exterior primer applied @ 2.20 kg/10 sqm)as directed by EIC. (including the cost of scaffolding with complete job)	Sq.m	1838		
3	Painting with synthetic enamel paint of approved brand and manufacture of including all cost required colour to give an even shade : Two or more coats on new work over an under coat of suitable shadewith ordinary paint of approved brand and	Sq.m	118.875		
4	Providing and applying with texture paint of approved shed by EIC as per bank approved quality or as directed by EIC.(with all complete job)	sq.m	92.93		
5	French spirit polishing :	kg	241.63		
6	Dismantalling the old exterior painting putty work prepairing for new work of painting including the cost of labour and scaffolding and with all complete job.	sq.m	1838		
	<b>TOTAL</b>				

\*

**SBI INFRA MANAGEMENT SOLUTIONS PVT LTD(SBIIMS)**  
**(A WHOLLY OWNED SUBSIDIARY OF SBI), CIRCLE OFFICE, PATNA**

**DETAILED ESTIMATE OF CIVIL WORK FOR INTERIOR AND EXTERIOR PAINTING WORK OF SORC BUNGLOW**

S.NO.	PARTICULARS	UNIT	QTY.	RATE	AMOUNT
2	Finishing walls with Premium Acrylic Smooth exterior paint(1st quality Asian paints / ICI Du-lux/ Berger/Nerolac or equivalent approved) with Siliconeadditives of required shade: New work (Two or more coats applied @ 1.43 ltr/10 sqm over and includingpriming coat of exterior primer applied @ 2.20 kg/10 sqm)as directed by EIC.(including the cost of scaffolding and scrubbing the surface with complete job)	Sq.m	3595		
3	Painting with synthetic enamel paint of approved brand and manufacture of including all cost required colour to give an even shade : Two or more coats on new work over an under coat of suitable shadewith ordinary paint of approved brand and manufactureas directed by EIC.	Sq.m	425		

**TOTAL**