

BOQ FOR INTERIOR FURNISHING WORK					
MYLLIEM BRANCH-SHILLONG					
Sl.No	Description of items	Unit	Qty	Rate(Rs.)	Amount(Rs.)
1	Supply and installing new Front Counters of overall size 5'6"x5'6", including cost of side credenza (3'x1'6") with top made up of 19 mm thick ply finished with laminate of 1.0 mm thick as approved by the Bank and wooden beading / moulding all round melamine polished. The cost to include two drawers of 100 mm deep & a file shutter of 450mm, a keyboard tray 250 mm wide with CPU stand, foot rest. The works to include all hardware like castors, brass hinges, ball catchers, fully extendable drawer slides, locks, handles etc. of approved make. Locks to be of single control type. All exposed edges to have wooden lipping stained to match the desk and melamine finished. Rate to include cost of Studds. Design and detail of the counters shall be as per Bank's new uniform colour, layout & elevation policy 2016 available with Bank's engineer, at A.O., with curvature on front with flexi ply. Counter & Credenza top to be provided with 8mm thick glass duly finished on edges and necessary cut to accommodate wires, edges to be m/c polished, with ms powder coated wire manager, complete as directed by EIC and placement as per layout given Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalent	nos	2		
2	Providing & fixing <b>counter Front glass</b> 12 mm thick duly bevelled of size - 1500mm x 750mm with frost film as per design directed, including cost of studs, making cut-outs for transaction and voice hole. Rate shall includes etching of glass as directed by bank.	SQM	4.8		
3	Supply and installing <b>Branch Head Table</b> of Overall size-6'0"x6'0" <b>including cost of side credenza (3'6x1'6")</b> with top made up of 19mm thick ply with 1 mm thick laminate on top as approved by the Bank and wooden beading/ moulding all round melamine polished. The table cost to include (pedestal) , two drawers of 100mm deep & a file shutter of 450 mm, a keyboard tray 250mm wide with CPU stand. The works to include all hardware like castors, brass hinges, ball catchers, fully extendable drawer slides, locks, handles foot rest etc. of approved make. Locks to be of single control type. All exposed edges to have wooden lipping stained to match the desk and melamine finished. Design and detail of the table shall be as per direction of EIC. All the surfaces to be in laminate finish & <b>8mm thick glass duly finished to be placed on top of table &amp; credenza</b> and necessary cut-out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy 2016 available with Bank's engineer, at A.O. Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalent	nos	1		
4	Supplying and installing <b>Tables</b> of Overall size - 5'6"x5'6" including cost of side credenza (3'x1'6") with top made up of 19mm thick ply finished with 1 mm thick laminate on top as approved by the Bank and wooden beading/ moulding all round melamine polished. The table cost to include (pedestal) two drawers of 100mm deep & a file shutter of 450 mm, a keyboard tray 250mm wide with CPU stand. The works to include all hardware like castors, brass hinges, ball catchers, fully extendable drawer slides, locks, handles foot rest etc. of approved make. Locks to be of single control type. All exposed edges to have wooden lipping stained to match the desk and melamine finished. Design and detail of the table shall be as per direction of EIC. All the surfaces to be in laminate finish & 8 mm thick glass to be placed on table, credenza top and necessary cut out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy 2016 available with Bank's engineer, at A.O. Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalent	nos	2		

5	<p>Fabricating and installing <b>Grahak Mitra table</b> of overall size-5'x5'6'' <b>including cost of credenza</b> in straight or curved profile as per design and direction of EIC. The vertical supports and the front panel will be made of 2 nos of 19mm ply finished with 1 mm thick laminate and glass 12mm as per details. The table cost to include (pedestal) two drawers of 100mm deep &amp; a file shutter of 450 mm, a keyboard tray 250mm wide with CPU stand. The works to include all hardware like castors, brass hinges, ball catchers, fully extendable drawer slides, locks, handles foot rest etc. of approved make. Locks to be of single control type. All exposed edges to have wooden lipping stained to match the desk and melamine finished. All the surfaces to be in laminate finish &amp; <b>8mm thick glass duly finished to be placed on table &amp; credenza top</b> and necessary cut-out to accommodate wires, edges to be m/c polished, with m.s. powder coated wire manager complete as per Bank's new uniform colour, layout &amp; elevation policy 2016 available with Bank's engineer, at A.O.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green or equivalent.</p> <p>Laminate Make: Greenlam/Centurylam or equivalent</p>	nos	1		
<b>SERVER ROOM NOT REQUIRED AS ADVISED BY RBO</b>					
6	<p>Providing and fixing <b>storage units</b> 1'-6" wide &amp; 2'6" high. The storage units shall have shutters made in 19mm thick plwood and finished in 1 mm thick laminate of approved shade including top. The storage units shall have intermediate shelves made in 19mm thick plywood with matching wood lipping. The storage shall have wood edge moulding as per the direction of EIC. This also includes providing necessary hardware like handles, hinges, locks, tower bolts etc of approved make. All exposed wooden surfaces shall be stained to shade as directed by the EIC and polished melamine</p>	m	11		
8	<p>Fabricating and fixing <b>wall/column paneling</b>, consisting of 25 mm x 35 mm (thickness not less than 1.5 mm) alluminium section framework at spacing not exceeding 600 mm both ways (horizontal and vertical.) Panelling framework to be secured to wall surface / column surface and to be finished with 1 mm thick laminate of approved colour, brand and shade over 12 mm thick ply. Design and detail shall be as per direction of EIC and Bank's new uniform colour, layout &amp; elevation policy.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green or equivalent.</p> <p>Laminate Make: Greenlam/Centurylam or equivalent.</p> <p><b>To be provided only in BM room and backside of SWO counters</b></p>	sqm	42		
9	<p>Fabricating and fixing <b>full height solid partition</b>, made of 6 mm ply approved brand both side and to be finished with 1 mm thick laminate of approved brand, colour and shade over 50 mm x 50 mm ( thickness not less than 1.5 mm) alluminium section framework at spacing not exceeding 600 mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. All exposed edge shall be covered with teakwood lipping with polishing complete in all respect. <b>Payment will be made for the area upto false ceiling only.</b></p> <p>Ply/Block Board Make: MR Grade of Century/ Green or equivalent.</p> <p>Laminate Make: Greenlam/Centurylam or equivalent.</p>	sqm	13.2		
10	<p>Fabricating and fixing <b>full height semi glazed partition</b>, made of 6 mm ply of approved brand in both side and to be finished with 1 mm thick laminate of approved brand, colour and shade over 50 mm x 50 mm ( thickness not less than 1.5 mm) alluminium section framework at spacing not exceeding 600 mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. Middle portion at 900 mm to 2100 mm height shall have 5 mm thick plain float glass (Make: Saintgobin/Modigurd) fixed with 10 mm thick teak wood moulding duly polished. All exposed edge shall be covered with teakwood lipping with polishing complete in all respect. Payment will be made for the area upto false ceiling only.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green or equivalent.</p> <p>Laminate Make: Greenlam/Centurylam or equivalent</p>	sqm	30		

11	<p>Providing and fixing <b>low height semi glazed wooden partitions</b> made of 6 mm ply of approved brand in both side and to be finished with 1 mm thick laminate of approved brand, colour and shade over 50 mm x 50 mm ( thickness not less than 1.5 mm) alluminium section framework at spacing not exceeding 600 mm both ways (horizontal and vertical). Middle portion at 900 mm to 1200 mm height shall have 5 mm thick plain float glass (Make: Saintgobin/Modigurd) fixed with 10 mm thick teak wood moulding duly polished. All exposed edge shall be covered with teakwood lipping with polishing complete in all respect.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalen</p>	sqm	9.65		
12	<p>Providing and <b>fixing glazed doors</b> at Main entrance of average size of 2'6"X7'-0" made of top, bottom, middle and side wooden framework of teak wood of size 5"x1 1/2" and finished with 1.0 mm thick laminate &amp; 8 mm thick float glass with frost film to be provided between the framework. Glass to have acid etched design pattern with logo as directed. Doors to be mounted on heavy duty floor spring. 1"dia and 15" long brush S.S. finish handle of approved make to be provided. All complete including locks and necessary hardwares such as hinge, stopper, tower bolt etc. Door should include 1st class local wood door frames of size 3"x2.5'" and cover all exposed edge with bidding as directed by EIC. (doors of other sizes will be paid on pro rata basis.)</p>	sqm	3.8		
13	<p>Providing and fixing <b>Semi glazed doors</b> of average size of 3'0"X7'-0" made of top, bottom and side wooden framework of teak wood of size 5"x1 1/2" and finished with 1.0 mm thick laminate 6 mm thick glass to be provided on upper portion between the framework. Glass to have frost film as per design directed. Doors to beequipped with heavy duty door closer. 1"dia and 12" long brush S.S.. finish handle of approved make to be provided. All complete including locks and necessary hardwares etc. Door should include door frames of size 2.5"x2.5'" (doors of other sizes will be paid on pro rata basis.)</p> <p>Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalent</p>	sqm	5.4	Rs. 5,400.00	Rs. 29,160.00
14	<p>Providing and fixing <b>flush doors</b>, 35 mm thick, of average size of 3'0"X7'-0" finished with 1.0 mm thick laminate on both the sides including door frame of size 2.5"x2.5'". Doors to be fixed with heavy duty door closer, with 1"dia and 15" long brush S.S.finish handle of approved make to be provided. All complete including locks and necessary hardwares etc</p>	sqm	3.8	Rs. 4,100.00	Rs. 15,580.00
15	<p>Providing and fixing <b>low height door shutter</b> in back side of SWO counter of average size of 750 mm x 1500 mm and 38 mm thick made of block board of approved brand and quality, finshed with 1 mm thick laminate of approved brand, colour and shade. The door shall includes all hardware such as: lock, handle, tower bolt, door stoper, door coloser, hinge etc. of approve make. All exposed edge shall be covered with teakwood lipping with polishing complete all respect. (doors of other sizes will be paid on pro rata basis.)</p> <p>Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalen</p>	Nos	2	Rs. 4,200.00	Rs. 8,400.00
16	<p><b>Wicket Gate:</b> Providing and fixing Wicket Gate made out of 32 mm flush door finished with 1 mm lamination of approved shade on both sides with all necessary harware such as hinges, tower bolt etc. Complete. The edges shall be finished with beech wood beading polished.</p>	sqm	2.5		

17	Providing & fixing in position Aluminium Composite Panel (ACP) <b>Shutter Boxing</b> with framing of Aluminium Tube section of min 1.5"x1" and 20 gauge 2'-0" C/C both ways. ACP to be in 2' width panels or distributed equally. The Panels to be fixed to the frame with 3M or equivalent adhesive and mirror screws. Joints to be finished with Silicon based sealant. ACP thickness of 3 mm minimum. Aluminium foil thickness to be min 0.20 mm. Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used. Shades to be as per Bank's approval. ACP Trap door will be 12 mm marine ply finished with ACP.	sqm	4		
18	Providing & fixing in position <b>Aluminium Composite Panel (ACP)</b> with framing of Aluminium Tube section of min 1.5"x1" and 20 gauge 2'-0" C/C both ways. ACP to be in 2' width panels or distributed equally. The Panels to be fixed to the frame with 3M or equivalent adhesive and mirror screws. Joints to be finished with Silicon based sealant. ACP thickness of 3 mm minimum. Aluminium foil thickness to be min 0.20 mm. Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used. Shades to be as per Bank's approval. ACP Trap door will be 12 mm marine ply finished with ACP.	sqm	5		
19	Providing and fixing suspended <b>false ceiling</b> with 600x600 mm size Fine Fisher tiles/Gypboard/Minwool/Armstrong and suspenders, frame work as per manufacturer's specifications. With Tagular edges Prima dune plus. The item to include cost of making necessary cut-outs for lights/air-conditioning grills as per design directed. <b>No false-ceiling to be provided in record-room, pantry, stationary and strong-room.</b>	sqm	90		
20	Providing and fixing <b>Vertical Blinds</b> of approved shade, design and texture Vista Levelor/Mac/Eqvt	sqm	14		
21	Providing and fixing floor mounted <b>writing desk</b> of size 4'x1'x3'(H) with 12 mm thick glass on top and voucher pigeon holes as directed, with laminated boards support	nos	1		
22	<b>Stickering with 3M designer film:</b> For SWO counters,UPS-Server Room, BM Chamber, Toilet(G) & Toilet(Ladies)	Set	1		

#### WORKS AT E-LOBBY

23	<b>FALSE CEILING :</b> Grid type :: Providing suspended ceiling at approx. 2450 mm height from floor with 600x600 mm size Fine Fisher Tiles Armstrong make including aluminum frame work and other fixtures as provided by the manufacturer as per specification including one coat of plastic paint wherever required and as directed by Engineer In charge.	sqm	8.5		
24	<b>ACP paneling :</b> Providing and fixing ACP panel with framing of allm. Tube section of min 1.5"x1" and 20G 2' c/c both ways. ACP to be in 2' width panels or equally distributed. Panels to be fixed to the frame with 3M or equivalent adhesive. Joints to be finished with silicon based sealant. ACP thickness min 1mm . Allm foil thickness to be 0.20 mm on both sides. Istrong/Alupan/Alubond/Eurobond/Fujibond/Alcobond or equivalent ISO certified brands to be used. Bright silver shade to be as per Bank's approval. Additional sections to be provided for fixing indoor AC units. Both AC units to be installed near the machine area at the highest position. Rate is inclusive of ACP door to be provided with same specifications of materials as directed.	sqm	18		
25	<b>Main door:</b> PF: Aluminium Main door comprising of approx 83.50mm styles, 85-90 mm top & bottom rails, 8350 mm lock rail black powder coated. Thickness of section not less than 1.5mm. Godrej /Derma/hafele/ingersol Rand/ Insta floor spring for 100 kg wt. and rated for min 0.3 million cycles and pivot on top 8 mm thick clear float glass Modiguard / Saint Gobain Wool pile / Weather strip on one vertical member including CP door handle of approved quality and size to fit on aluminium section . Door size 0.90 m x 2.10 m	Nos	1		
26	<b>Front fixed glazed partition :</b> PF : aluminum openable door comprising of approximate 83.5mm vertical members, black powder coated thickness of section not less than 1.5mm, 6mm clear glass openable with 4 nos 3" SS hinges , tower bolt on top & bottom on the other edge. door size 08.x2.40m and glazed aluminum partition with 8 mm clear glass in black powder coated aluminum frame	sqm	5.980		

27	<b>Louvers</b> : PF: Aircon louvers 600mm x 150 mm of approved colour below false ceiling above back room partition.	Nos	2,000		
28	<b>Shutter Boxing</b> : PF: Shutter boxing with trap door with ACP 3 mm thick fixed to aluminium framing as per specification for ACP panels complete as directed.	sqm	7.5		
29	<b>Intermediate partitions</b> : PF : intermediate partitions between machines from floor up to 1.5m height made with aluminium framework covered on both sides and exposed edges with 8mm thick commercial ply board / MDF board and finished with 1 mm thick laminate sheets of approved colour complete as directed and specified.	sqm	4.8		
30	<b>PF sandwich poster frame</b> of 6mm thick clear acrylic sheet mounted on 4 nos SS studs fixed firmly on the wall at specified position complete as directed and specified. Rate is inclusive of polishing the edges and champhering the corners.	Nos	2		

**TOTAL**

**NB: GST will be extra as applicable**

Note : Design and Detail of the counters shall be as per Bank's engineer at LHO and A.O