

STATE BANK OF INDIA
RBO MADHEPURA

PART-1

(Technical Bid)

**TENDER FOR INTERIOR DECORATION & FURNISHING WORKS AT NEW PREMISES OF AMY FORBESGANJ
BRANCH**

Name of the Tenderer : RBO MADHEPURA (63918)

Address : State Bank Of India, Regional business Office, Region- VI,
Near Railway Station, Madhepura-852113.

GSTIN : 10AAACS8577K2Z3

TENDER NOTICE

SBI RBO Madhepura invites tender in two bid system from interested SBI approved empanelled contractors having enlistment in **Interior & Furnishing Works [Category- 'AAA', 'AA', 'A', 'B', and 'C', (Work value above Rs.5.0 lakh and upto Rs.100.0 Lakh)]** under Patna Circle for undertaking **Interior & Furnishing Works at new premises of AMY Forbesganj Branch** through two bid tendering mode.

1.	Name of Work	:	Interior Decoration and Furnishing Works
2.	Tenders shall remain valid for	:	For a period of 90 days from the date of opening of price bid of tender.
3.	Earnest Money Deposit (EMD)	:	Rs.6900/ in the form of DD from any Nationalised Bank drawn in favour of State Bank Of India, RBO Madhepura. EMD of successful bidder will be converted towards Security deposit. The EMD of unsuccessful bidders will be refunded within 7 (seven) days of issue of work order to the successful bidder.
4.	Security Deposit	:	5% of value of work. The balance amount of Security Deposit excluding EMD will have to be submitted by the Vendor in the form of DD in favour of SBI RBO Madhepura within 7 (seven) days of acceptance of their offer. The Entire Security Deposit(including EMD) will be refunded after completion of defect liability period & satisfactory performance of work.
5.	Time allowed for completion	:	30 days from the date of issue of work order. The selected vendor will have to commence the work immediately on receipt of order.
6.	Estimated Cost	:	Rs.6.90 Lakh (approx)/- + GST
7.	Interim Payment	:	No interim payment will be made. Payment will be made after completion of work after submission of bill and necessary verification by Bank's Engineer.
8.	Availability of Tender Documents	:	Tender documents to be downloaded from the Bank's website www.sbi.co.in under ' Procurement News '
9.	Tender document downloading Start Date	:	From 02:00 P.M. on 06/10/2021
10.	Tender document downloading End Date	:	Upto 02:00 P.M. on 21/10/2021
11.	Last date and Time of submission of Tender	:	Upto 3.00 P.M. on 25/10/2021
12.	Date and Time of opening of Tender	:	25/10/2021 at 3.30 P.M.
13.	Defect Liability Period	:	6(Six) months from date of completion of work.
14.	Liquidated damages	:	0.5% per week of delay subject to maximum of 5% of

			contract value.
15.	Sealed tenders should be submitted within the specified date & time to the office of Regional Manager, State Bank of India, Regional Business Office, Near Railway Station Madhepura-852113.		
16.			
(a)			
(b)	<p>Sealed tenders are invited from the Bank's Empanelled Contractors as mentioned in NIT in two parts, i.e. Cover-I and Cover-II separately. Sealed tenders in two parts i.e. cover-I and Cover-II are to be submitted.</p> <p>(a) Cover-I (Technical Bid): Technical bid envelope shall contain the following documents: (i) Details of EMD. (ii) Technical Bid duly signed & stamped in each page. Cover-I will be opened as per above mentioned date & time in the presence of Tenderers who desire to attend.</p> <p>(b) Cover-II (Price Bid): Shall contain the price offered by the vendor. No condition/stipulation in Cover-II other than unconditional general rebate shall be accepted. Cover-II (Price Bid) will be opened only of those bidders who are successful in Technical Bid(Cover-I) after thorough scrutiny.</p>		
(c)	The Bidder is expected to examine all instructions, forms, terms and specifications in the bid documents. Failure to furnish all information required as per the Bid Documents or submission of bids not substantially responsive to the Bid documents in every respect will be at the bidders risk and shall result in rejection of the bid.		
(d)	In case the date of opening of tenders is declared as a holiday, the tenders will be opened on the next working day at the same time.		



Regional Manager

STATE BANK OF INDIA
SBI ZONAL OFFICE BHAGALPUR

PROJECT: AMY FORBESGANJ BRANCH

SCHEDULE OF WORKS: INTERIOR FURNISHINGS WORK BRANCH

ESTIMATE
RBO Madhepura

PARTICULARS OF ITEMS

S.No.	PARTICULARS OF ITEMS	UNIT	QTY	RATE	AMOUNT
1	<p>BANKING COUNTER</p> <p>Providing and fixing single Window Counters as per drawing & design: The work top shall be 1500 mm long, 900 mm deep & 750 mm high from FFL. The work top is to be fabricated out of 19 mm thick BWP block board up to 700 mm depth towards the front. Thereafter, a double layer of fixed ply (12 mm + 6 mm thick) is to be fixed with necessary fittings to the block board. The fixed ply is to be curved downwards at a distance of 200 mm with a turning radius of 75 mm and stiffened properly to the front modesty panel with appropriate wooden sections. The bottom edge of the fixed ply is to come up to a height of 375 mm from FFL. The front modesty panel is to be made out of 19 mm thick BWP block board and fixed to the bottom of the front edge of work top block board. A 10 mm wide groove with polished finishing at a height of 375 mm from FFL along the length of the front modesty panel is to be made for fixing LED strips. Each counter is to be provided with a 500 mm wide drawer unit, made out of 19 mm thick BWP block board a set of case to accommodate D-7 self-depository cabinet by godrej/Edenair Dimensions 27.25 x 18.125 x 18.125 inches) on front right and one key board in the middle. The left hand side should have 36" credenza made of 19mm thick BWP Phenol formaldehyde, block board with a set of one cub board. The work top is to be finished with 6 mm thick solid surface material, or, 12.0 mm thick high gloss laminate/laminated or approved shade & make on the surface, as directed. All exposed vertical surfaces are to be finished with 12.0 mm thick high gloss laminated or approved shade & make on the surface, as directed. All free edges of block board & plywood are to be finished thick glass with blue etch to be fixed on exposed portion of modesty panel with SS stud fixings. All free edges of block board & plywood are to be finished with white beech wood beading or flapping. The work is to be completed with providing of PVC Ledgeboard tray, CPU tray of approved make & 75 mm dia. PVC wire manager, etc. as directed. Normal vertical glass of 12 mm to be fixed at the front of SMO with one horizontal glass of approx 1' at the top of the vertical glass. To fit these glass steel beading may please be used. The work is to include all necessary materials, accessories, labour, tools & tackle except for only solid surface material on work top, if provided. The job shall be include provisions for electrical, computer & telephone wiring conduits, switch boxes, etc. The fixing of solid surface material on work top only as above shall be a separate item. All materials should be approved by the Bank. Executed running length is to be measured for finished work.</p>	RM	3		
2	<p>FULL HEIGHT PARTITION PARTLY paneled AND PARTLY GLAZED:</p> <p>Providing and fixing double skin partly paneled & partly glazed full height partition with frames of 50 mm x 38 mm (finished size) seasoned hardwood members (Gambhar, Malaysian Sal wood / hollock) at maximum intervals of 450 mm x 450 mm with provision of bigger members at skirting fixing to RCC Slab, skirting, fixing to false ceiling (if provided) fixing to RCC Slab, Beams etc. all wood work to be treated with 1st quality anti-termite paint and covered with 8 mm thick BWP grade plywood at maximum intervals of 450 mm x 450 mm with provision of bigger members at skirting fixing to RCC Slab. Beams etc. are covered with 6mm/8 BWP grade plywood respectively of Green or equivalent ISI marked on both sides and 1mm thick (Greenlam/Century/Archt) laminate and pasted in the same as per typical design, on both sides so as to form a double skin partition to level 900 mm and with 5.0 mm clear back-glass make of glass shall be of Model heat or equivalent above, etched / etching film pasted as per design fixed in frame with steel beading as per detail design, the frame of the partition shall continue right up to ceiling as shall be firmly fixed to the ceiling and ground by means of Renwal plugs etc necessary fasteners so as to form a stable system/ partition all complete work with provision for wiring to be done by other agencies all complete work as per drawing, design, specification and direction of Engineer-in-charge/Bank.</p>	Sq.m	18		
3	<p>FULL HEIGHT NON GLAZED PARTITION:</p> <p>Providing and fixing full height non glazed partition with all other specifications remaining identical to that in item No. 2 above as required and the glazed areas to be replaced by double skin partition of the same specification as exist in the other parts of the same partition - all complete work as per drawing, design, specification and direction of Engineer-in-charge/Bank.</p>	Sq.m	9		
4	<p>LOW HEIGHT PARTITION</p> <p>Providing and fixing low / half height partitions up to 4'-0" with double skin paneling up to 3'-0" and 12 mm thick clear float glass above frame less on the top and sides and sturdy fixed at the bottom on a polished laminated frame all complete job with all other specifications and details to be as per item No. 2 above and as per the design, i.e. shown in slides of low-height counters all complete work as per drawing, design, specification and direction of Engineer-in-charge/Bank. Model heat make or AIS make or equivalent approved by the bank.</p>	Sq.m	16		

5	WOODEN GLAZED DOOR FOR CHAMBERS ROOM ETC Providing and fixing glazed door, all complete as per specifications given in item No. 2 above. Doors shall have separate hard wood crosstubs of 100 mm x 60 mm of sal wood and frames of ganister which shall be of 150 mm x 40 mm at the top and sides and 200 mm x 40 mm at the bottom. Beading shall be given as per typical design and specifications. Door panel shall be of 8 mm thick clear float glass of Modifloat or equivalent approved by the bank. All necessary hardware such as brass hinges (4 nos. heavy quality for each door), door locks, brass tongue bolts and any other hardware required for the door shall be in the nature of Ganister frame shall be newly covered with 6.0 mm BWP ply and 1.0 mm laminate as has been mentioned in item - 2 above of approved brand as has been mentioned at item no. 1 above and as per design. All visible wooden surfaces shall be well polished, all complete work as per drawing, design, specification and direction of Engineer-in-charge/Bank.	Sqm	2		
6	HYDRAULIC DOOR CLOSER Providing and fixing hydraulic heavy-duty, electric or approved make equivalent door closures of heavy-duty, electric or equivalent approved brand and sample - all complete as per instructions of the Bank, all complete work as per drawing, design, specification and direction of Engineer-in-charge/Bank.	No.s	4		
7	GLAZED DOOR AT ENTRANCE IN ALUMINIUM FRAME Providing and fixing main entrance glass in fire rated aluminium sections to be made from INDOAL/INDIAL or equivalent and coloured to a per black all complete including glazing beads, gaskets with suitable heavy sections with 12 mm thick clear float glass/Modifloat or equivalent make beveled with etching / etching film as per design and specifications, all complete with all approved quality of hardware including locks, floor springs, handles etc. as per instruction of the Bank. Section to be used: Top Bottom, side - 9223, Centre 922 (for Glass Area) in doors - Top & Bottom 9206, centre 9219 Centre 9219, all complete work as per drawing, design, specification and direction of Engineer-in-charge/Bank.	Sq.m	2		
8	WORK STATIONS / TABLES (a) Making and erecting Desk-top with provision of work manager having two sides vertical support panels and modesty panel. All made of 18 mm thick BWP grade block board of Green / Century / Mayatarchid top laminated with 1.0 mm laminate of Green / Century / Century / archid. All edges shall be covered as per design and front-edge shall be covered with half round mouldings. Inner portion of table shall be painted with matt black 3 coat of synthetic enamel paint with primer. All wooden surface shall be well finished with melamine/spot polish. (b) Making & providing drawer chest with two drawers and one cupboard with concealed hinges and Goodie multipurpose locks. Box made of 19 mm thick and bottom with 5 mm BWP grade ply of Green/ Century/Samarat Mitra or equivalent front shall be clad with 1.0 mm thick laminate of Green / Century / Archid / Archid edges of drawers and cupboard shall moulded as per drawing/design, specification and direction of Engineer-in-charge/Bank. (c) Providing and fixing key board tray (as per design and specification at 1- above) by and made of PVC / Laminated board on Z shape powder coated runner with PVC soundness rollers. (d) L shaped 1800 mm x 750 mm branch head table as per drawing enclosed with r with high gloss finish on table top, sides, modesty panel and back unit (For Bin)	No.s	1		
9	(ii) L shaped 1500mm x 1680mm x 750 mm table for officer specification as mentioned above.	No.s	4		
9	LOW TYPE STORAGE CABINET MAKING AND FIXING LOW TYPE STORAGE CABINET WITH DRAWER AND CUPBOARD WITH 21 PERCENT DRAWING / DESIGN IN TABLE OR 19 MM THICK BWP BOARD BOARD OR Green/Century / Mayur or equivalent top and front laminated with 1.0 mm laminate of Green/ Mayur / Century/ Archid. Drawer shall run of Z type drawer slides with PVC rollers. All inside portion shall be painted with matt black enamel paint and all wooden surface shall be melamine/spot polish all complete work necessary and required hardware of standard quality, all complete work as per drawing, design, specification and direction of Engineer-in-charge/Bank. Top-1.5' Height-2.6'	Sq.m	4.5		
10	12mm TOUGHENED GLASS etc PROVIDING AND FIXING 12mm TOUGHENED GLASS IN REQUIRED SHAPE AND SIZE AS SHOWN IN THE ENCLOSED DRAWING WITH TRILING PROPERTY WITH TRILING PROPERTY AND TRILING IN POSITION 12 mm thick toughened glass with all necessary hardware as per the site condition as per the prevailing design and specification. All complete work including FLOOR SPRINGS OF GROUND OR HARDWYNN AND HANDLES WITH ALL MATERIALS, LABOR, INSURANCE AND TRANSPORTATION AND AS PER DIRECTION OF E/I (to be provided in e- lobby and counter side)	Sq.m	2		
11	VERTICAL BLIND: Providing & fixing 25mm wide horizontal blind (of a kind or any approved brand) in all windows & opening of chamber. All complete with all mechanisms etc. (Note: The area of the blind shall be measured for payment). All complete work as per drawing, design, specification and direction of Engineer-in-charge/Bank.	Sq.m	4		
12	PANELLING IN WALLS AND COLUMNS P/F panelling with 10mm BWP work with laminate as per item no.1 with GI frame work complete in all respect finally brand of material shall be as above item no.1 at a maximum spacing of 450mm x 450mm C/F. (the spacing shall need to be provided at suitable location ANY COLUMN with 1mm thick laminate of make mentioned at item no.1 above. To be provided at suitable location ANY COLUMN	Sq.m	40		

58/800 KALSHI LUN

13	ALUMINIUM FRAME AT ENTRANCE Providing kind finish 675 mm x 375 mm x 2mm thick anodized aluminium make as above with 7 partition party glassed with pre-tempered board of standard make and quality NOVAPAN, BRITLYN/GREEN and party glassed 15mm thick glass of Wood float or equivalent fastened on rubber channels including all the materials and labours as required for fabrication/installation complete. Materials shall be as per the item no - 7 as above. To be provided at branch entrance TO BE PROVIDED AT BACK AND ST FLOOR ENTRANCE	Sq.m	12		
14	DROP BOX The item is to be provided on the top of the box. The box shall be provided with a small lockable door with 2 no. 75 mm SS ball hinges and a small SS heap bolt. The item is to be made out of 12 mm thick BWR block board to a pigeon hole shape. The work is to be finished with 1mm thick high gloss laminate of approved shade. The inner surfaces are to be finished with French polish. The work is to be completed with necessary lipping & polishing to exposed surfaces. The box shall be fixed to a wall or column in the hall at a height of 1.2 m from FFL or as directed. The work is to include all necessary materials, accessories, labour, tools & tackle. Payment shall be made for finished work. Sources of the following categories are to be provided.	No.S	1		
14(i)	Cheque Drop Box				
15	NOTICE BOARD Providing and fixing notice board made of 19mm block board of H/Green/Century make BWP board with 1.00mm laminates on all exposed portion and painting the unpainted side with coat enamel paint of 1 at quality over one coat wood primer complete with 12mm soft pin board covered with velvet on and glazed operable door in front side with godrej multipurpose lock complete in all respect of size 40"x30"x3" with knob handle all complete.	NO.S	1		
16	SOLID SURFACE MATERIAL ON WORKING TOP Providing, fitting & fixing flexible 6 mm thick Corian Laminare (100% acrylic) CORIAN material of approved make of Du-Pont or equivalent only on table top of SWO, with rounding of edges set to complete job as per drawing & design. Solid surface material is to be fixed with acrylic epoxy adhesive compound including surface & edge finishing and mould. The fitting is to be done on exposed surfaces of SWO table tops, sides, vertical surfaces etc. or any other surface as directed. The job is to be executed through authorized applicator only as per Bank's specifications & requirements. Supporting documents certifying fitting & moulding of the product be only an authorized applicator are to be produced for payment of this item. The work is to be completed with all materials, accessories, labour, Tools & tackle and in strict conformity with manufacturer's specification & recommendations. The job shall also include provisions for electrical, computer, telephone wiring conduits, switch boxes etc. Executed plan area and elevation area of the surface work shall be measured for billing.	Sqm	5.5		
17	GRAHAK MITRAJCI Providing 150mm x 75mm x 6mm thick BWP grade block board of Green/Century brand and make as above mentioned at item-1 above, top laminated with 1 mm laminate or solid surface material on work top only as above all complete work as per drawing design. Specification and direction of Engineer-in-charge/Bank. The fitting of solid surface material on work top only as above shall be a separate item.	No.S	1		
18	GODREJ MAKE DRAWERS OF D-TEL FOR SWO COUNTERS Providing D-TEL box made up of Godrej / equivalent make sliding drawers cabinet with proper locking size 881mm x 460mm x 60mm height of weight 33.0 kg of automatic locking including of cost of labours and material etc. All complete work as per the prevailing standard design specification and direction of bank.	No.S	2		
19	Providing and fixing self adhesive sparkle series frosted film and for one way vision film of make as per design The film are to be pasted on the main glass door and other glasses as directed, cut and fixed as per design including the Bank's Logo. All materials should be approved by the bank. Executed area of film pasted on glasses/canelling shall be measured for finished work.	Sqm	24		
20	Providing Normal glass top for Tables and Side Unit Providing normal glass of 8 mm thickness with edge finished as per the size and shape of the table to be provided on the TABLE top of FO, BW, Service Manager and other as directed E/I to be completed in all respect with proper edge/corner finished include of transportation including and placing.	Sqm	8		

21	<p>FALSE CEILING (GYPSUM BOARD)</p> <p>Providing and fixing at all height false ceiling with required droplights and pattern of 12.5mm thick tapered edge Gypsum board conforming to IS: 2085 including and providing of frame work made of special sections pane pressed from MS sheet and, galvanized in accordance with zinc coating 800 as per IS:217 and providing of angle steel of size 25mm wide x 1.5mm thick with flanges of 22mm and 17mm at 900mm centre to centre one range to ceiling with dash hanger 12.5mm x 40mm long with 5mm dia bolts to the angle hanger of 922mm centre to centre to which the ceiling section hanger being fixed with nuts and bolts to G.I. Channels 45 x 45 x 10.5mm having depth of 10.5 mm dia at 450mm c/c shall be fixed in a direction perpendicular to 0.1 channel with connecting clip made out of 2.84mm dia x 230mm long G.I. Wire at every junction including fixing the gypsum board with ceiling section and perforated channels 0.25mm thick 0.27mm high having range of 20mm and 30mm long perforator or ceiling board as specified with help of raw plugs at 450mm c/c with 25mm long drive all screw @200mm interval including jointing and fixing to a flush finish of wall/partition with help of raw plugs at 450mm c/c with recommended filler, paper tapes, finisher and two coat of primer suitable for gypsum board as specified and square edges of the gypsum board with recommended filler, paper tapes, finisher and two coat of primer suitable for gypsum board as specified and direction of EJ. This rate is inclusive of two more coat of plastic emulsion of approved make shade and coat of primer, putty per manufacturer specifications and also including the cost of making opening light fittings, diffusers, grills, cutout made with frame of perforator gypsum partition ceiling members. TO BE PROVIDED IN THE PERIPHERY OF THE ROOM OF APPROX 2' WIDTH WITH REQUIRED DROPPINGS. Measurement will be done for the width and drop as applicable.</p>	Sqm	50	
22	<p>FALSE CEILING (MINERAL FIBER)</p> <p>Providing and fixing of Armstrong's Mineral fibre Acoustical False ceiling tiles of type Prima Fine Fibrous RH-90% of approx. size 600mm x 600mm x 15mm with regular edge at all heights laid on Armstrong's Prestrate XL Hot dipped galvanized exposed grid with 15 m with T-Section exposed hangers which shall be powder coated white. The framework will comprise of main Runner made from 0.33 mm thick GS sheet and of size 24 mm x 38mm x 260 mm and spaced at 1200 mm centre to centre separately fixed to the structural steel by approved hangers at 1200 mm maximum centre. Hangers (GS wire of 4.0 mm dia) to be fixed by approved Rawl plug, level adjusters and screws etc. all complete work as per drawing design, specification and direction of Engineer-in-charge Bank.</p> <p>The last hanger at the end of each main Runner should not be greater than 450 mm from the adjacent wall. Flush fitting of 1200 mm long cross tee (with double slitting) to be interlocked between main Runners at 600 mm centre to form 1200 mm x 600 mm modules. Cut cross Tees longer than 600 mm to be supported independently. 600 mm x 600 mm modules top to be formed by fitting 600 mm x 600 mm modules of size 22 mm and 3000 mm long cross Tees centrally between the 12 mm cross Tee. Fastener wall Angle shall be of 0.45 thick GS steel and of size 22 mm and 3000 mm long of white colour.</p> <p>The work shall be as per standards and specifications laid down by the manufacturers. Full provision of weight of wire during (if provided) and light fittings, wiring for any use, including co-ordinating with all trades and making any cutouts required for the same, all complete with a minimum of 2 coats of premium quality Acrylic emulsion paint and full finishing for light fittings all complete work as per drawing, design, specification and direction of Engineer-in-charge Bank.</p>	sqm	98	
				TOTAL
	<p>(1) RATES ARE INCLUSIVE OF SHALL BE QUOTED BY CONTRACTORS INCLUSIVE OF) All costs, less, allowances, charges, levies, transportation, cost of labor and materials all inclusive etc but excluding GST, as applicable which will be added as per government norms prevailing from time to time.</p>			
	(ii) QUANTITIES AND ITEMS MAY VARY /CHANGE AS PER THE SITE CONDITION AND REQUIREMENT OF THE BRANCH HOWEVER AS PER DIRECTION OF THE BRANCH/RBO/BE/BANK			
	(iii) MAPS ARE ENCLOSED, THE SINO COUNTER TOP SOLID TOP BASED ON THE REQUIREMENT AND AS PER INSTRUCTION OF EIC OR RBO.			
	(iv) CODE OF SAFETY AND GUIDANCE, ARE ENCLOSED			
	(v) COPY OF TERMS AND CONDITIONS ARE ENCLOSED			
	(vi) THE COLOUR PATTERN SHOULD BE AS PER NEW TYPICAL DESIGN ENCLOSED			