

PRICE BID

INTERIOR & FURNISHING WORK OF RBO MUNGER

Sl.	Particulars of Items	Unit	Quantity	Rate (Rs.)	Amount
1	<p><u>FULL HEIGHT GLAZED PARTITION</u> <u>PARTLY GLAZED FULL HEIGHT PARTITIONS:</u> Providing and fixing in position Full Height Partition (up to instructed level) consisting of un-anodized aluminum hollow section of 50x50mm size 1.5mm thick of JINDAL/INDAL confirming to ISI 303 standard as internal frame structure placed horizontally & vertically in 600 x 600mm interval , except skirting member which shall have 2x50x50mm members at reqd. spacing and 6mm wide grooves or as required as per architectural drawing.(c/c distance to be adjusted as per drawings, door/opening positions). The framing shall be fixed with 8mm thick BWR grade ply (of approved / equivalent make) firmly screwed to the aluminum frame on both side. The board surface so prepared shall be pasted with 1.0mm thick laminate of approved premium shade or texture finish in approved pattern, make & color. Partition shall be glazed up to 7.0 ft ht. above the 0.50 ft ht. from floor level . Glazed portion of partition shall be done with 12 mm toughened glass of approved make with etching work (acid wash) as per design& position approved by engineer-in-charge. Glass is to be fixed in with steam beech wood moulding of 25mm x12mm on partitions. Additional steam beech wood is required for making grooves providing 65x31mm beading on it. Item also includes providing and fixing 100mm wide skirting of 1mm thickness. Metallic Laminate as per approved sample on exposed partition surface as per architectural drawings. Vertical and horizontal groves as per drawing /site conditions. Design / pattern of partition shall be as per approval of engineer-in-charge. cost to include cost of silicon filling ,providing and applying melamine finish on wood surface/grooves including providing and applying 2-3 coats of VIPER over a coat of anti-termite paint where ever required. All work to be completed as per drawing, design. Specification and direction of Engineer-in-charge /Bank.</p>	SQM	22.00		
2	<p><u>FULL HEIGHT SOLID PARTITION</u> Providing and fixing in position Full Height Partition (up to instructed level) consisting of un-anodized aluminum hollow section of 50x50mm size 1.5mm thick of JINDAL/INDAL confirming to ISI 303 standard as internal frame structure placed horizontally & vertically in 600 x 600mm interval , except skirting member which shall have 2x50x50mm members at reqd. spacing and 6mm wide grooves or as required as per architectural drawing.(c/c distance to be adjusted as per drawings, door/opening positions). The framing shall be fixed with 8mm thick BWR grade ply (of approved / equivalent make) firmly screwed to the aluminum frame on both side. The board surface so prepared shall be pasted with 1.0mm thick laminate of approved premium shade or texture finish in</p>	SQM	28.00		

	<p>approved pattern, make & color. Additional steam beech wood is required for making grooves providing 65x31mm beading on it. Item also includes providing and fixing 100mm wide skirting of 1mm thickness. Metallic Laminate as per approved sample on exposed partition surface as per architectural drawings. Vertical and horizontal grooves as per drawing /site conditions. Design / pattern of partition shall be as per approval of engineer-in-charge. cost to include cost of silicon filling ,providing and applying melamine finish on wood surface/grooves including providing and applying 2-3 coats of VIPER over a coat of anti-termite paint where ever required. All work to be completed as per drawing, design. Specification and direction of Engineer-in-charge /Bank.</p>				
3	<p>WOODEN GLAZED DOOR FOR CHAMBERS ROOMS ETC: Providing and fixing glazed door, all complete as per specifications given in item No. 2 above. Doors shall have separate hard wood chowkhats of 100 mm x 60 mm of Sal wood and frames of Gamhar wood which shall be of 150 mm x 40 mm at the top and sides and 200 mm x 40 mm at the bottom. Beading shall be given as per typical design and specifications. Door panel shall be of 8 mm thick clear float toughen glass of Modi float or AIS make or equivalent approved by the bank. All necessary hardware such as brass hinges (4 nos. heavy qualities for each door), door locks, brass tower bolts and any other hardware required for the door shall be in the rate. Gamhar frame shall be neatly covered with 4.0 mm BWP ply and 1.0 mm high gloss laminate as has been mentioned in item – 2 above of approved brand as has been mentioned at item no.1 above and as per design. All visible wooden surfaces shall be covered with premium quality laminate. All work to be completed as per drawing, design. Specification and direction of Engineer-in-charge /Bank.</p>	SQM	5.85		
4	<p>LOW HEIGHT PARTITION Providing and fixing low / half height partitions up to 4' 0" with double skin paneling up to 3'-0" and 12 mm thick toughened glass of approved make above frameless on the top and sides and sturdily fixed at the bottom on a polished teakwood frame all complete job with all other specifications and details to be as per item No. 2 above and as per the design i.e. shown in sides of low-height counters all complete work. All complete work as per Corporate Centre, Mumbai approved materials Colour & Laminate etc and specifications and direction of Engineer-in-charge /Bank.</p>	SQM	66.00		
5	<p>WORK STATIONS / TABLES (a). Making and erecting Desk-top with provision of wire manager having two sides vertical support panels and modesty panel. All made of 19 mm thick BWP grade block board of Green / Century /Mayur</p>				

	<p>or equivalent top laminated with 1.0 mm laminate of Green/ Marino / Century or equivalent. All edges shall be covered with teak wood lapping and front-edge shall be covered with half round molding. Inner portion of table shall be painted with matt finish 3 coat of synthetic enamel paint with primer. All wooden surfaces shall be well polished with melamine/sprit polish.</p> <p>(b) Making & providing drawer chest with two drawers and one cupboard with concealed hinges and Godrej multipurpose locks. Box made of 19 mm thick and bottom with 6 mm BWP grade ply of Green/ Century or equivalent front shall be clad with 1.0 mm thick laminate of Green lam / Century or equivalent side edges of drawers and cupboard shall molded in round shape with Gamhar wood. All drawers shall have 'Z' shape powder coated MS runners with PVC sound less rollers. All work to be completed as per Corporate Centre, Mumbai approved materials Colour Laminate and specifications and direction of Engineer-in-charge /Bank.</p> <p>(c). Providing and fixing key board tray (as per design and specification at 1- above) try and made of PVC / Laminated board on 'Z' shape powder coated runner with PVC soundless rollers.</p> <p>(i) 1800 mm x 900 mm x 750 mm(For CMs) with side unit 900x450x750</p> <p>(ii) 1350 mm x 750 mm x 750 mm(For Managers and other officers) with side unit 900x450x750</p> <p>(iii) 1200x600x750 mm(For Assistants) with side unit 900x450x750</p> <p>All complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank.</p>				
6	<p>HYDRAULIC DOOR CLOSER Providing and fixing hydraulic Hardwyn, Everite or approved make equivalent door closures of Hardwyn, Everite or equivalent approved brand and sample – all complete as per instructions of the Bank. All work to be completed as per drawing, design. Specification and direction of Engineer-in-charge /Bank.</p>	Nos.	3		
7	<p>12 MM THICK TOUGHENED GLASS DOOR ETC Supplying and Fixing of fully glazed Door (in single / double leaf shutter) at approved position. The door shall be made of 12 mm thick toughened float glass & the glass shall be fitted with Patch Fittings of approved make. The door shall be fixed on approved make floor</p>	SQM	8.45		

	spring and with 2 Nos. of 18 inch S.S. handles, one dead lock with three keys, its fittings and fixtures, computerized vinyl push/pull sticker etc. complete all of approved make. The 12 mm thick glass shall have etching work (acid wash) done on it as per the drawing/ approval. Door handle shall be of Kich Industries make, stainless steel, AISI 316 grade pull handles, 22 mm dia x 450 mm STAIN CODE PHI 2212 S and shall be fixed in position. The cost to include all fixtures, 6 lever Godrej lock, push/pull stickers, Labour etc. complete. All work to be completed as per drawing, design. Specification and direction of Engineer-in-charge /Bank.				
8	<p>EXECUTIVE WORK STATION (WITH LAMINATE)</p> <p>Manufacturing and supplying ' L ' shaped Executive work station consisting of a table made with necessary 19mm Plywood (of approved / equivalent make) frame work having 16" wide and 2.0' deep storage unit on one side consisting of Four 5" deep sliding drawers and a modesty panel with embossed design. The table frame work shall be of over all size of 7.0' x 3.0' x 2.5' and it shall be fitted with 12mm glass on it's top. There shall be a side unit of 4.0' x 1'-6" x 2'-6" over all size made with 19mm Plywood (of approved / equivalent make) frame work having 3nos. of 5" deep drawers on upper side and below to drawers, the cupboard unit shall be with folding shutter & adjustable shelf all along the full width of the credenza. <u>In the table.</u> Arrangement of CPU stand, key board drawer, cable manager and foot rest of 4" x 1.5" teak wood section shall be provided and the three edges of front fascia shall be 1.5" thick with additional ply and leaped with necessary beach wood beading of same thickness melamine polished to same colour as veneer.. All drawer shall be fitted with telescopic channels and automatic push type locking arrangement and cupboards shall have locking arrangement and all exposed edges of ply wood shall be fitted with teak wood beading duly polished. All bidding shall have polish of matching color. All exposed and visible surfaces shall be laminated with 1.5 mm thick laminate of approved regular shade/ 1.0mm thick laminate of approved premium shade and make and all invisible surfaces to be laminated with 0.8 mm laminate of approved shade and make. The rates should include locking arrangement (to be operated by single key) for all drawers and cupboard along with best quality 4" brush steel handles, sliding channel with roller + ball bearing arrangements etc. complete. Cost should also inclusive of paneling, lapping of edges with plywood to achieve thickness etc. All work to be completed as per drawing, design. Specification and direction of Engineer-in-charge /Bank.</p>	No.	1		
9	<p>FOOT REST:</p> <p>Providing and placing foot rest made of 19 mm BWP grade block board with wooden lippings top clad with rubber mat. All inner portions shall have a coat of mat finish enamel paint all complete work as per drawing, design. Specification and direction of Engineer-in-charge</p>	Nos.	31		

	/Bank.				
10	<p><u>LOW TYPE STORAGE CABINET:</u> Manufacturing, supplying and fixing of box type cupboards / storage units of required, sizes and as shown in the drawing and of 1' 6" depth and made out of 19 mm thick Plywood (of approved / equivalent make) all-round and 8 mm Plywood (of approved / equivalent make) at the back. The 19mm Plywood shelves / compartments shall be provided at 15" c/c horizontally and 3' 0" c/c vertically. The unit shall have hinged type shutters on the front made out of 19 mm Plywood with approved quality concealed hinges, locks tower bolts, knobs all as per approved quality. All external surfaces to be laminated with 1.5 mm thick laminate of approved regular shade/ 1.0mm thick laminate of approved premium shade or texture finish and all internal surfaces to be laminated with 0.8mm thick laminate of approved shade & make. Front edges of shelves and all exposed edges of plywood to be leaped with teak wood finished with polish. Footing to be made of 2.5" x 1.5" teak wood frame covering all four sides of bottom surface and covered with 6 mm Plywood of approved make and 1.5 mm thick laminate of same shade. cost to include providing and applying melamine finish on wood surface/grooves including providing and applying 2-3 coats of VIPER over a coat of anti-termite paint where ever required. All work to be completed as per drawing, design. Specification and direction of Engineer-in-charge /Bank.</p>	SQM	32.00		
11	<p><u>FALSE CEILING.</u> Providing and fixing of Armstrong's Mineral Fiber Acoustical False ceiling tiles of type Prima Fine Fissured RH-99% of approx. size 600mm x 600mm x 12mm with square / tegular edge at all heights laid on Armstrong's Prelude XL Hot dipped galvanized exposed grid with 15 m with T-Section exposed flingers which shall be powder coated white. The framework will comprise of main Runner made from 0.33 mm thick GS sheet and of size 24 mm x 38mm x 3600 mm and spaced at 1200 mm centre securely fixed to the structural soffit by approved hangers at 1200 mm maximum centre. Hangers (GI wire of 4.0 mm diameter) to be fixed by approved Rawl plug, level adjusters and screws etc. All complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank. The last hanger at the end of each main Runner should not be greater than 450 mm from the adjacent wall. Flush fitting of 1200 mm long cross tee (with double stitching) to be interlocked between main Runners at 600 mm</p>	SQM	235.00		

	<p>centre to form 1200 mm x 600 mm modules. Cut cross Tees longer than 600 mm to be supported independently. 600 mm x 600 mm modules top be formed by fitting 600 mm x 600 mm modules to be formed by fitting 600 mm long cross Tee centrally between the 12 mm cross Tee. Perimeter wall Angle shall be of 0.45 thick GS Steel and of size 22 mm and 3000 mm long of white color. The work shall be as per standards and specifications laid down by the manufacturers. Full provision of weight of a/c ducting (if provided) and light fittings, wiring for any use, including co-coordinating with all trades and making any cutouts required for the same, all complete with a minimum of 2 coats of premium quality Acrylic emulsion paint and full finishing for light fittings all complete work as per drawing, design., specification and direction of Engineer-in-charge /Bank.</p>				
<p>12</p>	<p>GYPSUM FALSE CEILING</p> <p>Providing and fixing in position Seamless Gypsum Board False Ceiling in one or more levels as directed including vertical surfaces between different levels.</p> <p>The Ceiling including vertical surfaces is to be done with 12.5 mm thick plain Gypsum boards of approved make, duly finished with recommended filters, tapes, etc. to have a seamless flush look. The ceiling system is to be fixed to a concealed GI framework (Gypsteel Ultra make or approved equivalent) by 25 mm long GI drywall screws at 250 mm intervals along both ways. The framework shall be suspended securely from MS angle hangers fixed to true ceiling surface by dash fasteners. The whole system is to be fitted with all necessary arrangements like perimeter channels, intermediate channels, ceiling sections, ceiling suspension angles, rawl plug, soffit cleat etc. The work includes applying two coats of approved putty & primer suitable for Gypsum boards after necessary surface preparation and final painting with approved acrylic emulsion paint on the surface.</p> <p>Provisions for openable type lids for facilitating arrangements for rolling shutters are to be made as required. Lids shall be made out of 9 mm thick BWR plywood duly painted to match the ceiling surface and provided with 2 No. 75 mm SS butt hinges & 1 No. 100 mm SS tower bolt along the surface. The work is to be completed with all materials, accessories. Labour, tools & tackles and in strict conformity with manufacturers specifications & recommendations. Rate is to include the cost of making openings for ceiling mounted electrical & air-conditioning accessories. All work to be completed as per drawing, design. Specification and direction of Engineer-in-charge /Bank.</p>	<p>SQM</p>	<p>112.00</p>		

13	<p>SPARKLE FROSTED FILM</p> <p>Providing and fixing self adhesive Sparkle series Frosted Film and/or one way vision film of 3 M make as per design approved. The film has to be pasted on glasses surfaces as directed, cut & fixed as per design including the Bank's logo. supporting Invoice/bills are to be produced for payment of this item including certificate from the dealer certifying use of the product. All work to be completed as per drawing, design. Specification and direction of Engineer-in-charge /Bank.</p>	SQM	40.00		
14	<p>WOODEN CLADDING – A Type</p> <p>Providing and fixing Wall / column Paneling (up to instructed level) consisting of un-anodized aluminum hollow section of 50x50mm size 1.5mm thick of JINDAL/ INDAL confirming to ISI 303 standard as internal frame structure placed horizontally & vertically in 600 x 600mm interval (as per site requirement). The framing shall be fixed with 8mm thick BWR grade ply of approved / equivalent make firmly screwed to the aluminum frame on exposed side and further on thus prepared surface an additional layer of 4mm thick BWR grade ply of approved make shall be pasted in order to give the designed groove pattern. Thereafter the final raw surface shall be finished with 1mm laminate of approved premium shade or texture finish. Item includes providing and fixing 100mm wide skirting of 1mm thick mettalic laminate as per approved sample and Vertical and horizontal grove/ Design / pattern of cladding shall be as per drawing/ approval of engineer-in-charge. Cost to include all material and Labor charges. and applying 2-3 coats of VIPER over a coat of anti-termite paint where ever required. All work to be completed as per drawing, design. Specification and direction of Engineer-in-charge /Bank.</p> <p>(a) Interior columns</p> <p>(b) Chamber of Regional Manager</p> <p>© Conference Room</p>	SQM	60.00		
		SQM	14.00		
		SQM	45.00		

15	ROLLER BLINDS : Providing & fixing roller blinds (vista level or classic/ or equivalent of standard make) in off-white or any approved color on windows & opening of chamber. All complete with all mechanisms etc. (Note: The area of the blinds shall be measured for payment). All work to be completed as per drawing, design. Specification and direction of Engineer-in-charge /Bank.	SQM	40.00		
16	Providing & fixing U shaped Conference table with 19 mm thick BWP Phenol Formaldehyde block board of Green/Century/Mayur or equivalent with a teak wood beading 50 mmx 38 mm in front and necessary beading to cover all the exposed edges of board etc. The vertical supporting members of counter etc are to be made of 19 mm thick BWP Phenol Formaldehyde block board of Green/Century/equivalent. The table top has a neat hole to be made in the table for connecting the wires which is to be covered with dark coloured PVC insert(wire manager) with moveble parts to put the wires and sockets to cover the hole neatly. The exposed block board/plywood to be covered with 4.0 mm thick veneer of approved shade and colour with PU polish. The internal and non-visible side of tables shall be painted with 3 coats of enamel paint over one coat of primer on the internal side. The table to be completed as per drawing and direction.	METRES	16.50		
17	LAMINATED WOODEN FLOORING/SKIRTING Providing, fitting and fixing laminated wooden flooring of grade AC-6 (manufacturer's certificate and documentary evidence to be attached), including full preparation of sub-base, as required, skirting, all accessories, all complete, in specified shade, texture and colour, fully complete, as per instructions . 8mm thick of green/vista or approved equivalent. In the chamber of Regional Manager and Conference Room	SQM	80.00		
TOTAL					

GST Will be paid extra as applicable

Place: -

Signature of the vendor

Date:-

