

| SL.NO. | PARTICULARS   | QTY. | UNIT | RATE | AMOUNT |
|--------|---|------|------|------|--------|
| 1      | Each drawer/Cabinet, the fascia shall be made out of 19mm thick plywood of make like GREEN/CENTURY/ or equivalent of grade of boiling water proof and moisture resistant) with laminate on both sides It shall be mounted on approved quality, high precision soft closed telescopic channels(REQUIRED NO OF sets per kitchen) of make Kaff,Hettich, Hafele or approved equivalent of 45 kg capacity to be designed as per drawer size and to meet the weight requirement with minimum length of 20 inch to ensure smooth movements of drawer with/without content weights.The telescopic channel rails may be provided as per specifications. (BASE CABINET)   | 45   | SFT  |      |        |
| 2      | ,Providing and fixing a minimum of 2 nos of plain baskets((size-19x20x4), 2 nos of plain baskets((size-19x20x6), 2 nos of plain baskets((size-19x20x8),1 no. of cutlery basket (size-19x20x4),1 no of basket for cup & saucer (size-19x20x4), 1 no of basket for thali (size-19x20x4),1 no of basket for Bottle pullout (6" size),1 no. of detergent holder, 1 no. of Dustbin Holder,or as per requirement all make of Kaff,Hettich, Hafele or approved equivalent of 45 kg capacity as per standard with all complete job  | 1    | SET  |      |        |
| 3      | Supplying pre-fabricated/factory made or made at site overhead kitchen wall units above main kitchen platform having box type overhead units approx.length of 2000 mm ( in two parts ) and 700 mm height and 325mm depth as per the following specifications and enclosed sketches.The frame work or carcassof the cabinetsincluding fascia/sides /bottom, shelves etc. shall be made out of 19mm thick marine plywood (of make like Green ply/Century Ply/ Kit ply or equivalent of grade of boiling water proof and moisture resistant) with laminate of inside of 0.8 mm and 1.0 mm laminate of glossy finish Panel Doors(Approx15SQFT per Kitchen)shall be made out of 19mm thick plywood with glossy finish of make like greenlum/century or equivalent of grade of boiling water proof and moisture resistant.Panel Doors also having provision of Fixing of 6 mm transparent glass with provision of inside light to controlled with the opening of Doors.Each shutter shall be fixed to the framework using two numbers of soft close auto hinges of make Hettich, KAFFor approved equivalent make and Handle G profile (Approx 7 feet per kitchen) of reputed approved make.(TOP CABINET | 25   | SFT  |      |        |

|    |   |     |        |  |  |
|----|---|-----|--------|--|--|
| 4  | PROVIDING / FIXING OF CHIMENY 90CM SUCTION OF 1200M3/HR AUTO CLEAN MAKE OF KUTCHINA, SUNFLAME , PRESTIGE MAKEWITH ALL COMPLETE JOB AS DIRECTED BY EIC   | 1   | SET    |  |  |
| 5  | PROVIDING / FIXING OF ADDITIONAL PIPE FOR OUTER OF CHIMENY WITH ALL COMPLETE JOB AS DIRECTED BY EIC   | 6   | . MTR. |  |  |
| 6  | Providing and laying Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturer) of ist quality conforming to IS :15622 of approved make in colours such shades except white , Ivory ,Grey , Fume Red , Brown , laid on 20 mm thick Cement motar 1:4 (1cement: 4 coarse sand) including pointing the joints with white cement and matching pigment etc., complete.(MAKE AS PER APPROVED BY SBIIMS LIKE NITCO , , SOMANY , KAJARIA) with all complete job  | 15  | sqm    |  |  |
| 7  | Providing two or more coats of Plastic emulsion paint over a coat of cement primer of ICI, Berger Paints (India Ltd, Jenson & Nicholson (India) Ltd, Shalimar Paints Ltd and Asian – do – to complete job   | 35  | sqm    |  |  |
| 8  | Providing and applying wall putty of 2 mm average thickness over plastered & white washed walls & ceiling to prepare the surface even and smooth complete as per direction of SBIIMS  | 35  | sqm    |  |  |
| 9  | Providing new concealed electrical wiring for additional points from existing switch board for 04 nos. Kitchen 5/15 Amp power socket point, 3 nos. 5 Amp Socket   | 1   | UNIT   |  |  |
| 10 | Providing and fixing aluminium work for Glazed (6mm thick toughen glass )SLIDING windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS:1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass /stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. | 3.5 | sqm    |  |  |
| 11 | Dismantalling old material and old cabinet in kitchen and tiles including the cost stacking and disposal and cleaning with all complete job as directed by EIC lead upto 100m   | 1   | LS     |  |  |

|     |   |       |     |  |  |
|-----|---|-------|-----|--|--|
| 12  | Providing and laying RCC OF 1:1.5:3 cement sand coarse aggregate at the eddge of drainage line or wherever required as per site condtion including the cost reinforcement,shuttering deshuttering curing and with all complete job as directed by EIC   | cum   | 3   |  |  |
| 13  | Providing and laying 80mm thick faciory made cement concrete interlocking paverblock of M -30 grade made by block making machine with strong vibratory compaction, of approved s;ze, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc including the cost of dressing and after test of paver blocks from a govt engineering college . all complete as per the direction of Engineer-in-charge. | sqm   | 325 |  |  |
| RS. |   | TOTAL |     |  |  |
|     |   |       |     |  |  |
|     |   |       |     |  |  |

NOTE:-

\* ABOVE PRICE IS EXCLUDING GST.

\* GST PAID EXTRA BY THE BANK AS PER RULE.