

1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres Lead : With cement mortar 1:4 (1 cement : 4 fine sand)	Sqmt.	387		
2	External weather resisting 100% premium acrylic emulsion painting of surface with VOC less than 50gm/litre as per IS15489,siliconbase,alkali resistant,fungal resistant,dampness resistant with topcoat,basecoat,sealer filling and primer minimum warranty of 7 Years including cost of spider jhoola or steel prop Scaffolding (as the case maybe)	Sqmt.	10652		
3	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqmt.	700		
4	Cleaning the surface and removing vegetation dirt,dust ,bird dropping, including providing,including providing,applying and washing the surface withliquid Ammonia Chemical of 5% solution and other chemical cleaning agent	Sqmt.	287		
5	French spirit polishing : One or more coats on old work	Sqmt.	641		
6	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of thickness 4 mm	Sqmt.	91		
7	Cleaningthesurfaceandremovingdirt,dust,birddropping,includingproviding,includin gproviding,applyingandwashingthesurfacewithliquidAmmoniaChemicalof5%soluti onandotherchemicalcleaningagentasapprovedbyArchaeologicalSurveyofIndia/E ngineer-in-charge,of approved brand and manufacturer,withthe helpofrequiredscrubbersandalsocleaningwithmachineoperatedwaterjetmixedwit hdesiredquantityoffine silica wherever required,without causing any scratching/damagetothefaceandfinallywashingthesurfacewithcleanwaterwith thehelpofpressurejetmachine,completeinallrespect,includingtakingallprecautionst osafeguardventilators,windows,doorsetc.bysuitablecoveringsoastoavoidanydama getothebuilding/structure,allasper direction of Engineerin-charge	Sqmt.	10652		
GRAND TOTAL					