

BILL OF QUANTITIES FOR INTERIOR FURNISHING WORKS AT STATE BANK OF INDIA ,MAIN BRANCH, HISAR.					
	Item of Work	Qty	Unit	Rate	Total Amount
1	Providing and fixing top with Curvilinear profile on existing single window counter made out of 19mm thk. commercial block board and finished with 6mm thk. flexi ply as base including Providing and fixing (12mm thick) white acrylic stone (non-absorbent, non-porous solid surface composite material, belonging to the solid surface category) : Glacier White ., Dupont make as per drawings/design with provision for LED Light in bottom.providing by the Architects complete in all respect including buffing and wastage.	17.00	Sq.mt		
2	12 MM thk. toughend glass for Banking / SWO Counters with Etching. - front & Sides. Providing and fixing 12 mm thick, clear plain toughend glass of fixed in vertical position at counter level & to side partitions as per drawing, the counter top glass fixed on both sides to toughned glass partitions & side partitions fixed to wooden partition with superior quality stainless steel L - shaped clamps / glass holders 2 no. on both sides. A 6" dia. semi circular hole at the bottom for transaction shall be provided. All the edges of the glass shall be grinded polished and left free.	20.00	Sq.mt		
3	Superior quality stainless steel L - shaped slamps / glass holders 2 no. on both sides to holding the front glass partition to S.W.Counter.	12.00	Nos		
4	Re-lamination of Single Window Counters., Officer's & Staff Tables Re-lamination of Exiting Tables made of 19 mm thk. Commercial ply with front and side visible vertical surfaces to be finsihed with 4mm commercial ply and cladded with laminate 1mm thick (of approved shade).The work includes providing and fixing all required hardware i.e.handles, lockes,drawers channels etc and teak wood margins/pvc tape as and where required complete in all respects as per the instruction and satisfaction of the Engg. in charge /Architect. NOTE: ALL TABLE TOP SHALL BE AS PAID EXTRA.				
a	Size 7'0" X 3'0" X 2'6"	1.00	Nos		
b	Size 6'0" X 3'0" X 2'6"	2.00	Nos		
c	Size 5'0" X 2'6" X 2'6"	14.00	Nos		
5	Re-lamination of Workstations Re-lamination of Exiting Workstations made of 19 mm thk. Commercial ply with front and side visible vertical surfaces to be finsihed with 4mm commercial ply and cladded with laminate 1mm thick (of approved shade).The work includes providing and fixing all required hardware i.e.handles, lockes,drawers channels etc and teak wood margins/pvc tape as and where required complete in all respects as per the instruction and satisfaction of the Engg. in charge /Architect. NOTE: ALL TABLE TOP SHALL BE AS PAID EXTRA.	12.00	Nos		
6	8.0 MM thk glass on top of officers tables. All the edges of the glass shall be grinded polished including Hole for cable manager.	25.00	Sq.mt		
7	Post Forming Table Top: Provding and fixing Post forming Table Tops in approved share laminate including all hardware and also providing wire manager with hole. The work includes removal of existing table tops and disposal of same to Contractors own dump.	40.00	Sq.mt		

	Item of Work	Qty	Unit	Rate	Total Amount
8	Wall Paneling (Re-lamination) Providing and fixing 4mm thk. commercial ply over exiting wall panelling/storage cabinets/side credenza/doors/Partitions etc and finishing with 1mm thk. approved shade laminate., complete with grooves etc as per design. The work also includes replacement of top teak wood beading/PVC tape with new beading/tape as desired and polishing as desired.				
i.	Panelling with laminate	260.00	Sq.mt		
9	Wall Paneling (with teak ply) Providing and fixing 4mm thk. commercial ply over exiting wall panelling/ceiling and finishing with 6mm thk. approved shade teak ply including esprit polishing, complete with grooves etc as per design. The work also includes removal of existing teak ply and disposal of same to contractors own dump.				
i.	Panelling with Teak Ply _Make: Greelam/Times/Sonear Basic Price @ 65/- sq.ft	130.00	Sq.mt		
10	Roller Blinds of Vista Make- IceLand Series	30.00	Sq.mt		
	Providing & Fixing Roller Blinds of Vista make- Iceland Series made of Translucent fibre glass fabric of approved shade including 32mm round channel and mechanism and other fitting fixed in position as per manufacture's specification, complete in all respects to the satisfaction of Architect/Engineer in Charge.				
11	Frosted Film				
	Providing and fixing 3 M make decorative film on glass of approved shade as per architect's instruction with grooves etc. all completed. Note Actual area of film installed will be measured and paid . No wastage will be considered	20.00	Sq.mt		
12	MDF JALI				
	Making and fixing in position (as per approved sample) Laser Cut Jaali partition to be made out of MDF board of 4mm. thickness and sandwiched in 4mm thk. glass from both sides. All exposed surfaces to be finish with clear gloss Verinlengo paint as per approved shade . All complete as/ design to the entire satisfaction of Architect/ Engineer in charge (Elevation area to measure).	12.00	Sq.mt		
13	Lacquered Glass panels on SS studs : Providing and fixing 6mm thick Lacquered glass fixed with SS studs and Dow Corning make Neutral Silicone sealant 896 over the frame of 12mm thk. Comm.ply fixed against the wall as panelling as per the drawing to complete satisfaction of the Architect/Bank Engg. in charge.(Make: Saint gobain/AIS)	6.00	Sq.mt		
14	Door Closer - Providing and fixing silver colour (or matching with colour scheme as per site) hydraulic door closer Godrej / Hyper / Everrite make, to Doors complete in all respects.	4.00	Nos		
15	Mortice Lock -Providing and fixing silver colour (or matching with colour scheme as per site) Godrej make to Doors complete in all respects.	2.00	Nos		
16	Writing desk / Customer Voucher Stand / Forms Stand including Pass Book, Cheque Drop & Suggestion Box Providing and fixing forms stand of size 4'-0" X 1'-6" X 3'-9" with 3 nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer. Space for housing vouchers of size 1'6" W, 1'-0" D & 9" H is also provided on the top and on side (L-shaped, wall hung) including provision of Pass Book, Cheque Drop & Suggestion Box as per drawings made of 19 mm thick commercial ply with 1.0 mm thick laminate to be fixed and ¾" x ¼" teak wood lipping on two visible sides on it All exposed Teak wood edges / teak wood lipping /	1.00	Nos		

	Item of Work	Qty	Unit	Rate	Total Amount
	beading shall be spirit polished with matching pigment. etc. & to be fixed on the wall.cost of spacers ect. all inclusive complete.				
17	<p>False Ceiling With Steps. - Gypsum Board</p> <p>Providing and fixing suspended false ceiling (as per specification of manufacture) including steps as per design with 12.5 mm tapered edge Gyp-board / 12 mm thick Elephant Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level. The grid consists of a perimeter channel (MF6a of dimensions 20 mm X 27 mm X 37 mm X 3.5 M) fixed round the perimeter to receive and of the ceiling section (MF5) and the outer edges to gyp-board. The intermediate channel (MF7 of dimensions 15 mm X 45 mm X 0.9 mm X 3.6 M) at 1200 mm c/c in the one direction and the ceiling section (MF5 of dimensions 80 mm X 26 mm X 0.5 mm X 3.6 M) at 450 mm c/c in the other direction are connected by a connecting clip (MF9).</p>	18.00	Sq.mt		
	The grid is suspended with an adjustable strap hanger (MF8) of dimensions 25 mm X 0.5 mm at 1200 mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts / fasteners Nut and bolts are used to connect strap hangers to soffit cleats and for joining ends of channel sections together. The gypsum board layers are screwed to the M/F ceiling sections with gyp-board drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels (MF7) to be used around the cut outs for light fittings. A/C ducting etc. The work should be complete as per instructions of Architect or Engineer in charge. The rates should be inclusive of two or more coats of plastic emulsion over a coat of primer to give an even shade.				
	The rate should be inclusive of making opening with frame etc. for electrical / air conditioner, A.C. grills & trap door etc. if required & finishing of ceiling in all respect. Steps/ Vertical bands shall be measured in square feet. Payments shall be made only for exposed surfaces & actual measurement at site. The work includes cost and conveyance of materials and labour charges including. All operational charges,tools, lifts and all heights etc.				
18	<p>False Ceiling - (Mineral Fibre)</p> <p>Providing and fixing false ceiling at all heights, made of 600 mm X 600 mm X 16 mm Prima Dune / Sand Supreme, RH 99 & micro log edge with black lining, mineral fibre ceiling tiles of type – Fine Fissured micro lock with silhouetted grid (black reveal), Tegular edge, laid on Armstrong exposed grid systems. The framework comprises of main rubber spaced at 1200 mm c/c, securely fixed to the structural soffit by approved hangers of spacing not more than 1200 mm c/c. Hangers (G.I. wire of 4 mm dia.) to be fixed by approved rawl plugs, level adjusters & screws etc. The last hanger at end of each main runner should not be more than 450 mm from the adjacent wall.</p>	12.00	Sq.mt		
	Flush fitting 1200 mm long Cross T's (with double stitching) to be interlocked between main runners at 600 mm c/c to form 1200 mm X 600 mm modules.Cut cross T's longer than 600 mm to be supported independently. 600 mm X 600 mm modules to be formed by fitting 600 mm long flush fitting cross T's centrally between the 1200 mm Cross T's. The rates shall be inclusive of making opening with frame etc. for electrical / air conditioner & finishing of ceiling in all respect, the work includes provision of trap door if required.				

