

BILL OF QUANTITIES FOR INTERIOR FURNISHING WORKS			
AT STATE BANK OF INDIA STATE BANK OF INDIA MOHABATPUR BRANCH, Distt. HISAR.			
1	Providing & fixing vitrified tiles of size 600x600 mm of approved make in flooring laid in any pattern as specified over base of 20 mm thick cement coarse sand mortar 1:3, and jointed with white cement slurry mixed with pigment to match the shade to tiles. The tiles shall be of premium quality double charged (first quality) of reputed manufacture i.e. JOHNSON/NITCO/KAJARIA/NIRO GRANITE. The work also includes dismantling of existing floor/wall tiles or stone & removal of malba and disposal of the same away from site	98	Sq.mt
2	Casting RCC 230mm x 230mm RCC lintel beam comprising of 12mm dia steel bars (4 NOS.) with 8mm dia stripps in 1:2:4 cement concrete. The work includes shutering/framework/curing and floor screed complete in all respects to the satisfaction of the Architect and Bank Engineer.	3	cu.mt
3	11.43 Cm thick Brick wall with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level laid in 1:4 cement sand mortar in super-structure.	4	Sq.mt
4	Providing and Applying 12 mm Cement Plaster in mix 1:6 (1 cement: 6 fine sand) on Brick Work complete in all respects.	8	Sq.mt
5	Renovation of Toilets		
a	Providing and laying 1st quality ceramic rectified glazed tiles 300x900 or 300x600 (as specified in Dado (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: on 20 mm thick cement mortar 1:4(1 cement: 4 coarse) sand), including grouting the joints with white cement and matching pigments etc., complete. Approved makes(Nitco, Johnson, RAK, Kajaria (Note: Work Incl.Dismantling of existing tiles and disposal of material to contractors own dump.)	20	Sq.mt
b	Providing and laying 1st quality ceramic floor tiles 300x 300 (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: on 20 mm thick cement mortar 1:4(1 cement: 4 coarse) sand), including grouting the joints with white cement and matching pigments etc., complete. Approved makes(Nitco, Johnson, RAK, Kajaria) (Note: Work Incl.Dismantling of existing flooring and disposal of material to contractors own dump.)	5	Sq.mt
c	Providing & fixing ½" G. I. 'C' grade pipes for distribution in toilets / pantry including chase cutting, chase filling, coat of primer / anti rust paint at all joints, proper pvc insulation cover for all pipes. The rate shall include all accessories like tees, unions, elbows, bends etc. Required to make the system operational and complete.	6	Rmt
d	Providing & Fixing in position European type water-closet suite (as approved by the Architect/Engineer-In-Charge), syphonic type consisting of:		
(i)	Viterous Chinaware Syphonic suite with 10 liters capacity matching Chineware cistern and all internal brass fittings complete with 'P' or 'S' trap with or without vent, as approved.		
(ii)	One piece seat & lid in hollow white plastic, fitted with chromium plated hinges and rubber buffers (to the approval of Architect/Engineer-In-Charge) Color : WHITE Make:- (HINDWARE- OLIVA Cat No: 92042 WITH CISTERN).		

(iii)	Complete in all respects including stainlen steel JET set & connecting with existing CI pipe with CI/PVC pipes , removing existing fixtures including cutting & making good the walls & floors.	2	NO'S		
e	Providing and fixing in position approved make C.P.Brass liquid soap dispenser fixed into wall with C.P. brass screws complete in all respects including cutting and making good the wall etc. Make:(Ess Ess - Croma Series / Essel - Econ Series /Jaquar- continental series)	1	NO'S		
f	Providing and fixing in position best indian make bevelled edge 5.5mm thick mirror mounted on asbestos sheet ground fixed in position by means of 4.no Chromium plated brass screws & washers over rubber washers & rawl plug embedded in the wall or Chromium plated brass clamps with c.p. brass screws (as required by the Architect/Engineer-In-Charge) complete including cutting & making good walls ect.Size(600x910mm)	6	Sq.ft		
g	Providing and fixing CP Brass towel ring complete with brackets fixed to wooden cleats with CP brass screws with concealed fitting arrangement of approved quality and color. Make:(Ess Ess - Croma Series / Essel - Econ Series/Jaquar- continental series)	1	NO'S		
h	Providing & fixing in position Lavatrry suites cousistry of :-				
(i)	Lavatrry in vitreous chinaware(630mmx450mm). COLOR:WHITE. (HINDWARE: STUDIO Cat No: 10096) with pedestal Cat No: 11038				
(ii)	C.I.Brackfast for building into wall including painting.				
iii	32mm C.P.Brass waste of standard pattern.				
(iv)	15mm C.P. Brass screw down pillar tap with couplings (Pressmatic Jaquar Cat No: PRS-031)				
(v)	Including flexible waste pipe				
	All brass wok chromium plasted and complete in all respects including cutting & making good the walls,floors & paintry of fittings ect.	1	NO'S		
i	Providing & fixing CP Jali, complete in all respects.	3	each		
j	Providing & fixing G.I. reducer (Snw/ Unique) for floor drain, complete 75 x 50mm size.	2	each		
k	Providing & fixing C.P brass bib cock of approved make conforming to isi 8931 (15mm nominal bore)Make:(Ess Ess - Croma Series / Essel - Econ Series/Jaquar-continental series)	2	NO'S		
l	Providing & fixing C.P. brass stop cock of approved make conforming to isi:8931(15 mm nominal bore.) Make:(Ess Ess - Croma Series / Essel - Econ SerieslJaquar-continental series)	3	NO'S		
6	Gypsum Board False Ceiling				
	Providing and fixing suspended false ceiling including steps as per design with 12.5mm tapered edge Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level.The grid consists of a perimeter channel (MF6a of dimensions 20mm x 27mm x 37mm x 3.5M) fixed round the perimeter to receive and of the ceiling section (MFS) and the outer edges to gyboard. The intermediate channel (MF7) of dimensions 15mm x 45mm x 0.9mm x 3.6M) at 1200mm c/c in the one direction and the ceiling section				
	(MFS of dimensions 80mm x 26mm x 0.5mm x 3.6M) at 450mm c/c in the other direction are connected by a connecting clip (MF9). The grid is suspended with an adjustable strap hanger (MF9). The grid is suspended with an adjustable strap hanger (MF8) of dimensions 25mm x 0.5mm) at 1200mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts/fasteners Nut and bolts are used to connect strap hangers to soffit cleats and for joining ends of channel sections together.				

	The gypsum board layers are screwed to the M/F ceiling sections with gypboard drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels (MF7) to be used around the cut outs for light fittings. AIC ducting etc.			
	The work includes painting with 2 coats of plastic emulsion to give an even & finished surface. The payment area will be the visible area only The work should be complete as per instructions of Architect or Engineer in charge.	60.00	Sq.mt	
7	False Ceiling - (Mineral Fibre) Providing and fixing false ceiling at all heights, made of 600 mm X 600 mm X 16 mm Prima Dune / Sand Supreme, RH 99 & micro log edge with black lining, mineral fibre ceiling tiles of type – Fine Fissured micro lock with silhouetted grid (black reveal), Tegular edge, laid on Armstrong exposed grid systems. The framework comprises of main rubber spaced at 1200 mm c/c, securely fixed to the structural soffit by approved hangers of spacing not more than 1200 mm c/c. Hangers (G.I. wire of 4 mm dia.) to be fixed by approved rawl plugs, level adjusters & screws etc. The last hanger at end of each main runner should not be more than 450 mm from the adjacent wall. Flush fitting 1200 mm long Cross T's (with double stitching) to be interlocked between main runners at 600 mm c/c to form 1200 mm X 600 mm modules.	36.00	Sq.mt	
	Cut cross T's longer than 600 mm to be supported independ-ently. 600 mm X 600 mm modules to be formed by fitting 600 mm long flush fitting cross T's centrally between the 1200 mm Cross T's. The rates shall be inclusive of making opening with frame etc. for electrical / air conditioner & finishing of ceiling in all respect, the work includes provision of trap door if required.			
8	Teak Ply Ceiling Providing and fixing 4mm thk. teak veneer in ceiling over 8mm thk. commercial ply screwed to GI ceiling sections also incorporating 2" x 2" soft wood sections where ever specified as drawing. The work includes esprit polished of approved shade. The payment area will be the visible area only The work should be complete as per instructions of Architect or Engineer in charge.	8.00	Sq.mt	
9	Plastic Emulsion Paint Painting & finishing the walls, including surface preparation primer and putty ,finished with three or more coats of plstic emulsion paint, so as to achieve smooth and even finish complete in desired shades and colours (as approved by Architect/Engineer-In-Make:- Asian paints/ICI Dulux/Nerolac.	60	Sq.mt	
10	TEXTURE WORK on walls Providing and applying texture work of (Spectrum make rustic finish), ready mixed material with synthetic binders, applied manually with spatula uniformly on to the wall surfaces, complete as per instructions of the architect / Bank's Engineer.	35	Sq.mt	
11	Gypsum Dry wall – 60 min fire rated (FOR UPS/SYSTEM ROOM/RECORD FLOOR ETC)			

	102 mm thk. Gypsteel Ultra stud partition which includes one layer of tapered edge 15 mm thk. Gyproc fire line.(Conforming to IS 2095 – 1996 part I) is screw fixed with drywall screws of 25mm at 300mm centre to either side of 70mm Gypsteel Ultra stud (0.5mm thk. Having one flange of 34mm and another flange of 36mm made of GI steel) placed at 610mm centre to centre in 72mm gypsteel ultra floor and ceiling channel (0.5mm thk. having equal flanges of 32mm made of GI steel), which is anchored to the floor & true ceiling			
	using suitable anchor fasteners or metal screws with pvc plugs. The boards are to be fixed to the framework with joints staggered to avoid leakage through joints. A gypsteel fixing channel of 99mm width (0.9mm thk. Having two flanges of 9.5mm each) has to be provided at the horizontal joints of the two boards screw fixed to 9.5mm each) has to be provided at the horizontal joints of the two boards screw fixed to the studs using metal to metal that head screws. Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look which includes filling and finishing with gyproc jointing compound. Gyproc joint paper tape and two coats of plastic emulsion paint to Drywall. Top coat (as per recommended practices of saint – gobain Gyproc India). 50mm glasswool slab of density 32Kg/m3 shall be placed in cavity. Fireline of saint Gobain or equivalent of M/s BORAL INDIA LTD. Or EVEREST INDUSTRIES			
		10.00	Sq.mt	
12	Door to System room - Fire rated steel door including frame - 2 (Two) Hrs Metal test certificate will be provided issued from GQMC. (Kutty flush doors & furniture co. Pvt Ltd.paonta sahib, distt. Sirmour, H.P. & GMT, Baddi)	1.95	Sq.mt	
a)	Frame - Providing and fixing fire resistant door frame of section 100 x 50 mm having built in rebate out made up of 1.2 mm GPSP Sheet duly powder coated / 16 SWG G.I. sheet (zinc coating not less than 120 gm / sqm) duly filled with vermiculite based concrete mix, suitable for mounting 120 minutes fire rated door shutters. The frame is fitted with intumescent fire seal strip of size 10 x 4 mm (minimum) around the frame and fixing with dash fastener of approved size and make, including apply a coat of approved brand fire resistant primer etc. complete as per direction of Engineer – in charge (including Dash fastners).			
b)	Shutter - Providing and fixing Metal Door Shutter 46 mm thk.made up of 0.8mm thick GPSP Sheet. Glazed fire resistant door shutters of 120 minutes fire rating conforming to IS : 3614 (Part – II), tested and certified as per laboratory approved by Engineer – in – charge,			
	with suitable mounting on door frame, the entire shutter filled insulation material / Honeycomb craft paper of 160gsm (zinc coating not less than 120 gm/m2) and fixing with necessary stainless steel ball bearing hinges of approved make,provision of Fire Rated Wired Glass size of glass 300 X 200 including applying a coat of approved fire resistant primer etc. all complete as per direction of Engineer – in charge (paneling to be paid for separately).			

c	<p>Hardware for fixing - Fire rated steel door including frame Providing and fixing following hardware for fixing fire rated steel door including frame, complete. Hinges 4X3X3 (Min. 3Nos), Pull Handle 19 X 250mm - Pair, Dead Lock, Fire Rated Wired Glass size - 300 X 200, Fastners Hilti 10 X 92mm - (Min - 10Nos.)</p>				
13	<p>Panelling With Aluminium Composite Panels (With Aluminium Frames) Supplying & fixing 4mm thick Aluminum component sheet of approved make and shade including making of ground of (1"X2") aluminum hollow section as per design ,with 6mm-19mm wide vertical or horizontal groove finished with Dow Cowing sealant (789) as per Architect's drawings & instructions aluminum componenet sheet should be of virgin grade and having aluminum profile thickness of 0.5mm on both sides of core. The rate is inclusive of all fixtures and fittings (with sealent) for proper finish. The works includes front face shutter boxing complete. the rate includes all required shuttering, scafoulding, labour, material, complete.</p>	50.00	Sq.mt		
14	<p>Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)</p>	35.00	Sq.mt		
15	<p>Single Level SWO Counters Providing and fixing at site SWO counters each upto 5'0" long, 2'6" high and 3'0" wide, as per design and drawing. SWO counters to be made of 19 mm thick commercial ply with 1.0 mm thick laminate on outer visible surfaces excluding table curvilinear top (single color on horizontal surface & two colors on vertical surfaces), with 40 mm X 12 mm thick teak wood/MDF beading required all around, as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the counter.The top with Curvilinear profile shall be made out of 19mm thk. commer block board and finished with 6mm thk. flexi ply as base for acrylic sheet or approved laminate as/design with provision for LED Light in bottom. Teak wood/MDF lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have a keyboard tray of size 600 X 270 with both side laminated board with back support, of EBCO make fixed on channels, as per manufacturer's instructions / specifications.</p>	3.05	Rmt		
	<p>Three drawers with autolock running on both sides mounting Telescopic (channels) of EBCO make, made of 19 mm thick commercial ply with 1 mm thick laminate on front face and drawer locks to be provided on one side of the counter as per layout. The sides of the drawers shall be made of 12 mm thick plywood, bottom of 6 mm thick plywood & front of 19 mm thick commercial ply. Non Visible/Inside surface i.e. inside leg-space of table, inside drawers shall be finsihed with 1mm thk. white/off white laminate. All exposed Teak wood edges / teak wood lipping /MDF beading shall be Spray painted Satin Enamel paint or spirit (natural) polish as required. The drawers shall have partitions for keeping currency notes & the counter should also includes foot rest , Space for CPU as per drawing, complete in all respects. The provision of swaping machine of green channel size 9"x 6" with lid shall be provided at right side of each counter while facing from front.</p>				

16	Providing and fixing (12mm thick) white acrylic stone (non-absorbent, non-porous solid surface composite material, belonging to the solid surface category) as per drawings/design.providing by the Architects complete in all respect including buffing and wastage. (Make: Du-Pont.,LG,Samsung)	4.65	Sq.mt	
17	12 MM thk. toughend glass for Banking / SWO Counters with Etching. - front & Sides. Providing and fixing 12 mm thick, clear plain toughend glass of fixed in vertical position at counter level & to side partitions as per drawing, the counter top glass fixed on both sides to toughned glass partitions & side partitions fixed to wooden partition with superior quality stainless steel L - shaped clamps / glass holders 2 no. on both sides. A 6" dia. semi circular hole at the bottom for transaction shall be provided. All the edges of the glass shall be grinded polished and left free.	2.80	Sq.mt	
18	Superior quality stainless steel L - shaped slamps / glass holders 2 no. on both sides to holding the front glass partition to S.W.Counter.	6.00	Nos	
19	Officer's & Staff Tables Table made of 19 mm thk. Commercial ply with front and side visible vertical surfaces to be finished with laminate 1mm thick (of approved shade); Table Top to be clad with additional 4mm thk MDF finished with Satin Enamel Spray Painted of approved shade, with 40 mm X 12 mm thick teak wood/MDF beading all around, as per drawing. The front of the table top shall be projected as per drawing.The modesty guard shall be finished with 12.0 mm thk. toughed glass with 4" wide S.S. Spacer. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the table. The wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 of EBCO make fixed on channels, as per manufacturers instructions / specifications.			
	A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, at 4" above the floor level and 3" away (horizontally), from vertical end which will be made of 19mm thick commercial ply finished with laminate 1mm thk. and 3/4" x 1/4" teakwood/MDF lipping on two visible sides. three lockable drawer running on side mounting drawer slides (channels) of EBCO make made of 19 mm thick commercial ply with 1mm thick laminate on front face, handle / knob and magnetic catcher shall be provided on one side of the table as per layout. The sides of the drawer shall be made of 12 mm thick plywood / 19 mm ply, bottom of 6 mm thick plywood & front of 19 mm thick bply. A full length foot rest made of hard wood 3" x 1 1/2" section shall be provided at 4" above floor level. Non-Visible/inside surfaces i.e. inside / leg-space of table, inside of drawer / cupboard shall be finished in 1mm thk. laminate of white/off white shade and teak wood /MDF edges / lipping / beading shall be Spirit polished or Spray Painted as required.			
a	Size 6'0" X 2'6" X 2'6"	1.00	Nos	
b	Size 5'0" X 2'6" X 2'6"	1.00	Nos	

20	8.0 MM thk glass on top of officers tables. All the edges of the glass shall be grinded polished including Hole for cable manager.	3.00	Sq.mt		
21	Side Credenza Providing & fixing Side credenza (15" to 18" deep) made of 19 mm thick commercial ply and 6 mm thick plywood on back side & 1mm thick laminate of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have three drawers, horizontally running on side mounting drawer slides (channels) of EBCO make.The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be provided beneath				
	the drawers all non visible/inside surfaces shall be finished with white/off white laminate 1mm thk. and teak wood edges / lipping / beading shall be Spirit polished with matching pigment.				
a	Officer's & Staff side credenzaas per Drawing & specification mention in item above. Size - 3'-0"/ 4'-0" X 1'-6" X 2'-6" (W X D X H)	3.05	Rmt		
22	Back credenza / Storage Providing & fixing back credenza 18" deep (top surface 18" to 24" as per site) & 36" HT. made of 19 mm thick commercial ply board and 6 mm thick plywood on back side & 1mm thk laminate of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have draweres 4"high, horizontally running on side mounting drawer slides (channels) of EBCO make. The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be	7.40	Sq.mt		
	provided beneath the drawers and non-visible/inside surfaces should be finished in 1mm thk. laminate of white/off white shade and teak wood edges / lipping / beading shall be Spirit polished with matching pigment				
23	Wooden Partitions with Laminate				
	Full Height partly Glazed (with etching) & partly both side laminated Partitions: Providing & fixing partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections frame @ 2'-0" to 2'-0" c/c vertically & horizontally. The frame shall be fixed rigidly at floor level as well as ceiling with rawl plugs. The frame work to be cladded with 8mm thick commercial ply and 1.0mm thick laminate APPROVED make in specified pattern as per interiors details on both sides .				
	Also 2 1/2"X5/8" teak wood section shall be provided against 8mm thk. glass with etching work as per interior details where ever specified. The rate shall also include for providing grooves in laminate & wood.				
	Note: (i) All ply to be sprayed with anty termite and anti borer spray. (ii) Rates to include all necessary supports and as per details (iii) Measurements to be recorded up to finished false ceiling level.				
		56.00	Sq.mt		
24	Fixed Toughned Glass Partitions				

	Providing & Fixing 12mm thk. Toughned Glass Panels with SS glass connectors as per manufacturers guidelines of (Godrej/Dorma/Ozone/Stanley) make,rested on 12 mm x 25 mm 'U' channel grouted with in floor surface,fixed in position, as per interior details & recessed in ceiling fixed ,also providing and fixing 3 M make decorative film on glass of approved shade as per architect's instruction with grooves etc. as per the instruction of the Achitect/Engineer in charge.	4.00	Sq.mt		
25	Wall Connecting Profile				
	Providing and fixing wall connecting profile in floor to hold 12mm thk. Toughened glass.,make: DORMA/OZONE	4.00	Rmt		
26	Toughned Glass Doors				
	Providing & Fixing Openable 12mm thk. Toughned Glass Door,holded with Patch fitting (i.e. bottom & top patch,L-Patch, floor machine & Door lock) of (Godrej/Dorma/Ozone/Stanley) make,fixed in position as per manufacturers guidelines. The Job also includes providing & fixing of 24" long SS handle & provisions of holes/cuts in glass panel to facilitate fixing of Patch fitting & Handle. The job shall be complete in all respects,including necessary hardware,also providing and fixing 3 M make decorative film on glass of approved shade as per architect's instruction with grooves etc. complete in all respects as per the instruction of the Architect / Engineer in charge.	5.85	Sq.mt		
27	Wall Paneling				
	Providing and fixing paneling over the existing wall made out of framework of 50 mm X 25 mm - 18 gauge section un annodised Aluminium (as per requirement) frame work @ 16" to 24" c/c vertically & horizontally.The frame work to be clad with 8.0 mm thick commercial ply and following finishigs as per drawing and instructions.				
	All exposed surfaces to be clad with teakwood moulding of size 30 mm X 12.0 mm made to shape. The work should be complete in all respects including provisions of grooves duly designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall include for providing groves in laminate & wood. Payments shell be made only for exposed surfaces & actual measurement at site, no payment shell be made for paneling behind furniture such as tables, Credenza , storage etc.				
i.	Panelling with laminate	32.00	Sq.mt		
28	Flush Doors				
	Providing fully panelled35mm thk. flush doors along with 2-1/2" x 5" door frames to be finished with 1.0mm laminate of approved shade with1/8" x 1/8" groove asper design, complete in all respects. to the satisfaction of Engg./ Architect	8.00	Sq.mt		

29	Writing desk / Customer Voucher Stand / Forms Stand including Pass Book, Cheque Drop & Suggestion Box Providing and fixing forms stand of size 4'-0" X 1'-6" X 3'-9" with 3 nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer. Space for housing vouchers of size 1'6" W, 1'-0" D & 9" H is also provided on the top and on side (L-shaped, wall hung) including provision of Pass Book, Cheque Drop & Suggestion Box as per drawings made of 19 mm thick commercial ply with 1.0 mm thick laminate to be fixed and ¾" x ¼" teak wood lipping on two visible sides on it All exposed Teak wood edges / teak wood lipping / beading shall be spirit polished with matching pigment. etc. & to be fixed on the wall.cost of spacers ect. all inclusive complete.	1.00	Nos		
	MISCELLANEOUS				
30	Softboard Providing and fixing in position soft baord (12mm) including fabric cover wooden beading of size 25mmx 19mm on all sides finished with 3 coats melamine polish of approved shade(Basic rate Rs. 175/- per mtr.)	4.00	Sq.mt		
31	Roller Blinds of Vista Make- Iceland Series Providing & Fixing Roller Blinds of Vista make- Iceland Series made of Translucent fibre glass fabric of approved shade including 32mm round channel and mechanism and other fitting fixed in position as per manufacture's specification, complete in all respects to the satisfaction of Architect/Engineer in Charge.	6.00	Sq.mt		
32	MDF JALI Making and fixing in position (as per approved sample) Laser Cut Jaali partition to be made out of MDF board of 8mm. thickness and make. All exposed surfaces to be finish with clear gloss Verinlengo paint as per approved shade . All complete as/ design to the entire satisfaction ofArchitect/ Engineer in charge (Elevation area to measure).	40.00	Sqft		
32	ALUMINUM SHUTTERS FOR ELECTRICAL PANEL with LOUVERS Providing and fixing aluminum shutters over Aluminum frame with frame of section size of 115mm x 45mm in 16 gauge with Aluminum louvers of 77.6mm x 27.6mm of weight 0.483/m including powder coating of selected shade and all desired hardware of approved make fixed at site complete in all respects to the satisfaction of Architect., Engg. in Charge	6.00	Sq.mt		
33	Lacquered Glass panels on SS studs : Providing and fixing 6mm thick Lacquered glass fixed with SS studs and Dow Corning make Neutral Silicone sealant 896 over the frame of 12mm thk. Comm.ply fixed against the wall as panelling as per the drawing to complete satisfaction of the Architect/Bank Engg. in charge.(Make: Saint gobain/AIS)	10.00	Sq.mt		
34	Door Closer - Providing and fixing silver colour (or matching with colour scheme as per site) hydraulic door closer Godrej / Hyper / Everrite make, to Doors complete in all respects.	4.00	Nos		
35	Mortice Lock -Providing and fixing silver colour (or matching with colour scheme as per site) Godrej make to Doors complete in all respects.	2.00	Nos		
36	Night latch in cash cabin door - Providing and fixing night latch lock Godrej make in aluminium / wooden doors, complete in all respects.	1.00	Nos		
	TOTAL				