












| NAME OF WORK : PRICE BID OF INTERIOR WORK FOR FURNISHING OF STATE BANK OF INDIA BRANCH AT NANGAL CHOUDHARY.(HR.). |   |       |        |      |              |
|---|---|-------|--------|------|--------------|
| PART -A (INTERIOR WORKS)  |   |       |        |      |              |
| S.N   | Item of Work  | Qty   | Unit   | Rate | Total Amount |
| 1   | <b>Main Entrance Glazing &amp; Door(Branch &amp; ATM)</b><br><b>(Toughened Glass 12.0 mm thk. with etching )</b> Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass single leaf glazed Toughened door of size approximately, 4'-0" to 3'-0"X 7'-0" all sides edge grinded, polished to be fixed on patch fittings, the door to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shape and size to accommodate fitting etc. the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant where ever required and SS cover over patch fittings to accommodate toughened glass of above items - Hardware - Top pivot, Top patch fitting(s), Bottom patch fitting(s), Corner / Central lock(s) with strike plate, Floor spring, 1'-6" S S door handle (both sides) in door - pair, etc. all complete of godrej / dorma. the rate shall be include etching film / logo all inclusive, complete in all respect. (Note: In case of false ceiling, the vertical members to be fixed below R.C.C slab but the area of Glazing payable will be below the false ceiling only). | 19.52 | Sq.Mtr |      |              |
| 2   | <b>WALL PANELLING(Branch &amp; ATM) :-</b> Wall paneling to be providing in Banking hall made from aluminum frame work using aluminum sections of 50 mm X 25 mm - 18 gauge section un anodized Aluminum of Jindal/ Indal make work Properly fixed to the Wall or Column with proper Spirit level. Frame work to be covered with 8mm thick Plywood of BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) of century, green make and 1 mm Thick laminate as per color scheme of the bank. 35mmX 12mm steam beach Lipping to be provided to all the edges Complete job including melamine polish on edge beading/Cornices etc. and painting of grooves in approved colour. All job to be done as per architects satisfaction/ bank direction .<br><b>BANKING HALL:- Wall paneling Ht : 4'-6", Centre pillars to be cladded upto ceiling bottom "(i.e. + 9'-0 level)</b><br><b>(Note: the area under storage or table, side credenza shall not be counted in wall paneling. only visible area will be payable).</b>  | 69.70 | Sq.Mtr |      |              |
| 3(a)  | <b>FULL HEIGHT PARTITIONS:-</b> Providing and fixing full height partitions of 44 mm X 44 mm X 16 Gauge aluminum extruded sections @ 2'-0" to 2'-0" c/c vertically & horizontally. The bottom member shall be aluminum extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminum extruded sections frame shall be fixed rigidly at floor level as well as ceiling with rowel plugs / steel plugs . 8 mm thick Ply of BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) and 1 mm Thick laminate shall be fixed on both sides as per color scheme of the bank.Glass (10mm thick) with etching as per design and doors with lock is to be providing as per drawing and fixed with Steam beach molding duly melamine polished/paint. 35mm X 12mm steam beach Lipping to be provided to all the edges of the door. All wood to be painted in wood preservative. The rate include making provision for electrical conduits and switch boxes. All job to be done as per architects satisfaction/ bank direction . Note: (In case of false ceiling, the vertical members to be fixed below R.C.C slab but the area of partition payable will be below the false ceiling only).   | 35.31 | Sq.Mtr |      |              |



|    |  |      |        |  |  |
|----|--|------|--------|--|--|
| b) | <b>LOW HT. PARTITION FOR COUNTER SEPARATION:—</b> Providing and fixed low height partitions made of 44 mm X 44 mm X 16 Gauge aluminum extruded sections @ 2'-0" to 2'-0" c/c vertically & horizontally. The bottom member shall be aluminum extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminum extruded sections frame shall be fixed rigidly at floor level as well as wall with rowel plugs / steel plugs . 8 mm thick ply of BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) and 1 mm Thick laminate shall be fixed on both sides as per color scheme of the bank. 12mm thick glass to be provided on the Top of Partition. Teak wood beading 1 ½ " X 3 ¼"( melamine polished ) around partition edges complete in all respects. height : 4'-0"   | 8.37 | Sq.Mtr |  |  |
| c  | <b>12 MM thk. toughend glass for Banking / SWO Counters with Etching. - front &amp; Sides.:</b> Providing and fixing 12 mm thick, clear plain toughened glass of fixed in vertical position at counter level & to side partitions as per drawing, the counter top glass fixed on both sides to toughened glass partitions & side partitions fixed to wooden partition with superior quality stainless steel L - shaped clamps / glass holders 2 no. on both sides. A 6" dia. semi circular hole at the bottom for transaction shall be provided. All the edges of the glass shall be grinded and polished complete in all respects   | 9.30 | Sq.Mtr |  |  |
| 4  | <b>Hardware</b>  |      |        |  |  |
| a  | Providing and fixing of Godrej /Harrison night latches in cash cabin doors as per the directions of the Bank.  | 1.00 | Nos    |  |  |
| b  | Providing and fixing of Mortice locks of approved make (Godrej /Ozone/Hettich/ Dorma) in UPS,ATM, Record Room, etc. as per the directions of the Bank.   | 8.00 | Nos    |  |  |
| c  | Providing and fixing hydraulic door closures Silver colour of approved make(Godrej /Ozone/Hettich/ Dorma) & color.   | 8.00 | Nos    |  |  |
| 5  | <b>Single Level SWO Counters and Single Level Officer's Counter with 1½" thick post-form factory made Tops</b> Providing and fixing at site SWO counters each upto 5'0" long, 2'6" high and 3'0" wide, as per design and drawing. SWO counters to be made of 19 mm thick commercial ply BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) with 1.0 mm thick laminate on outer visible surfaces (single color on horizontal surface & two colors on vertical surfaces), with 40 mm X 12 mm thick teak wood beading required all around, as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the counter. The top with Curvilinear profile shall be made out of 19mm thk. Comm. ply BWR grade IS 303 and finished with 6mm thk. flexi ply as base for acrylic sheet as per design with provision for LED Light in bottom. Teak wood lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have a keyboard tray of size 600 X 270 finished with laminate on top side with back support, of EBCO make fixed on channels, as per manufacturer's instructions / specifications. Three drawers with autolock running on both sides mounting Telescopic (channels) of EBCO make, made of 19 mm thick commercial ply with 1 mm thick laminate on front face and drawer locks to be provided on one side of the counter as per layout. The sides of the drawers shall be made of 12 mm thick plywood, bottom of 6 mm thick plywood & front of 19 mm thick commercial ply. Non Visible / Inside surface i.e. inside leg-space of table, inside drawers shall be finished with enamel paint white /off white. All exposed Teakwood edges / teak wood lipping beading shall be Spray painted Satin Enamel paint or spirit (natural) polish as required. The drawers shall have partitions for keeping currency notes & the counter should also includes foot rest, Space for CPU as per drawing, complete in all respects. The provision of swaping machine of green channel size 9"x 6" with lid shall be provided at right side of each counter while facing from front | 6.10 | R.mtr. |  |  |
| 6  | <b>Lacquered glass panels on SS Studs:</b> Providing & fixing 6 mm thk. Lacquered glass fixed with SS Studs and dow corning make silicone sealant 896 over frame of 19 mm thick commercial ply fixed against the wall as paneling as per drawing with complete satisfaction of the Architect/Bank's Engineer in charge.(Make: saint Gobain/AIS)  | 2.79 | Sq.Mtr |  |  |

|    |  |       |        |  |  |
|----|--|-------|--------|--|--|
| 7  | <b>Low storage unit with ¾" thick post-form factory made Tops</b><br>Providing storage unit of size 18"x2'-6" & 18" x 3'-6" (W x H) of ¾" thick commercial ply BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) with 1.0mm thick horizontal laminate and 1.0mm thick vertical laminate having one shelf in center. The storage unit will have all necessary hardware, laminate band and teakwood/ partal wood beading ¾ " X ½"/ moulding. Recessed skirting (3/4") finished with 1.0mm thick laminate is present. Clip hinges ( dadoo kabzaa ) to be used for fixing storage unit shutters. All inside surfaces are painted with 2 coats of synthetic enamel paint over coat of wood primer .the work to be done complete in all respects.  | 12.10 | Sq.Mtr |  |  |
| 8  | <b>Full height storage unit :</b> Providing storage unit of size 18"x7'0" (W x H) of ¾" thick commercial ply BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) with 1.0mm thick horizontal laminate and 1.0mm thick vertical laminate having shelves @1'-3" C/C. The storage unit will have all necessary hardware, decorative jalli pattern laminate band and teakwood/ partal wood beading / moulding. Recessed skirting (3/4") finished with 1.0mm thick laminate is present. Clip hinges ( dadoo kabzaa ) to be used for fixing storage unit shutters.   | 7.44  | Sq.Mtr |  |  |
| 9  | <b>Wooden boxing for electrical panel:</b> Providing Cabinet unit of size 18"x8'-6" (W x H) of ¾" thick commercial ply BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) with 1.0mm thick horizontal laminate. The storage unit will have all necessary hardware, decorative jalli pattern laminate band and teakwood/ partal wood beading / moulding. Recessed skirting (3/4") finished with 1.0mm thick laminate is present. Clip hinges ( dadoo kabzaa ) to be used for fixing storage unit shutters. All work to be done complete in all respects  | 4.65  | Sq.Mtr |  |  |
| 10 | <b>PIN UP BOARD :-</b> Made of 12mm thick soft board covered by 25mm x 25mm teak wood beading painted polished to approved colour and soft board covered with blazer/ fabric cloth of approved colour. Texture and sample approved by architect. Notice Board to be fixed to wall space between storage unit ( ground placed ) and storage unit ( wall hung ) in manager's Cabin & on top of writing table & in Banking Hall. ( basic rate of fabric shall not be less than Rs.65/- per mtr.)  | 5.58  | Sq.Mtr |  |  |
| 11 | <b>FALSE CEILING:-</b>   |       |        |  |  |
| a  | Providing and fixing Gypsum board false ceiling in levels as per the detailed drawing - made up of G.I. frames as specified by Gypsum India limited and 12mm thick Gypsum board with suitable suspenders fixed to the ceiling. Ceiling section, perimeter channel, suspenders etc. shall be standard sections supplied by Gypsum India LTD. Spacing of intermediate channels shall be at 1200c/c, and ceiling section at 457mm c/c.the work includes finishing of joints, applying primer, two or more coats of plastic emulsion paints (white colour) , making cut-out for light fixtures, etc. providing of perimeter channels / beading etc. complete in all respect  | 74.35 | Sq.Mtr |  |  |
| b  | Providing and fixing of false ceilings at all heights of 600 mm x 600 mm x 16 mm <b>ARMSTRONG Mineral Fibre ceiling tiles</b> of type Prima Dune Premier-Beveled Tegular Edge RH-99 laid on Armstrong 15mm exposed grid system. The framework comprise of main runner spaced at 1200mm centers securely fixed to the structural soffit by approved hangers at 1200mm maximum centers. Hangers (GI wire of 4.0mm dia) to be fixed by approved roof plug, level adjusters and screws etc. The last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall. Flush fitting 1200mm long cross tees (with double stitching) to be interlocked between main runners at 600mm centers to form 1200 x 600mm modules. Cut cross tees longer than 600mm to be supported independently. 600mm x 600mm modules to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200m cross tees and making arrangement for light fixtures, etc. complete in all respect. | 56.00 | Sq.Mtr |  |  |

|    |  |       |        |  |  |
|----|--|-------|--------|--|--|
| 12 | <b>Manager's table with 1½" thick post-form factory made Tops :-</b><br>Providing Table for manager (Size 5'-6" x 3'-0" x 2'-6" ) made of 1½" thick post-form factory made Tops & ¾" thick commercial ply BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) finished with 1.0mm thick horizontal and 1.0mm thick vertical laminate of specified colour and make. 12mm thick bevelled glass (approved make) of same size is placed with edges covered with partial wood beading. Drawer unit ( drawer size: 1'-1" x 1'-6" x 6", 3Nos. ) is located on one side with proper sliding arrangement and auto lock are provided along with storage unit. The counter will have all necessary hardware, laminate band and teakwood/ partial wood beading 1 ½ " X ½" / moulding. Recessed skirting ( ¾") finished with 1.0mm thick laminate is present below the counter. In front, apron of ¾" board ( laminate finished ) is provided. Keyboard drawer. CPU shelf 12" x 18" & footrest 3" x 1 ½" etc. to be provided. Laminate colour combination scheme with beading to be followed. All inside surfaces are painted with 2 coats of synthetic enamel paint over coat of wood primer. All work is to be done complete in all respects. | 1.00  | Nos    |  |  |
| 13 | <b>Officer's table with 1½" thick post-form factory made Tops :-</b><br>Providing Table for Officer's tables (Size 5'-0" x 2'-6" x 2'-6" ) rest specification as per Item No-12.   | 1.00  | Nos    |  |  |
| 14 | <b>Daftri's table with 1½" thick post-form factory made Tops :-</b><br>Providing Table for Officer's tables (Size 5'-0" x 2'-6" x 2'-6" ) rest specification as per Item No-12.  | 1.00  | Nos    |  |  |
| 15 | <b>Side credenza with ¾" thick post-form factory made Tops :-</b> Providing and placing side rack (Size 4'-0" x 2'-3" x 1'-4" ) made of ¾" thick ply BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) finished with 1.0mm thick horizontal laminate. 4 Drawers ( Size 1'-1" x 1'-3" x 4" ) of ¾" board are placed below. Remaining portion has 2 shutters with 1 shelf. Laminated colour combination scheme to be   | 2.00  | Nos    |  |  |
| 16 | <b>Writing desk / Customer Voucher Stand / Forms Stand including Cheque Drop &amp; Suggestion Box with 1½" thick post-form factory made Tops :-</b><br>Providing and fixing forms stand of size 4'-0" X 1'-6" X 3'-9" with 3nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer. Space for housing vouchers of size 1'6" W, 1'-0" D & 9" H is also provided on the top and on side (L-shaped, wall hung) including provision of 2 Nos Cheque Drop & 1 no Suggestion Box made of 19 mm thick commercial ply BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated ) with 1.0 mm thick laminate to be fixed and ¾" x ½" teak wood lipping on two visible sides on it All exposed Teak wood edges / teak wood lipping / beading shall be spirit polished with matching pigment. etc. & to be fixed on the wall cost of spacers etc. all inclusive complete.  | 1.00  | No     |  |  |
| 17 | <b>SIDE TABLE :-</b> Providing and placing side table of size 2'-0" x 2'-0" x 1'-6" made with 2" x 2" teakwood frame melamine polished with decorative 2 ½" x 1 ½" beading along with 12mm thick Glass on the top. All inside surfaces are painted with 2 coats of synthetic enamel paint over coat of wood primer. All work is done complete in all respects to architects / bank managements satisfactory .  | 4.00  | Nos    |  |  |
| 18 | <b>VERTICAL BLINDS :-</b> Providing and fixing perforated vertical blinds of Trac / vista/ Hounter Douglas make of approved colours ( 50mm / 89 mm width) and mechanism & other fitting fixed in position as per manufacture's specification, complete in all respects to the satisfaction of Architect/Engineer in Charge. ( basic rate of fabric shall not be less than Rs.90/- per mtr.)  | 12.08 | Sq.Mtr |  |  |
| 19 | Providing and fixing white board of size 3'-0" x 3'-0" in Manager's chamber clamping on the wall complete in all respect as per directions of the bank/Architect.  | 1.00  | No     |  |  |

|    |  |        |        |  |  |
|----|--|--------|--------|--|--|
| 20 | <b>TEXTURE PAINT:</b> Ground Floor walls to be finished with texture paint of approved make ( Rustic) above 4'-6" upto ceiling bottom including scaffolding, cleaning & supply of all materials. Also providing & fixing 2" wide hillock wood flat member at junction between ceiling & wall along length.   | 71.56  | Sq.Mtr |  |  |
| 21 | <b>Panelling With ACP / Aluminium Composite Panels (With Aluminium Frames)</b> Supplying & fixing 4mm thick Aluminum component sheet of approved make and shade including making of ground of (1"x2") aluminum hollow section as per design ,with 6mm-19mm wide vertical or horizontal groove finished with Dow Cowing sealant (789) as per Architect's drawings & instructions aluminum componenet sheet should be of virgin grade and having aluminum profile thickness of 0.5 mm on both sides of core. The rate is inclusive of all fixtures and fittings (with sealent) for proper finish. The works includes front face shutter boxing complete. the rate includes all required shuttering,scaffolding, labour, material, complete | 20.45  | Sq.Mtr |  |  |
| 22 | <b>Duco Painted HDF Decorative Jali with frame:-</b> Making and fixing in position(As per Approved Sample) Laser cut jali to be made out of HDF(Interior Grade) board of 8MM Thickness with Acrylic frosted sheet and making provision of LED Strip light, fixed inside boxing frame of 6" x6" made of 19 mm thick commercial ply BWR grade IS 303 ( phenol bonded, B.W.P., borer proof, chemically treated )All exposed surfaces to finish with clear gloss duco paint as per approved shade.All work is done complete in all respects to architects / bank managements satisfactory .  | 2.79   | Sq.Mtr |  |  |
| 23 | <b>ENAMEL PAINT :</b> Applying two or more coats of synthetic enamel paint of approved make over a coat of wood / metal primer on doors, windows, shutters, steel grills, ventilators, etc. as per directions of the bank/Architect. (Make:- Asian paints/ICI Dulux/Nerolac.)  | 74.35  | Sq.Mtr |  |  |
| 24 | <b>PLASTIC EMULSION PAINT:</b> Applying two or more coats of plastic emulsion paint of approved make over a coat of primer on walls and ceiling. The work includes sand papering, applying of wall putty of Birla make, P.O.P etc. to give even and smooth finish as per directions of the   | 371.75 | Sq.Mtr |  |  |
| 25 | Providing and erecting 4 ½" thick brick wall with bricks of class 75 designation in superstructure in cement mortar 1:6 (1 cement : 6 coarse sand) including both side cement plaster 10 mm thick in 1:4 cement mortar. The work shall be completed in all respect .   | 39.05  | Sq.Mtr |  |  |
| 26 | <b>CERAMIC TILE DADO&amp; floor tiles:-</b> Providing and fixing first quality Ceramic Tiles for floor tiles of size 12"x12" & wall tiles of size 18"x12" of Kajaria or equivalent, of approved make, shade, design & color over necessary leveling screed of 1:4 cement mortar (20mm thick) with proper slope and 9 - 12 mm thick of approved design and colour to be fixed with Bal Gold Star adhesives (grey in colour) manufactured by Bal Endura Adhesives India Pvt. Ltd. The proportion of Bal Gold Star adhesive shall be 1 bag of 20 Kg mixed with 1 litre of AD-I liquid. All joints of the tiles shall be finished with the matching colour of floor tiles, curing etc. complete in all respects.                             | 48.33  | Sq.Mtr |  |  |
| 27 | <b>VITRIFIED TILE FLOORING:-</b> Providing and fixing in flooring 1st quality 12mm thick double charged vitrified tiles flooring of approved make & shade of size 600x 600mm over necessary leveling screed of 1:4 cement mortar (20mm thick) with proper slope and 9 - 12 mm thick of approved design and colour to be fixed with Bal Gold Star adhesives (grey in colour) manufactured by Bal Endura Adhesives India Pvt. Ltd. The proportion of Bal Gold Star adhesive shall be 1 bag of 20 Kg mixed with 1 litre of AD-I liquid. All joints of the tiles shall be finished with the matching colour of floor tiles, curing etc. complete in all respects.  | 141.27 | Sq.Mtr |  |  |
| 28 | Dismantling 9" & 4 ½" thick brick wall and removal of door etc.carefully by using chisel to cut & making good wall edges with 1:4 cement plaster including removal of debris from site.  | 10.00  | Sq.Mtr |  |  |

|    |  |       |        |  |  |   |
|----|--|-------|--------|--|--|---|
| 29 | Making RCC Slab in pantry size 7'-10 1/2" x 2'-0' . with jet black granite & single bowl stainless steel sink of Neelkanth make including Tap and floor trap connected with man hole/septic tank. the work shall be completed in all respect including plastering etc.   | 1.47  | Sq.Mtr |  |  |   |
| 30 | <b>SANITARY WORKS</b>  |       |        |  |  |   |
| a  | Providing and fixing White Vitreous China pedestal type <b>Water Closet (European type)</b> with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I.brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : (Make Jaguar, Model Continental Cat No CNS-WHT-755SS+CNS-WHT-207 or equivalent. | 2.00  | Nos.   |  |  |    |
| b  | Providing and fixing <b>Wash Basin with Pedestal</b> with C.I. brackets, 15 mm C.P.brass pillar taps, 32 mm C.P. brass waste of standard pattern,including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 550x400x 195 mm.(Wash Basin Make : Jaguar, Model Continental Cat No- CNS-WHT-801 & Pedestal Model: Continental Cat No-CNS-WHT-301 or equivalent .   | 2.00  | Nos.   |  |  |    |
| c  | Providing and fixing white vitreous china <b>Flat Back Urinal</b> of with fittings, size 355x340x 535 mm ,C.P. brass flush pipe, spreaders with unions and clamps (all in C.P. brass) with waste fitting as per IS : 2556, and other couplings in C.P. brass, including painting of fittings and cutting and making good the walls and floors wherever required: (Urinal Make : Jaguar ,Cat No URS-WHT-13261 or equivalent   | 1.00  | Nos.   |  |  |   |
| d  | <b>Health Faucet:-</b> Providing and fixing Health Faucet of Make : Jaguar Cat No ALD-CHR-563 hand shower(Health Faucet) with one meter length extension of Jaguar or equivalent with all necessary materials Viz., arrangement for fixing and placing in position etc., complete as directed.   | 2.00  | Nos.   |  |  |  |
| e  | <b>Angle Cock:-</b> Providing and fixing Angular Stop Cock with wall flange of Make : Jaguar Cat No OPP-CHR-15053PM or equivalent with all necessary materials Viz., arrangement for fixing and placing in position etc., complete as directed.  | 11.00 | Nos.   |  |  |  |
| f  | <b>Pillar Cock:-</b> Providing and fixing Pillar Cock of Make : Jaguar, Cat No.OPP-15001PM or equivalent with all necessary materials Viz., arrangement for fixing and placing in position etc., complete as directed.   | 2.00  | Nos.   |  |  |  |
| g  | <b>Bib Cock:-</b> Providing and fixing Bib Cock with wall flange of Make : Jaguar, Cat No.OPP-15037PM or equivalent with all necessary materials Viz., arrangement for fixing and placing in position etc., complete as directed   | 4.00  | Nos.   |  |  |  |
| h  | <b>Stop Cock:-</b> Providing and fixing Stop Cock with wall flange of Make : Jaguar, Cat No.OPP-150083KPM or equivalent with all necessary materials Viz., arrangement for fixing and placing in position etc., complete as directed. Exposed part kit of concealed stop cock&flush cock with fitting sleeve,operating lever & adjustable wall flange with seal(compatible with ALD-083,ALD-089 & ALD-081)   | 3.00  | Nos.   |  |  |  |
| i  | Providing and fixing ALD-083 Regular body of Concealed Stop Cock suitable for 15 mm pipe line with protection cap(without exposed parts)   | 3.00  | Nos.   |  |  |  |
| j  | <b>Bottle trap:</b> Providing and fixing Bottle trap of Make : Jaguar, Cat No.ALD-CHR-769L250X190 or equivalent with all necessary materials Viz., arrangement for fixing and placing in position etc., complete as directed.  | 4.00  | Nos.   |  |  |  |
| k  | <b>Waste Coupling:-</b> Providing and fixing Waste Coupling 32 mm Half Thread of Make : Jaguar, Cat No.ALD-CHR-709 or equivalent with all necessary materials Viz., arrangement for fixing and placing in position etc., complete as directed.   | 3.00  | Nos.   |  |  |  |

|           |  |       |        |  |  |   |
|-----------|--|-------|--------|--|--|---|
| <b>l</b>  | <b>Towel Ring:-</b> Providing and fixing Towel Ring round with round flange Make : Jaguar, Cat No.ACN-1121BN or equivalent with all necessary materials Viz., arrangement for fixing and placing in position etc., complete as directed.   | 2.00  | Nos.   |  |  |   |
| <b>m</b>  | <b>Braded Hoses:-</b> Providing and fixing Braded Hoses Make : Jaguar, Cat No.ALD-CHR-803AB, 600 mm long Braided Hose with M10X1 Nipple,15mm Nut, O-Ring &Rubber washer (suitable for tall boy basin mixer) or equivalent with all necessary materials Viz., arrangement for   | 6.00  | Nos.   |  |  |  |
| <b>n</b>  | Provided and fixing and placing in position of toilet Mirrors with ledge of overall size 600 mm X 900 mm of 8 mm thick mirror of Atul make made in 19mm plywood backing with 1 mm laminate as approved make and color. 20 mm x 20 mm steam beech beading all around the mirror .All exposed faces of steam beech beading to have melamine polish. The rates should include all necessary hardware,back hole frame fixing etc. complete in all respects   | 2.00  | Nos.   |  |  |   |
| <b>31</b> | <b>G.I.Fitting :-</b> Provided and fixing G.I Pipes complete with G.I. fittings and clamps, concealed pipes with all bend, Tees, Unions etc. including Cutting chases ,painting with anticorrosive bitumastic paint & making good the Walls/ Floor and joining with existing pipe line complete in all   |       |        |  |  |   |
| <b>a</b>  | 15 mm dia. nominal bore  | 60.00 | R.Mtrs |  |  |   |
| <b>b</b>  | 20 mm dia. nominal bore  | 30.00 | R.Mtrs |  |  |   |
| <b>32</b> | Providing and fixing 75 mm Dia PVC waste for Toilets including Trap, CP Grating etc. and cutting floor, making good with PCC 1:4;8 joining the pipe with existing trap, Pipe/ IC complete in all Respect   | 50.00 | R.Mtrs |  |  |   |
| <b>33</b> | Providing and fixing 100 mm Dia PVC waste for WC including P Trap, etc. and cutting floor, making good with PCC 1:4;8 joining the pipe with existing Pipe/ IC complete in all Respect  | 40.00 | R.Mtrs |  |  |   |
| <b>34</b> | Fire Resistant Door -Fire rated steel door including frame Hrs Metal test certificate will be provided issued from GQMC. (Kutty flush doors & furniture co. Pvt Ltd.paonta sahib, distt. Sirmour,H.P. & GMT, Baddi)<br>Frame - Providing and fixing fire resistant door frame of section 100 x 50 mm having built in rebate out made up of 1.2 mm GPSP Sheet duly powder coated / 16 SWG G.I. sheet (zinc coating not less than 120 gm / sqm ) duly filled with vermiculite based concrete mix, suitable for mounting 120 minutes fire rated door shutters. The frame is fitted with intumescent fire seal strip of size 10 x 4 mm (minimum) around the frame and fixing with dash fastener of approved size and make, including apply a coat of approved brand fire resistant primer etc. complete as per direction of Engineer – in charge (including Dash fasteners).<br>Shutter - Providing and fixing Metal Door Shutter 46 mm thk.made up of 0.8mm thick GPSP Sheet. Glazed fire resistant door shutters of 120 minutes fire rating conforming to IS : 3614 (Part – II), tested and certified as per laboratory approved by Engineer – in – charge, with suitable mounting on door frame, the entire shutter filled insulation material / Honeycomb craft paper of 160gsm (zinc coating not less than 120 gm/m2) and fixing with necessary stainless steel ball bearing hinges of approved make,provision of Fire Rated Wired Glass size of glass 300 X 200 including applying a coat of approved fire resistant primer etc. all complete as per direction of Engineer – in charge (paneling to be paid for separately). Hardware for fixing - Fire rated steel door including frame. Providing and fixing following hardware for fixing fire rated steel door including frame, complete. Hinges 4X3X3 ( | 1.96  | Sq.Mtr |  |  |   |
| <b>35</b> | Providing and fixing solid flush doors with Frame of sizes (2'-6" x 6'-9", 3'-0" X 6'-9,3'-6" x 6'-9" )as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make and finished with 1mm thick approved laminate on both sides. The edges finished with steam beach lipping. A door frame of 4 1/2" x 2 1/2" Hollock wood section shall be provided finished in melamine. Rate shall include door stopper, a pair of handles 12" SS Brushed finished, 5" hinges 4 Nos., buffers, tower bolts, etc with necessary hardware items .  | 7.00  | Nos.   |  |  |   |

|    |  |      |      |            |  |
|----|--|------|------|------------|--|
| 36 | Providing and fixing Window (size 2'-6" x 3'-0") of commercial hardwood Such as hillock, champ,chikrassy, etc. of frame size 4 1/2" x 2 1/2" with one openable shutter and fix portion to have 6mm thick frosted glass including iron hold fast, corner straps,screw, bolts for holding hold fast etc. and M S Grill to be provided in windows with 3/4"x3/4" MS square @3" C/C with complete fixing in position.the work shall be completed in all respect. | 2.00 | Nos. |            |  |
|    | <b>TOTAL OF PART-A (INTERIOR WORKS)</b>  |      |      | <b>RS.</b> |  |
|    | <b>DISCOUNT (IF ANY)</b>   |      |      | <b>RS.</b> |  |
|    | <b>G.TOTAL</b>   |      |      | <b>RS.</b> |  |
|    | <b>GST Extra as applicable.</b>  |      |      |            |  |

(IN WORDS) RS

SIGNATURE OF CONTRACTOR:

NAME OF CONTRACTOR:

ADDRESS OF CONTRACTOR: