PRICE BID FORMAT FOR INTERIOR RENOVATION WORKS AT SBI VAZHITHALA BRANCH (EXISTING PREMISES					
	(70962)) UNDER RBO-V, THODUPUZHA, A				
SI.No	DESCRIPTION OF WORK	Qty	Unit	Rate	Amount
	SINGLE WINDOW SYSTEM : LAMINATION TOP				
1	Providig and fixing of single window system without partitions as shown in drawings comprising of each counter size 1600 length or as per detailed drwing attached. Counter and writing top at front with 1000 mm width at 750 mm height. The top and the side supports shall be fixed with 19mm plywood (IS 303) of approved make with curved bend in front modesty as per drawing and fixed with white glossy white laminate of 1 mm thick of approved brand. The front vertical portion of the counter is to provided with aqua blue shade of saint gobain glass 6 mm thick upto a height of 40 cm from the floor level. 12 mm thick clear float galss with etching fixed with SS D Brackets fixed at front (600mm) above the counter (height as per drawing). Modesty panel fixed with 12 mm thick toughened glass of aqua blue shade (Saint Gobain or equivalent) with D Brackets. One set of 3 drawers of equal height, inside a drawer box of 450 mm width 712.5 mm hight and 600 mm deep made of 18 mm ply wood at bottom, sides and front with necessary lipping, telescopic drawer slides, locking arrangements , 100 mm long brush finish ss handles etc complete. Top most cash drawer should be arranged with provision for compartments of various denominations with 8 mm thick plywood. This drawer has to be provided with automatic lock. Key board tray of 600 x 350 mm size made of 18 mm thick plywood finished with 1 mm laminate and MS wire manager of 50 mm dia of approved quality. Foot rest cum CPU stand of 1150 mm x 450 mm size with 18 mm thick plywood finished with 1 mm thick laminate to shape as shown in the drawing. All the internal and external exposed surfaces including inside of drawers to be finished with 1 mm thick laminate . All exposed edges of plywood to be fixed with 2 mm thick matching edge banding.	4	RM		
2	SINGLE WINDOW SYSTEM (With Out Front Glass). The same as above specification without front glass.	2	RM		

3	LOW HEIGHT PARTITION FOR SINGLE WINDOW SYSTEM/COUNTERS: Providing and fixing of Low height partitions for Single window system of 1350 mm height from finished floor level, as per the drawing. Aluminium sections of size 50 x 50 x 1 mm thick of INDAL/ JINDAL make as internal frame structure vertically at about 60 cm centres and 3 nos horizontally of the same size of frame at floor level, 750 mm and at 1350 mm level fixed in position. 8 mm plywood both sides of frame work finished with 1 mm laminate of approved color and shade with grooves on both sides upto 800 mm height. top of the partition finished with laminate of 1 mm thick. Clear float glass of 12 mm thickn ofapproved band with etching shall be fixed with SS D Brackets for a height of 500 mm above the solid partition. Partition on rear similar to side partition, but solid partition. One door shutter for each cabin for 680 mm width and 1350 mm height, similar to door shutter item, fitted with Godrej night latch at 500 mm from floor level, openable inside the cubicle	24	Sq.M	
4	Custom Made Low Height Partition for CO cabin: Providing and fixing in position of custom made low height partitions of the height 1500 mm (900mm solid partition and 600mm glass above) as per drawing attached. Aluminium sections of size 50 x 50 x 1 mm thick of INDAL / JINDAL as internal frame structure vertically and 3 nos horizontally of the same section at floor level 900 mm level and at 1500 mm level. 8 mm plywood of approved quality finished with 1 mm laminate with grooves on both sides of frame work. Top of the partition finished with laminate and 10 mm thick glass with etching is fixed over the partition with SS D brackets including a door as per the specification for door shutter item with Godrej or equivalent mortice lock, tower bolt hinges etc. complete.	11	Sq.M	
5	Custom Made Full Height Solid Partition: Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 8 mm plywood on both sides of frame work from the floor level to false ceiling level finished with 1 mm laminate on both sides including necessary grooves. Measurement for the partition area shall be considered from floor level to false ceiling level only.	9	Sq.M	

6	[a	-		 	
	Custom Made Full Height Solid Partition (Ply with laminate on one side & Cement board on other side): Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 8 mm plywood on one side of the frame work from the floor level to false ceiling level finished with 1 mm laminate including necessary grooves and 10 mm thick Cement board on the other side of the frame work from the floor level to false ceiling level finished with two coats of plastic emulsion paint of approved make and shade over a coat of putty shall be provided. Measurement for the partition area shall be considered from floor level to false ceiling level only.	8	Sq.M		
7	Custom Made Full Height Cement Board Partition: Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 10 mm thick Cement board on the other side of the frame work from the floor level to false ceiling level finished with two coats of plastic emulsion paint of approved make and shade over a coat of putty shall be provided. Measurement for the partition area shall be considered from floor level to false ceiling level only.	10	Sq.M		
8	Partly solid and partly glazed door:- Providing and fixing door shutter using 35 mm thick solid block board finished with 1 mm thick laminate on both sides with grooves fixed with 8 mm glass 600 x900 mm fixed with beech wood beadings above 900 mm. Each door shutter to be provided with 4 nos. 150 mm SS hinges, a pair of 300 mm long SS handles, tower bolts, hydraulic door closer mortice lock etc of Dorma or equivalent make.	5	Sq.M		

9	Fully glazed Door- Providing and fixing frameless fully glazed 12mm thk toughened glass door fixed with necessary patch fittings (Dorma or equivalent make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items. (DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 600mm length) Measurement will be taken only upto solid partition level above.	8	Sq.M	
10	Providing and fixing of fixed glass partitions with 12mm thick toughened glass using PT Standard fittings like PT 90/PT 92 of Dorma or equivalent make at the top and bottom including cutting, making holes in glass and fixing the fittings in floors, ceilings etc and making the same good with necessary screws including etching as per approved patterns.	43	Sq.M	
11	Gypsum Board False Ceiling: Providing and fixing of M/F suspended false ceiling with G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprisingFrame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls alround perimeter side of the ceiling. The intermediate channels suspended from ceiling,through strap hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional channels (MF 6A)for light fittings, air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws including 2 coats of plastic emulsion paint of approved color and over a coat of putty and a coat primer etc, complete.		Sq.M	

11a	Provide and fix Grid type false ceiling with 60 x60 cms size Armstrong/ Saintgobain/ other approved makes 15mm thick accuostic mineral fibre boards with reveal edges, framework with Powder coated GI tee 25mm wide sections, all fittings and fixtures etc complete including providing cutouts for light fittings, AC diffusers, smoke detectors etc complete as per specifications.	11	Sq.M	
12	BM Table: Providing and fixing Branch Manager's table of size 2000 x 800 X 750 mm high to detail as shown in drg. Comprising table top out of 18mm thick Plywood finished with 1mm thick laminate of approved color and brand and side edges with 2mm thick band strip.12 mm glass with polished bevelled edges to be provided for the table top with necessary wire manager. Foot rest cum CPU stand with 18 mm plywood finished with 1 mm laminate. All the internal and external exposed face of plywood to be finished with 1 mm laminate and all the exposed edges of ply to be provided with 2 mm matching edge band. Keyboard tray 600 x 350 mm made of 18 mm thick plywood finished with 1 mm laminate and 50 mm dia MS wire manager of approved quality. One set of 3 drawers of equal height, inside a drawer box of 450 mm width 712.5 mm height and 600 mm deep made of 18 mm thick plywood at bottom, sides rear with necessary lipping telescopic drawer slides, locking arrangements, 100 mm long SS handles etc. complete.	1	No.	
13	Side Tables For BM: Providing and fixing side unit for Manager / BM table to detail as per drg. of size 1200mm x 600 mm made of 18 mm Plywood finished with 1 mm laminate having covered with 2 mm matching edge band Two shutters fixed with Box Type hinges, Locking arrangement, 100 mm long S.S brush finish handles, tower bolt, ball catch etc,.complete. 12 mm glass with polished edges to be provided for the table top. All external internal exposed faces of Plywood to be finished with 1 mm laminate and the exposed edges of ply to be provided with 2 mm thick matching edge band.	1	No.	
14	Officer's table: Providing and fixing Officer's table of size 1500 x 750 X 750 mm high to detail as shown in drg. as per specification in item no.12 above. 11 mm thick glass with polished edges to be provided on table top.		No.	
15	Cash Officer's table: Providing and fixing cash officer's table of size 2000 x 800 X 750 mm high to detail as shown in drg. as per specification in item no.12 above. 12 mm thick glass with polished edges to be provided on table top.	1	No.	

				•	1
16	Side Tables For OFFICER - Providing and fixing side unit for				
	Officer table to detail as per drg. of size 120 x 45 cm as per	2	No.		
	specification in item no.13 above				
17	Side Tables For OFFICER - Providing and fixing side unit for				
	Officer table to detail as per drg. of size 100 x 45 cm as per	1	Nos.		
	specification in item no.13 above				
18	Side Tables For OFFICER - Providing and fixing side unit for				
	Officer table to detail as per drg. of size 145 x 45 cm as per	1	Nos.		
	specification in item no.13 above				
19	Side table for counters - providing and fixing side unit of size				
	1500 x 450 mm for counters as per speification in item no.13	3	No.		
	above	3	140.		
20					
20	Low Level Storage : Providing and fixing low level storage to				
	detail as shown in the drg. Size about 450mm wide, 750mm				
	1200 mm high with openable shutters in front approx 450				
	mm wide fixed with box type hinges, locking arrangements				
	150 mm SS handles and tower bolts made of 18 mm				
	Plywood for top, bottom, rear sides and One intermediate				
	member finished with 1 mm laminate of approved colour	15	Sq.M		
	and brand and all the edges and sides fixed with matching 2	13	5q.ivi		
	mm thick pvc band strip. All the exp[osed internal and				
	external faces of plywood to be finished with 1 mm thick				
	laminate of approved colour and shade. Measurement shall				
	be taken for the front elevation area.				
21	Providing and fixing columns/ wall panelling to detail as				
	shown in the drawing with 18 mm thick plywood finished	60	Sq.M		
	with 1 mm thick laminate.	00	Oq.ivi		
22	Providing and fixing wall mounted writing desk of 1200 x 350 mm				
22	in 19 mm plywood with 1 mm laminate on all exposed surfaces.				
	Top portion is to be provided with 12 mm clear glass with polished				
	edges, with shelves to keep slip books including frosting of		NI.		
	approved design and exposed edges to be fixed with TW beeding	1	No.		
	with melamine polish. A provision to be made for keeping Banks				
	printed Broachers for public etc. complete				
23	Providing and Fixing 100 mm wide Vertical Blinds of Vista	27	Sq.M		
	Levton or approved equivalent make and colour.				
24	Painting the walls/ ceiling with two coats of plastic emulsion				
	paint of approved make and shade including cleaning the	250	Sq.M		
	surface.				
25	Painting the walls/ ceiling with two coats of plastic emulsion				
	paint of approved make and shadeover a coat of putty	200	Sq.M		
	including cleaning the surface.				
26	Painting the windows/ doors/ ventilators with two coats of				
	synthetic enamel paint of approved make and shade	40	Sq.M		
	including cleaning the surface.	. •	1		
	morading occurring the sarrace.			ļ	

27	Providing and fixing 6 mm plywood with 1 mm laminate of approved make and shade to the existing partition/panelling/ counter and table sides etc. and wherever necessary making the surface in level. Rate includes charges for removing and refixing existing glass /beedings/ handles/locks etc. complete. Edges should be neatly finished using pvc edge band		Sq.M	
28	Remove the existing laminate and fix with new 1 mm laminate of approved make and shade	16	Sq.M	
29	Repairing of false ceiling such as closing of exisitng cuttings of light fittings/ ac with gypsum and finishing with 2 coats of paint over a coat of putty and providing cuttings for light fittings/ ac wherever required			
а	providing cutting for light/ ac fitting and making good the false ceiling after installation of the fitting	15	Nos.	
b	closing of existing cuttings of light/ ac fittings and finishing with 2 coats of paint over a coat of putty	10	Sq.M	
30	Dismantling existing counters, cabins, partitions, furniture, false ceiling etc and stacking the usable items as directed and disposal of debris away from site	1	LS	
31	Dismantle brick masonry and finishing the exposed surface with cement mortar 1:4 and disposal of all debris clear off the premises		Sq.M	
32	Flooring:- Providing and fixing 60 x 60 cm vitrified ceramic tiles Johnson & Johnson 'Marbonite' or equivalen approved for flooring and skirting. Tiles to be fixed to existing flooring using approved quality tile on tile adhesive. Basic price of tile to be taken as Rs.65/- per square foot ex showroom. (Tiles will be selected by the Bank)		Sq.M	
	TOTAL (Excluding GST)			

GST at applicable rates will be extra