

| Subject Proposed Interiors for State Bank of India Branch Office at State Bank of India Branch Office at SCO – 145, Sector-03, Kurukshetra, Haryana. |  |       |                       |      |        |
|--|--|-------|-----------------------|------|--------|
| Furnishing - BOQ - B.O. & E- Corner  |  |       | M/S CREATIVE CONCEPTS |      |        |
| S.No   | ITEM   | QTY   | UNIT                  | RATE | AMOUNT |
| <b>INTERIORS / FURNISHING</b>  |  |       |                       |      |        |
| <b>Note</b> - The rates includes laminates suede / Matte / High gloss where ever required as per instructions in all works.                          |  |       |                       |      |        |
| 1  | <p><b>Single Level SWO Counters</b><br/>           Providing and fixing at site SWO counters each upto 5'0" / 4'9" long, 2'6" high and 3'0" wide, as per design and drawing. SWO counters to be made of 19 mm thick commercial ply with 1.0 mm thick laminate on outer visible surfaces (single color on horizontal surface &amp; two colors on vertical surfaces), with 40 mm X 12 mm thick teak wood beading required all around, as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the counter. The top with Curvilinear profile shall be made out of 19mm thk. commer block board and finished with 6mm thk. flexi ply as base for acrylic sheet as per design with provision for LED Light in bottom. Teak wood lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have a keyboard tray of size 600 X 270 finished with laminate on top side with back support, of EBCO make fixed on channels, as per manufacturer's instructions / specifications.</p> | 15.00 | Rft.                  |      |        |
|  | <p>Three drawers with autolock running on both sides mounting Telescopic (channels) of EBCO make, made of 19 mm thick commercial ply with 1 mm thick laminate on front face and drawer locks to be provided on one side of the counter as per layout. The sides of the drawers shall be made of 12 mm thick plywood, bottom of 6 mm thick plywood &amp; front of 19 mm thick commercial ply. Non Visible / Inside surface i.e. inside leg-space of table, inside drawers shall be finsihed with enamel paint white /off white. All exposed Teak wood edges / teak wood lipping beading shall be Spray painted Satin Enamel paint or spirit (natural) polish as required. The drawers shall have partitions for keeping currency notes &amp; the counter should also includes foot rest, Space for CPU as per drawing, complete in all respects. The provision of swaping machine of green channel size 9"x 6" with lid shall be provided at right side of each counter while facing from front.</p>  |       |                       |      |        |
| 2  | <p>Providing &amp; fixing 12 mm thk.Solid Surfaces (Acrylic Sheet )on counter top &amp; required vertical position made to shaped for Single window Counter at transaction level as per design and approved colour (White). Make: LG / Samsung / Gravia / Granimum.</p>  | 60.00 | Sft.                  |      |        |
| 3  | <p><b>12 MM thk. toughend glass for Banking / SWO Counters Low height partitions with Etching. - front &amp; Sides.</b><br/>           Providing and fixing 12 mm thick, clear plain toughend glass of fixed in vertical position at counter level &amp; to side partitions as per drawing, the counter top glass fixed on both sides to toughned glass partitions &amp; side partitions fixed to wooden partition with superior quality stainless steel L - shaped clamps / glass holders 2 no. on both sides. A 6" dia. semi circular hole / as per designe at the bottom for transaction shall be provided. All the edges of the glass shall be grinded polished and left free.</p>   | 54.00 | Sft.                  |      |        |

| Subject Proposed Interiors for State Bank of India Branch Office at State Bank of India Branch Office at SCO – 145, Sector-03, Kurukshetra, Haryana. |   |       |                       |      |        |
|--|---|-------|-----------------------|------|--------|
| Furnishing - BOQ - B.O. & E- Corner  |   |       | M/S CREATIVE CONCEPTS |      |        |
| S.No   | ITEM  | QTY   | UNIT                  | RATE | AMOUNT |
| 4  | Superior quality stainless steel L - shaped slamps / glass holders 2 no. on both sides to holding the front glass partition to S.W.Counter.   | 24.00 | Nos.                  |      |        |
| 5  | <b>Officer's &amp; Staff Tables</b><br>Table made of 19 mm thk. Commercial ply with Table Top, front and side visible vertical surfaces to be finished with 1.0 mm thk. laminate of approved colour & shade, with 40 mm X 12 mm thick teak wood all around, as per drawing. The front of the table top shall be projected as per drawing. The modesty guard ( to B M & C.M. Table) shall be finished with 12.0 mm thk. toughed glass with 4" wide S.S. Spacer. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the table. The wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 of EBCO make fixed on channels finished with laminate, as per manufacturers instructions / specifications.  |       |                       |      |        |
|  | A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, at 4" above the floor level and 3" away (horizontally), from vertical end which will be made of 19 mm thick commercial ply finished with 1.0 mm thk. laminate and 3/4" x 1/4" teakwood lipping on two visible sides. One drawer with lock and one cupboard with shutter made of 19 mm commercial ply with 1 mm laminate on front side of cupboard shutter with shutter having good quality locks, handle / knob and magnetic catcher shall be provided on one side of the table as per layout. The sides of the drawer shall be made of 12 mm thick plywood / 19 mm ply, bottom of 6 mm thick plywood & front of 19 mm thick ply. A full length foot rest made of hard wood 3" x 1 1/2" section shall be provided at 4" above floor level. Non-Visible/inside surfaces i.e. inside / leg-space of table, inside of drawer / cupboard shall be finished in enamel paint of white/off white shade and teak wood edges / lipping / beading shall be Spirit polished or Spray Painted as required. |       |                       |      |        |
| a  | O.T. / S.T. - Size 4'9" / 5'0" X 2'6" X 2'6"  | 4.00  | Nos.                  |      |        |
| b  | B.M. - Size 6'0" X 3'0" X 2'6"  | 1.00  | Nos.                  |      |        |
| 6  | <b>8.0 MM thk glass on top of officers tables.</b> All the edges of the glass shall be grinded polished including Hole for cable manager.   | 68.00 | Sft.                  |      |        |

| Subject  |   |        |                       |      |        |
|--|---|--------|-----------------------|------|--------|
| Proposed Interiors for State Bank of India Branch Office at State Bank of India Branch Office at SCO – 145, Sector-03, Kurukshetra, Haryana. |   |        |                       |      |        |
| Furnishing - BOQ - B.O. & E- Corner  |   |        | M/S CREATIVE CONCEPTS |      |        |
| S.No   | ITEM  | QTY    | UNIT                  | RATE | AMOUNT |
| 7  | <p><b>Side Credenza</b><br/>Providing &amp; fixing Side credenza ( 15" to 18" deep ) made of 19 mm thick commercial ply and 6 mm thick plywood on back side &amp; finished with 1.0 mm thk. laminate of approved colour on top horizontal surface &amp; vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have three drawers with locking arrangements, horizontally running on side mounting drawer slides /channels of EBCO make. The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be provided beneath the drawers all non visible / inside surfaces shall be finished with white / off white enamel paint and teak wood edges / lipping / beading shall be Spirit polished with matching pigment.</p>  |        |                       |      |        |
| a  | Officer's & Staff side credenza as per Drawing & specification mention in item above. Size - 3'-6"/ 4'-0" X 1'-6"/1'-3"/1'0" X 2'-6" (W X D X H)  | 17.00  | Rft.                  |      |        |
| 8  | <p><b>Back credenza / Storage</b><br/>Providing &amp; fixing back credenza 18" deep (top surface 18" to 24" as per site) &amp; 36" HT. made of 19 mm thick commercial ply board and 6 mm thick plywood on back side &amp; finished with 1.0 mm thk. laminate of approved colour on top horizontal surface &amp; vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have drawer 4" high, horizontally running on side mounting drawer slides (channels) of EBCO make. The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be provided beneath the drawers and non-visible/ inside surfaces should be finished with enamel paint of white/off white shade and teak wood edges / lipping / beading shall be Spirit polished with matching pigment.</p> | 41.00  | Rft.                  |      |        |
| 9  | <p><b>False Ceiling With Steps &amp; Cove - Gypsum Board</b><br/>Providing and fixing suspended false ceiling (as per specification of manufacture) including steps &amp; cove as per design with 12.5 mm tapered edge Gyp-board / 12 mm thick Elephant Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level. The grid consists of a perimeter channel (MF6a of dimensions 20 mm X 27 mm X 37 mm X 3.5 M) fixed round the perimeter to receive and of the ceiling section (MF5) and the outer edges to gyp-board. The intermediate channel (MF7 of dimensions 15 mm X 45 mm X 0.9 mm X 3.6 M) at 1200 mm c/c in the one direction and the ceiling section (MF5 of dimensions 80 mm X 26 mm X 0.5 mm X 3.6 M) at 450 mm c/c in the other direction are connected by a connecting clip (MF9).</p>   | 600.00 | Sft.                  |      |        |

| Subject  | Proposed Interiors for State Bank of India Branch Office at State Bank of India Branch Office at SCO – 145, Sector-03, Kurukshetra, Haryana.   |                              |      |      |        |
|--|--|------------------------------|------|------|--------|
| <b>Furnishing - BOQ - B.O. &amp; E- Corner</b> |  | <b>M/S CREATIVE CONCEPTS</b> |      |      |        |
| S.No   | ITEM   | QTY                          | UNIT | RATE | AMOUNT |
|  | The grid is suspended with an adjustable strap hanger (MF8) of dimensions 25 mm X 0.5 mm at 1200 mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts / fasteners Nut and bolts are used to connect strap hangers to soffit cleats and for joining ends of channel sections together. The gypsum board layers are screwed to the M/F ceiling sections with gyp-board drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels (MF7) to be used around the cut outs for light fittings. A/C ducting etc. The work should be complete as per instructions of Architect or Engineer in charge. The rates should be inclusive of two or more coats of plastic emulsion over a coat of primer to give an even shade. |                              |      |      |        |
|  | The rate should be inclusive of making opening with frame etc. for electrical / air conditioner, A.C. grills, trap door & cove with provisions of LED light etc. if required & finishing of ceiling in all respect. Steps/ Vertical bands / Cove shall be measured in square feet. Payments shall be made only for exposed surfaces & actual measurement at site. The work includes cost and conveyance of materials and labour charges including. All operational charges, tools, lifts and all heights etc.  |                              |      |      |        |
| 10   | <b>False Ceiling - (Mineral Fibre)</b><br>Providing and fixing false ceiling at all heights, made of 600 mm X 600 mm X 16 mm Prima Dune / Sand Supreme, RH 99 & micro log edge with black lining, mineral fibre ceiling tiles of type – Fine Fissured micro lock with silhouetted grid (black reveal), Tegular edge, laid on Armstrong exposed grid systems. The framework comprises of main runner spaced at 1200 mm c/c, securely fixed to the structural soffit by approved hangers of spacing not more than 1200 mm c/c. Hangers (G.I. wire of 4 mm dia.) to be fixed by approved rawl plugs, level adjusters & screws etc. The last hanger at end of each main runner should not be more than 450 mm from the adjacent wall.  | 700.00                       | Sft  |      |        |
|  | Flush fitting 1200 mm long Cross T's (with double stitching) to be interlocked between main runners at 600 mm c/c to form 1200 mm X 600 mm modules. Cut cross T's longer than 600 mm to be supported independ-ently. 600 mm X 600 mm modules to be formed by fitting 600 mm long flush fitting cross T's centrally between the 1200 mm Cross T's. The rates shall be inclusive of making opening with frame etc. for electrical / air conditioner & finishing of ceiling in all respect, the work includes provision of trap door if required.   |                              |      |      |        |

| Subject Proposed Interiors for State Bank of India Branch Office at State Bank of India Branch Office at SCO – 145, Sector-03, Kurukshetra, Haryana. |   |        |                       |      |        |
|--|---|--------|-----------------------|------|--------|
| Furnishing - BOQ - B.O. & E- Corner  |   |        | M/S CREATIVE CONCEPTS |      |        |
| S.No   | ITEM  | QTY    | UNIT                  | RATE | AMOUNT |
| 11   | <p><b>Full Height Partitions with etching on glasses. - Solid / partially glazed/ flush door.</b><br/>           Providing and fixing partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections @ 2'0" to 2'6" c/c vertically &amp; horizontally. The bottom member shall be aluminium extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminium extruded sections frame shall be fixed rigidly at floor level as well as ceiling with rawl plugs / steel lugs. The frame work to be clad with 8.0 mm thick commercial ply and finished with 1.0 mm thk. of approved laminate as per pattern on both sides upto 3'0" height and above 7'0" height and 5.00 mm thick glass with etching as per design fixed with teak wood moldings above 3'0" height and upto 7'0" height. The skirting shall be finished with 1mm thk brushed steel finish laminate. Work also includes providing and fixing of flush door of (21/2" x 5/8") section with doors, handle &amp; locking arrangements as per drawing and specifications. All teak veneer / ply / wood to be treated with wood preservatives of approved ISI quality.</p> | 150.00 | Sft.                  |      |        |
|  | <p>All wood shall be finished with high gloss Spirit polished of approved shade. The rate shall also include for providing grooves in veneer. All job to be done to Architect's satisfaction / as per bank direction. Measurements to be taken upto false ceiling level &amp; Payments shall be made only for exposed surfaces &amp; actual measurement at site, no payment shall be made above false ceiling.</p>  |        |                       |      |        |
| 12   | <p><b>Low Height Partition with etching on glasses ( Height + 4'-0" / 6'0")</b><br/>           Providing and fixing Low Height Partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections @ 16" c/c vertically &amp; horizontally. The bottom member shall be aluminium extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminium extruded sections frame shall be fixed rigidly at floor level with rawl plugs / steel lugs / screw. The frame work to be clad with 8.0 mm thick commercial ply and finished with 1.0 mm thk. approved laminate as per pattern on both sides upto 4'0" height. The skirting shall be finished with 1mm thk brushed steel finish laminate. All teak veneer / ply / wood to be treated with wood preservatives of approved ISI quality. All teak veneer / ply / wood shall be finished with high gloss Spirit polished of approved shade.</p>  | 95.00  | Sft.                  |      |        |
| 13   | <p><b>Main Entrance Door for B.O / e-corner &amp; BM - Toughened Glass 12.0 mm thk. with etching</b><br/>           Providing &amp; fixing frameless fully glazed 12.0 mm thk. toughend float glass single leaf glazed Toughened door of size approximately, 1800 to 700mm X 2100 / 2400 mm all sides edge grained, polished to be fixed on patch fittings, the door to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shape and size to accommodate fitting etc. the rate shall include necessary etching film / logo all inclusive, complete.</p>  | 96.00  | Sft.                  |      |        |

| Subject Proposed Interiors for State Bank of India Branch Office at State Bank of India Branch Office at SCO – 145, Sector-03, Kurukshetra, Haryana. |  |        |                       |      |        |
|--|--|--------|-----------------------|------|--------|
| Furnishing - BOQ - B.O. & E- Corner  |  |        | M/S CREATIVE CONCEPTS |      |        |
| S.No   | ITEM   | QTY    | UNIT                  | RATE | AMOUNT |
| 14   | <b>Hardware for fixing Toughened Glass for B.O.</b><br>Providing and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings to accommodate toughened glass of above items - Hardware - Top pivot, Top patch fitting(s), Bottom patch fitting(s), Corner / Central lock(s) with strike plate, Floor spring, 1'-6" S S door handle (both sides) in door - pair & S.S. stopper cleat for each shutter etc. all complete of godrej / dorma.  | 4.00   | Job                   |      |        |
| 15   | <b>Fixed Glass / Glazing for B.O - Toughened Glass 12.0 mm thk. with etching.</b><br>Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass of size - as per site all sides edge grained, polished to be fixed with necessary patch fittings (godrej / dorma) the glazing to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shap and size to accommodate fittings and fixing the fixtures, screws, sealant wherever required and SS cover over patch fittings, etc. the rate shall be include necessary etching film / logo all inclusive, complete  | 155.00 | Sft.                  |      |        |
| 16   | <b>Panelling to wall &amp; Ceiling</b><br>Providing and fixing paneling over the existing wall made out of framework of 50 mm X 25 mm - 18 gauge section un anodised Aluminium ( as per requirement) frame work @ 16" to 24" c/c vertically & horizontally. The frame work to be clad with 8.0 mm thick commercial ply and following finishings as per drawing and instructions. All exposed surfaces to be clad with teakwood moulding of size 30 mm X 12.0 mm made to shape. The work should be complete in all respects including provisions of grooves duly designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall include for providing groves in laminate & wood. Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made for paneling behind furniture such as tables, Credenza , storage etc. |        |                       |      |        |
| i.   | Panelling finished with 1.0 mm thk. Approved shade & colour laminate.  | 500.00 | Sft.                  |      |        |
| 17   | <b>Writing desk / Customer Voucher Stand / Forms Stand including Pass Book, Cheque Drop &amp; Suggestion Box</b><br>Providing and fixing forms stand of size 4'-0" X 1'-6" X 3'-9" with 3 nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer. Space for housing vouchers of size 1'6" W, 1'-0" D & 9" H is also provided on the top and on side (L-shaped, wall hung) including provision of Pass Book, Cheque Drop & Suggestion Box as per drawings made of 19 mm thick commercial ply with 1.0 mm thick laminate to be fixed and ¾" x ¼" teak wood lipping on two visible sides on it All exposed Teak wood edges / teak wood lipping / beading shall be spirit polished with matching pigment. etc. & to be fixed on the wall cost of spacers ect all inclusive complete.   | 1.00   | Nos.                  |      |        |

| Subject  | Proposed Interiors for State Bank of India Branch Office at State Bank of India Branch Office at SCO – 145, Sector-03, Kurukshetra, Haryana.   |                              |      |      |        |
|--|--|------------------------------|------|------|--------|
| <b>Furnishing - BOQ - B.O. &amp; E- Corner</b> |  | <b>M/S CREATIVE CONCEPTS</b> |      |      |        |
| S.No   | ITEM   | QTY                          | UNIT | RATE | AMOUNT |
| 18   | <b>Door Closer</b> - Providing and fixing silver colour (or matching with colour scheme / as per site) hydraulic door closer - Godrej / Hyper / Dorma make to Doors complete in all respects.  | 3.00                         | Nos. |      |        |
| 19   | <b>Mortice Lock</b> -Providing and fixing silver colour (or matching with colour scheme as per site) Godrej make to Doors complete in all respects.  | 1.00                         | Nos. |      |        |
| 20   | <b>Night latch</b> in cash cabin door - Providing and fixing night latch lock Godrej make in aluminium / wooden doors, complete in all respects.   | 1.00                         | Nos. |      |        |
| 21   | <b>Painting Work – Texture Paint</b><br>Providing and applying special / texture paint Asian royal matalic finish of approved shade & make as per manufacturers specification and architects instructions. payment shall be made only exposed surface of texture paint. No measurement shall be made for texture paint behind paneling, furniture such as tables, Credenza, storage etc.   | 700.00                       | Sft. |      |        |
| 22   | <b>Door to System room - Fire rated steel door including frame - 2 (Two) Hrs Metal test certificate will be provided issued from GQMC.</b><br>(Kutty flush doors & furniture co. Pvt Ltd.paonta sahib, distt. Sirmour, H.P. & GMT, Baddi)  | 21.00                        | Sft. |      |        |
| a)   | Frame - Providing and fixing fire resistant door frame of section 100 x 50 mm having built in rebate out made up of 1.2 mm GPSP Sheet duly powder coated / 16 SWG G.I. sheet (zinc coating not less than 120 gm / sqm ) duly filled with vermiculite based concrete mix, suitable for mounting 120 minutes fire rated door shutters. The frame is fitted with intumuscent fire seal strip of size 10 x 4 mm (minimum) around the frame and fixing with dash fastener of approved size and make, including apply a coat of approved brand fire resistant primer etc. complete as per direction of Engineer – in charge (including Dash fastners).   |                              |      |      |        |
| b)   | Shutter - Providing and fixing Metal Door Shutter 46 mm thk.made up of 0.8mm thick GPSP Sheet. Glazed fire resistant door shutters of 120 minutes fire rating conforming to IS : 3614 (Part – II), tested and certified as per laboratory approved by Engineer – in – charge, with suitable mounting on door frame, the entire shutter filled insulation material / Honeycomb craft paper of 160gsm (zinc coating not less than 120 gm/m2) and fixing with necessary stainless steel ball bearing hinges of approved make,provision of Fire Rated Wired Glass size of glass 300 X 200 including applying a coat of approved fire resistant primer etc. all complete as per direction of Engineer – in charge (paneling to be paid for separately). |                              |      |      |        |
| c)   | Hardware for fixing - Fire rated steel door including frame Providing and fixing following hardware for fixing fire rated steel door including frame, complete.<br>Hinges 4X3X3 ( Min. 3Nos), Pull Handle 19 X 250mm - Pair, Dead Lock, Fire Rated Wired Glass size - 300 X 200, Fastners Hilti 10 X 92mm - (Min - 10Nos.).  |                              |      |      |        |

| Subject  |   |        |                       |      |        |
|--|---|--------|-----------------------|------|--------|
| Proposed Interiors for State Bank of India Branch Office at State Bank of India Branch Office at SCO – 145, Sector-03, Kurukshetra, Haryana. |   |        |                       |      |        |
| Furnishing - BOQ - B.O. & E- Corner  |   |        | M/S CREATIVE CONCEPTS |      |        |
| S.No   | ITEM  | QTY    | UNIT                  | RATE | AMOUNT |
| 23   | <p><b>Panelling With ACPWith Aluminium Frames - White colour)</b><br/>           Supplying &amp; fixing 4mm thick Aluminum component sheet of approved make and shade including making of ground of (1"X2") aluminum hollow section as per design ,with 6mm-19mm wide vertical or horizontal groove finished with Dow Cowing sealant (789) as per Architect's drawings &amp; instructions aluminum componenet sheet should be of virgin grade and having aluminum profile thickness of 0.5 mm on both sides of core. The rate is inclusive of all fixtures and fittings (with sealent) for proper finish. The works includes front face shutter boxing complete. the rate includes all required shuttering, scafoolding, labour, material, complete.</p>  | 300.00 | Sft.                  |      |        |
| 24   | <p><b>White Colour Powder coated Aluminium Doors with ACP / PVC coated Board / 5.5 mm thk.Glass witch eatching &amp; frosted as per requirements. (For Doors, Partitions &amp; electrical control panel covering)</b><br/>           Providing and fixing aluminium door made of approved colour powder coated, aluminium extruded sections of various sizes as given below to be fabricated as per approved pattern for doors fixed in position with butt hinges to frame &amp; frame fixed in position with rawl plugs, wooden pegs, screws, aluminium angles / cleats, etc. The doors will be made of three horizontal members and two vertical members provided with 8" long aluminium tower bolt, door stopper, 4 – lever, Make- Plaza, Harrison, Godrej, built in dead lock and aluminium T section / angle at vertical side. Both sides pre-laminated board 12 mm thick shall be fixed in panels with tapered glazing clips. After fixing / embedding with walls &amp; lintel, etc. the surface will be properly repaired / made good with existing specifications.<br/>           a). 65 X 38 X 16 Gauge - All horizontal and vertical members of Door Frame.<br/>           b). 114 X 44 X 16 Gauge - All bottom &amp; lock / middle rail horizontal members of doors.<br/>           c). 83 X 38 X 16 Gauge - Door members - Top rail &amp; Stiles.<br/>           The rate shall include all hardware to complete the job.</p> | 50.00  | Sft.                  |      |        |
| 25   | <p><b>Carpet</b><br/>           Providing and fixing carpet as per approved sample by Architect / Engineer in charge/ matching to existing.</p>   | 100.00 | Sft.                  |      |        |
| <b>TOTAL</b>   |   |        |                       |      |        |
| GST Extra as / applicable  |   |        |                       |      |        |