

PRICE BID: INTERIOR FURNISHING WORK OF STATE BANK OF INDIA,RACPC -II PATNA

Part- A Interior Furnishing

Sl.No.	particulars	Unit	Qty	Rate	Am
1	FALSE CEILING (Gypboard)				
	<p>Providing and fixing 12.5mm tapered edge Gypboard (confirming to IS: 2095 - 1982) is then screw fixed to ceiling section with 25mm drywall screws at 230mm centers. Screw fixing is to be done mechanically either with screw driver or drilling machine with suitable attachment. The boards are to be jointed and finished so as to have a flush look which includes filling and finishing the tapered and square edges of the boards with jointing compound. and cove 6" and cove Down side Beat 3" all work Finish smoth and same level. No extra payment will be made for the cutting of the light points, stain glass , cove lighting, etc. Rate should also include extra perimeter channel, ceiling section and hangers if necessary. The joints to be properly mended with papertapes and gypsum compounds, two coats of drywall topcoat all complete. The rate should include the full completion of the ceiling along with levels as per design including acrylic emulsion paint finish. At the time of handing over the site, all necessary repairing work to be considered if required. The work to be completed as per the specification, design, drawing and approval of the architect. (With Cove Running ft. Only for Cove AGM Room, Meeting Room, And Front area as per Drawing. .same level Gypsum Other area.)</p>	Sq.Ft.	7000		
	<p>Providing , fabricating and erecting lay in type tegular or drop type GYP SUM TILE false ceiling of 600 mm x 600 mm grid with approved brand of gypsum. The rate shall include the additional cost of Tee and L supports and other accessories near the ends/ odd size edges/corners. Provide additional length support from the ceiling to the false ceiling grid wherever necessary, making necessary openings for electrical light fittings, alarm detectors and any other fixtures. No extra payment for making openings in the panel/grids for the purpose of light fittings. Item rate shall include all the taxes, transportation, erection, loading and unloading and any other incidental expenditure for completing the work. Making necessary framework for AC ducting, if any, and necessary cutouts, taping and finishing to proper line and level including making grooves and trap doors for ac. unit in 18mm.thk M.r.grade plywood with stainless steel hinges and locks with moulding 1" x1" for edge including finished with white plastic paint. diffusers and light fitting.</p>	Sq.Ft.	3200		
2	PARTITION				

	Providing and fixing of 2 1/2" x 2" finished saal wood section without sap and joints at maximum 2'- 0" C/C both horizontally and vertically treated with pentaphehene pale from STP as antitermite and fire reterdant from Viper. To be fixed screwed to the floor and ceiling with MS cleats.The framework will be claded with 6mm thick BWR plywood both sides and finished with 1mm thick approved shade laminate as per design with approved adhesive.3"x1/2" white beach/ white cedar skirting with natural polish to be fixed along with the entire bottom length of partition of both sides.Extra framework to be fixed for fixing glass.In case of partly glazed and low height partition (4'-0" & 6'-0") partition, 8mm thick glass to be provided with 3" x 3/4" white beach/white cedar moulding with natural polish all complete.In case of low height patition (4'-0") approved colour soft board should be embedded in partition with white beach/ white cedar wooden beading with natural polish. For full height semiglazed partition there will be some totally solid portion to block the vision as required or as per the drawing.The work to be completed as per the specification, design and approval of the Architects.				
	Note: During joint measurement partition height will be considered upto False Ceiling level. In event of difference in false ceiling height, the partition height will be calculated as average height				
a	Full Blocked Partition (Pantry Room)	SFT	1285		
b	Full ht. Partly Glazed Partition (AGM Cabin-1' to 7'6"Glazing,and DocumentationArea, Audit Room-4 to7'6" Glazing)	SFT	840.00		
c	Low ht. Blocked Partition 4'-00" Height(two table Between)	SFT	216.00		
d	Low ht. Partly Glazed Partition (4'-6")(Glass height will start from 3'0" to 4'-0") (All Half Height Partition)	SFT	796.00		
2	WALL / COLUMN PANELLING (laminate finished)				
	Providing and fixing wall & Coloumn panelling consisting of 1 1/2"x 1" finished sal wood section without sap and joints at maximum 2'-0" c/c both horizontally and vertically treatedwithpentaphehene pale from STP as antitermite and fire retardent from viper. To be fixed screwed on the existing walls. The frame work to be claded with 6mm BWR ply with 1mm thk laminate of approved colour. The work to be completed in all respect as per drawing, specification and approval of the Architects. The rate shall also include the making of boxes 6" out from the wall surface and also the making of niches 6" deep wherever the design demands	Sqft	2260		
3	12mm GLASS PARTITION (W.S)				
	Providing and fixing in position12mm thick machine polished Clear glass atpartition Between two table upper position of work station 1'-0"x2'-0"(H.) The rate shall be includ the fixing hardwer .screw etc.The work to be completed in all respect as per drawings, directions and approval of the Architects.	SFT	52.00		
4	DOORS				
a	Full height partly glazed / Full Blocked door				

	<p>Providing and fixing solid core flush door of 35mm thick, finished with 1mm thick approved colour laminate. A wooden cover moulding of 3"x 3/4" thick white beach/ white cedar with natural polish should be provided for floor spring fitted door. 8mm thick glass with etching (approved design) shall be provided with 1 1/2"x 3/4" thk. white beach/ white cedar glass moulding (as per approved design) with natural polish for full height partly glazed door. In case of vision panel door 18"x 9" 8mm thick clear glass with moulding with natural polish to be provided. The rate shall be inclusive of floor spring (heavy duty), 4" brass hinges, doorstopper, screws, 10" "H" shape brass handle (Kitch) , dead lock of godrej, key hole cover, night latches, tower bolt, door closer of approved make. All edges of the door to be covered with necessary lipping with natural polish. The work should be completed as per the specification, design, and approval of the architect.</p>				
	<p>Note : Wooden door frame fixed to the wall shall have 4" x 2 1/2" white beach/ white cedar (seasoned) section with natural polish. The doors fitted with door closure shall be provided 3" x 1 1/2" white beach/ white cedar section with natural polish for door frame work</p>				
i	Full ht. Partly Glazed door with etching a AGM room (3'-0"x 7'-0")	NO	1		
ii	UPS & server, toilet entrance-4, pantry, meeting room (3'-0"x 7'-0") with door frame. (Door finish 5' Upto 18"x2' clear glass)	NO	8		
iii	Store room door (3'-0"x 7'-0")	NO	1		
iv	Wicket door (3'-0" x 5'-0")	NO	6		
5	MAIN ENTRANCE DOOR				
	<p>Providing and fixing of partly glazed pivoted door at the main entrance consists of 6"x2" seasoned white beach/ white cedar wood section for bottom rail and 4"x2" seasoned white beach/white cedar wood section for top rail finished with natural polish. 12mm thk modi guard/saint gobain clear float glass with banks logo (as per design) and S/S matt finish handle (6'-0" long) of neki /haffle make to be fixed on both sides & proper locking arrangement in bottom rail to be done. The rate should be inclusive of lipping, moulding, beading and heavy duty floor spring of approved make. The work to be completed in all respect as per design, direction and approval of the architect. The rate should include all other accessories like handles, pivots etc. The contractor must follow the design provided by the architect.</p> <p>Note :- There are 2 entrances (Entrance 1 double leaf, Entrance 2 single leaf as specified in the drawing.</p>	SFT	59		
	.				
6	TABLE				

	<p>Providing and fixing table made out of 19mm thk BWR block board for top, sides and front of approved make cladded with 1mm laminate as per design in all visible areas. The table will have 3 nos of drawer unit. The drawer to be made out of 12mm BWR plywood and bottom and back made out of 6mm BWR plywood and it should play drawer sliding channels. The inside of the drawer and the table to be synthetic enamel painted (approved colour). A leg rest to be provided duly painted made out of 3"x1" TWsection with synthetic enamel paint finished. Key board to be made by 19mm thk BWR block board cladding with 1mm thk laminate. The necessary multipurpose lock (brass) ,brass hinges, 4" matt finished handle, (brass) of approved make to be provided in each drawer. 3/4" half round white beach/ white cedar wooden moulding with natural polished to be provided in the table top facia as per detail drawing. On top of branch manager table 12 mm thick clear glass to be provided with 3/4" diastudds. The rates shall include the polishing and bevelling of the glass. The table front apron should have 3/8" half round white ceader moulding finished with natural polish. The necessary wire manager to be provided on the table. Below mentioned OWS table top will 3/4"thk. All the expose area duly enamel painted. The work to be completed as per detail drawing and approval of thr Architect. pls refer detail drawing while coating for other details.</p>				
(a)	AGM (8'x 4') Table with glass top.as per Architect Drawing.	NO	1		
(b)	CM (6'-0"x 3'-0") with glass top	NO	2		
(c)	Manager-5Nos,server room & NPA-MG,Documentation-2Nos. (5'-0" x 2'-6") with glass top	No.	9		
(d)	WS (4'-0" x 2'-0")	No.	36		
(e)	Life Mutual room Table (7'-0" x3') Only table three side cover. No drawer.	No.	1		
(f)	Meeting room Table (16'x4') Oval table	No.	1		
(g)	Visitor Table (4' x 4') S.S Frame With Glass	No.	4		
(i)	Reception Table with glass Top	No	1		
6.1	Provided and fixing AGM table top,lowH.storage top,and side Unit top all edge cover complited Finish. (10 to 15 mm.) korean marble milky white colour . The work to be completed as per colour approval and specification of the Architect.	Sqft	95		
6.2	STORAGES				
	<p>Providing and fixing storage made out of 19mm MR block board for top, sides and 6mm MR ply for back finished with 1.0mm laminate. The shutter to be made out of 19mm block board with 1mm laminate. The necessary multipurpose locks, 6" brass matt finished handle, brass hinges etc to be provided. 3"x1/2" white beach/white ceader skirting to be provided duly natural polish as per matching tone, Inside of the unit to be synthetic enamel paintedn in matching tone.All the exposes edges of the boards/ plywoods to be covered with white beach / white ceader lipping 1 1/2"x 1" moulding duly natural polish all complete. For full height storage file divider made out of 6mm thk ply to be provided, The work to be completed as per approval and specification of the Architect.</p>				

a	Low Height storage (upto3'-0" high) (1'-6" wide)	Sqft.	250		
b	Full Height storage (upto 7'-0" high) (1'-6" wide)	Sqft.	125		
7	SIDE UNITS		70		
	Providing and fixing side unit/ back unit made out of 19mm MR block board for top, sides and 6mm thk MR ply for back finish with 1mm thk laminate. The drawers to be made out of 19mm BWR block board in the front clad with 1mm laminate. Side to be made out of 12mm plywood and bottom, back made out of 6mm plywood and it should play on drawer sliding channel. Drawer and sliding shutter inside to be synthetic enamel painted. The sliding shutter made out of 19mm block board with 1mm laminate finished and should play on aluminium channel all four sides. The necessary godrej multipurpose lock, brass hinges, 4" brass matt finish handle, 4" brass matt finish sliding handle etc to be provided. 3"x 1/2" white beach/ white cedar wooden skirting with natural polish to be provided as per matching tone all along the visible areas. Inside of the unit to be synthetic enamel painted in matching tone. All the exposed edges of the boards/plywood to be covered with white beach/white cedar lipping/ mouldings with natural polish completed. side and back unit top will have 1 1/2"x 1" white beach/white cedar moulding with natural polish at front fascia. The work to be completed as per specification, design and approval of the architect.	Sqft.			
8	PLANTER BOX (size: 16"x16"x16")				
	Providing and fixing planter box made out of 19mm block board finished with 1mm laminate as per design with a 3"x 1/2" white beach/white cedar wooden skirting with natural polish. Inside to be enamel painted. All exposed edges to be covered with white beach/white cedar moulding with natural polish. The work to be completed as per design and approval of architect.	NOS	12		
9	ROLLER BLINDS				
	Providing and fixing of classic system Blackout fabric Roller Blinds which should be made up of 100%Polyester with Acrylic coating resistant to cracking and fraying. It should have 100% blackout rate. The fabric should be min.0.52mm (± 5%) and having min weight 358 g/sqmt (± 5%).Light Fastness ≥ 6. Can be installed (a) On Face (b) Ceiling Mount (c) On Frame (d) in Recess. The Fixing Brackets are made by steel with powder coating to give greater finish. Brackets shall be accommodating overhead or side mounting with clutch assembly on either end of the blind. The ROLLER TUBE shall be of extruded by non rusting Aluminum alloy with 1.25 mm thickness, with anodized for long life.Available in 32-40mm dia metre for small and big blinds respectively. Aluminium bottom bar with powder coating:55 microns or anodizing 10 microns. 5 colour option available. Wall thickness: 1mm. Width 15mm, Height 30mm, Weight: 300gm /rmt (+-5%). for a perfect fall of fabric to avoid warpage / floating. Installation to be insert type with end caps to give a neat look. Operating Chain: #10 plastic/steel ball chain (or as per manufacturer's standard) adoptable to the clutch pitch for smooth, quiet lifting & lowering of blind.	SFT	934		

	The blind can be stop in desire position with help of stop lock used for raising or lowering action of the shades. The fixing arrangements as per approved make manufacturer specification all complete as per direction of Engineer-in-charge. (Area shall measured from bracket to bracket and from top to bottom).				
10	SOFT BOARD/NOTICE BOARD				
	Providing and fixing soft board / notice board fabricated out of 12mm BWR ply covered with 12mm soft board padding and upholstery propylene fabric @ 80/mtr. Edges of soft board should have white beach/white ceader moulding with natural polished.	SFT	210		
	Note: Where pin up board is in a panelled area, the top of the pin up board should be flushed with panel, keeping the same level. The work skould be completed as per specification, design and approval of the Architects.				
11	CORNICE MOULDING				
	Providing and fixing pop cornice moulding along the periphery wherever the walls / partition meeting the ceiling size 4" x 2" duly painted as per approval of the architect.	RFT	500		
12	PLANTS (ARTIFICIAL) AND CREEPERS				
	Providing and placting artificial plants & Creepers of appraved colour with small multicolour marble pebbels and sand to be provided wherever required. The work to be completed as per approval of the Architect.	SETS	10		
13	FIRST AID BOX				
	Providing and fixing in position first aid box made out of 19mm thk BWR block board finished with 1mm thklaminate. Inside to be enamel painted. All exposed to be covered with white beach / white cedar lipping with natural polish. Necessary hardware like multipurpose lock, brass hinges and handle to be provided. The work to be completed as per direction and approval of the architects.	NO	1		
14	ROLLING SHUTTER ENCASEMENT				

	Providing and fixing rolling shutter encasement fabricated out of 12mm thk BWR flexi ply finished with 3mm thk approved colour ACP fixed with silicone sealant and 3mm groves for top, sides, front and bottom with necessary openablepallah at bottom, hardware including, locks, hinges & handles. The job to be completed as per manufacturers specification and approval of the architects. The necessary structure made out of 19mm x 75mm BWP BB for curved canopy portition and vertical surface using alluminium frame sections.(2 Encasement Opening door)	SFT	155		
15	MAIN ELECTRICAL PANEL ENCASEMENT				
	Providing and fixind main panel encasement in position fabricated out of 19mm BWP BB with 1mm thk laminate for top, both sides and front. Encasementwill be having powder coated alluminium louver & 6mm thk glass for seeing the indicator in both pallahs. The exposed surface of 19mm thk BWP BB finished with white beach/white ceader lipping & inside to be enamel painted. The item to be completed in all respect as per design, direction and approval of the architects.	SFT	95		
16	MIRROR FOR TOILET (SIZE 2'-0" x 3'-0")				
	Proving and fixing mirror in toilets made out of 6mm thk matching ploish glass all over eds mounted over 1/2" thk marine ply. The mirror shall be fixed with 1" dias.sstud.The work to be completed in all respect as per design, direction and approval of the Architect.	NOS	2		
17	CUSTOMER SEATING				
	Providing and placing in position visitors chair made of metal tubular frame fully black powder coated with 50 micron thk. And seat and back made of flexi perforated ply. Thework to be completed as per approval 7 direction of the Architect.				
(a)	Chrome finish 3 seater	NOS	5		
	Providing and placing in position visitors Sofa made of wooden frame 3" frame& leather cover. Thework to be completed as per approval direction of the Architect.				
(b)	3 seater Sofa	NOS	3		
	1 seater Sofa	NOS	3		
19	FLIM ON GLASS PARTITION				
	Providing and fixing 3MM make scotchcal 2508Static decorative Frosted crystal Or Flim Striped Shutters Sti R6O0Durableand Ceramic Surface special effect translucent self-adhesive flim.(Front Door &AGMroom,Documentation& Audit Room).	sqft.	328		
20	PAINTING				

	PUNNING WORKS				
(a)	Thoroughly scrapping the walls by wet processes and removing the existing paint and applying POP putty and sand papering the surface after the POP works and preparing the wall surface to take up the final painting works.	Sqft	3200		
	EMULSION PAINTING				
(b)	Providing and applying a coat of primer to make the entire wall surface smooth finish, applying <u>two or more</u> coats of ready mixed exterior emulsion paint of Apex ultima from Asian Paints/ weather coat all guard from Berger Paints/ Surfex maxima from surf.	Sqft	8000		
	ENAMEL PAINTING				
(c)	Providing & applying ready mixed enamel paint of Asian paints/ berger paints/ Surfa coats or any other approved brand of recommended shades to give an even shade on wood work or steel work with <u>two or more coats</u> after thorough cleaning the old painted	Sqft	470		
	TEXTURE PAINT				
(d)	Providing & applying ready mixed structure Paint of Asian paints/ berger paints/ Surfa coats or any other approved brand .	Sqft	380		
	TOTAL				

**PRICES SHOULD BE QUOTED
EXCLUSIVE OF GST
GST WILL BE PAID EXTRA BY THE BANK**