

PRICE BID

<b>Udyogamandal AC Estimate</b>					
SI.No.	Item Description	Qty	Unit	Estimate	
				Rate	Amount
1	Supply, Installation, Testing and commissioning of minimum 3.0 TR capacity, INVERTER CASSETE type split air conditioners with first fill of refrigerant & electrical wiring between indoor and outdoor units complete.				
	<b>Indoor unit</b> ceiling hung comprising cooling coil, evaporator fan with motor, filters, insulated drain pan, drain pump, expansion valve, refrigerant filter drier with codeless remote control unit, etc.				
	<b>Outdoor unit</b> comprising hermetically sealed <b>scroll / rotary compressors</b> , condenser coil with fan & motor, starters / controls / cutouts / relays etc., mounted inside a powder coated sheet metal cabinet of 2mm thick, duly treated for corrosion protection complete, mounted on ribbed rubber pads. <b>(Excluding copper pipe)</b>				
	a) Capacity 3.0TR , with scroll/ rotary Compressor	2	Set		
2	Supply , installation, commissioning of <b>inverter type</b> 1 Tr 3 star rated Hi wall split AC with 3 Mtr Cu piping having necessary insulation, Drain piping, Electrical cabling all accessories, refrigerent supply & filling, cordless remote, all allied earthing, Thermal insulation to prevent the dripping of water from the interconnection between pipes of indoor and outdoor machine along with <b>stabilizer, MS stand</b> . The installation works complete with related civil works for making opening in wall for copper piping and finishing it neatly with brick work, plastering, finishing, removal of debris.	3	Set		
	Total Machine Cost				
3	Supply and erection of copper piping using hard drawn copper (1mm thick) refrigeration pipe complete with bends, Elbows, Supports, Insulation etc. interconnecting indoor and outdoor units (both suction and discharge lines) along with necessary electrical copper wiring including earthing conductor in rigid PVC conduit.	50	m		
4	Tray/ Duct: Supply and erection of 160 mm wide, 100 mm depth PVC Square Pathy or Square UPVC rain water gutter supported from the ceiling using threaded rods and sloated angles with suitable joints and sealents to make the joints leak proof for drawing the refrigerant copper piping upto the wall before condenser unit.	40	m		
5	Supply and erection of angle/channel support for the condenser unit to be mounted on the wall. (Cassette units)	2	Set		
6	Supply and erection of 25mm dia insulated PVC drain water piping (4kg/sq.cm.) upto just above ground level	55	m		
7	Supply and wiring of proper capacity electrical cable from the out door supply point to the AC out door units	25	m		

8	Timer for ATM AC units (Protonics/ Legrand/ equivalent)	1	No		
9	Dismantling and refixing of existing split AC units of the branch ( 1 Tr and 2 Tr units) including service of the units, gas top up if required and copper and drain pipes as required	9	Nos		
	Total base amount for items other than machines				
	Total base amount for the works				

**Note : The rates quoted should be excluding GST. GST as per applicable rates will be paid extra in addition to the quoted rates.**

**(PART B) COMPREHENSIVE ANNUAL MAINTENANCE CONTRACT (CAMC) :  
FOR 5(FIVE) YEARS AFTER WARRANTY PERIOD:**

Note: The AMC charges (for 5 years) to be quoted below will be added to the total quoted amount for the work above and the lowest bidder L1 will be decided accordingly. The offer from those bidders who have not quoted for AMC will be summarily rejected.

**Terms & Conditions**

- Quarterly servicing of both indoor and outdoor units of all ACs during warranty and AMC period.
- Cost of all spares and consumables will have to be borne by the supplier and AMC provider during the warranty and AMC period.
- Attending to any number of breakdown calls during the warranty period and AMC period.

(B)	<b>ANNUAL MAINTENANCE CONTRACT FOR 5 YEARS AFTER WARRANTY PERIOD OF 1 YEAR (Excluding GST)</b>	Qty	Unit	Rate	Amount
	<b>1<sup>st</sup> YEAR (Excluding GST)</b>	2	3Tr Cassette AC		
		3	1 Tr Split		
	<b>2nd YEAR (Excluding GST)</b>	2	3Tr Cassette AC		
		3	1 Tr Split		
	<b>3<sup>rd</sup> YEAR (Excluding GST)</b>	2	3Tr Cassette AC		
		3	1 Tr Split		
	<b>4<sup>th</sup> YEAR (Excluding GST)</b>	2	3Tr Cassette AC		
		3	1 Tr Split		
	<b>5<sup>TH</sup> YEAR (Excluding GST)</b>	2	3Tr Cassette AC		
		3	1 Tr Split		
<b>TOTAL AMC CHARGES FOR 5 YEARS (EXCLUDING GST)</b>					

**GRAND TOTAL FOR DECIDING THE LOWEST BIDDER L1.**

<b>GRAND TOTAL QUOTED FOR WORK (A) ABOVE</b>	<b>₹.</b>
<b>GRAND TOTAL QUOTED FOR ANNUAL MAINTENANCE CONTRACT (B) ABOVE</b>	<b>₹.</b>
<b>TOTAL AMOUNT FOR DECIDING THE LOWEST BIDDER</b>	<b>₹.</b>

**In Words : Rupees**

.....  
.....