

BOQ FOR INTERIOR WORK FOR DONGAON BRANCH (NEW PREMISES)					
S.No	Description	Qty	Unit	Rate	Amount
1	PARTITION- SOLID/ PARTLY GLAZED/ FULLY GLAZED				
	Providing and fixing double skin solid/ fully or partly glazed partition with 6mm thick glass panels with film/ etching/ acid wash in designs/ patterns for various heights (450mm/ 900mm/ 1200mm/ 2100mm & up ceiling height as per drawing and following specifications	72	sqm		
	<u>Aluminium frame work of 50x50x1.2mm of JINDAL/ INDAL make</u> at about 600mm centre to centre and along column/wall ends, junctions of walls, as necessary. Horizontally of same size of frame at floorlevel, 450mm, 900mm, 2100mm and roof level. All frames are fixed in position with alternate vertical frames fixed to soffit of slab with necessary screws, MS clamps, raval plugs, expansion fasteners, etc., complete as per the drawing. <u>In door area concealed 50 x50mm II class teak wood/ Beech wood frame</u> to be provided.				
	Lining with 8mm commercial ply (IS:303)/8mm Bison board on both sides of frame work from floor level to 900mm level and 2100mm level to 3000mm level finished with <u>1mm laminate</u> of approved make and shade including providing necessary 2mm grooves in laminate. Between 900mm and 2100mm levels <u>8mm thick clear float glass with etching</u> fixed with beech wood beading of size 40 x 15mm all round in panels.				
	All concealed faces of ply and wooden framework shall be finished with one coat of wood preservative paint and TW/BW beading/ moulding to be polished with melamine polish or duco paint after properly preparing the surface. (Measurement for the partition area shall be considered from floor level to false ceiling level only.)				
	<u>Making openings</u> The quoted rate should include the cost of making required no. of cuttings, opening for providing electrical, data, voice switch boxes in the partition and making it good the surface with necessary beadings complete as directed.				
2	PANELLING TO WALL/ COLUMN WITH FRAME				
	Providing and fixing panelling to wall/ column using aluminium hollow section of 50mmx25mm size 1.2mm thick of JINDAL/ INDAL make placed horizontally and vertically at 600mm centre to centre & fixing of 8mm thick MR grade ply screwed firmly to the frame and pasting 1.0mm thick laminate in specified designs & approved colours, with skirting etc. complete in all respect in vertical plum level and as directed with beadings polishig complete as directed. It may be noted that there should be 3" gap between the wall and panelling for fixing switch boxes and laying conduits, hence the quoted rate should include cost of providing steel brackets/ wooden or ply packings to create this gap)	110	Sq.M		
3	PANELLING TO WALL/ COLUMN WITH OUT FRAME				
	Providing and fixing panelling to wall/ column using 19mm ply directly to wall/ column including lamination.	20	Sq.M		
4	FLUSH DOORS IN PARTITION				

BOQ FOR INTERIOR WORK FOR					
DONGAON BRANCH (NEW PREMISES)					
S.No	Description	Qty	Unit	Rate	Amount
	Providing and fixing flush doors of solid/ partly glazed/ fully glazed in partition with <u>35mm thick solid core flush shutter finished with 1mm laminate</u> of approved colour and shade on both sides with necessary grooves, 8mm thick clear float glass of size 250 x 1400mm with etching fixed with required size rebate TW/ beach wood moulding/ beading as per drawing. Each door shutter shall be provided and fixed with hardware fittings like hinges (4nos.), <u>hydraulic door closer, door stopper, mortice lock, SS brush finish handles</u> 32mm dia & 600mm long on both sides, etc. ('Dorma' or equivalent make). All frames and shutters to be polished with melamine polish/duco paint after properly preparing the surface.	12	Sq.M		
5	TOUGHNED GLASS DOOR WITH PATCH FITTING				
	Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with Dorma make patch fittings including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film of approved design and pattern. 1 pair of 1000mm long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items. Dorma Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Centre Lock US-20, Handle - TG DIH1000 - 38mm dia X 1000mm length	6	sq.m		
6	8 MM THK GLASS ON TABLE TOP				
	Providing and fixing 8mm thick glass on table top size 1650 to 1800mm including with edge polishing and making holes for cable manager.	5	Nos.		
7	GYPBOARD FALSE CEILING				
	Providing and fixing in position M / F suspended false ceiling to details per drg. No. of Job No. with GI frame work and 12.5 mm tapered type gyp board panels to form grids of 45.7 x 122 cm as per manufacturers specification including provision for stepped shaped ceiling for light through comprising.	120	sqm		
	Frame work of intermediate channels (M.F.T.) at 122 cm centre along one direction M/F ceiling section MF5 at 45.7 cm centres along other direction. Perimeter channels (MF 6A) along walls alround perimeter side of the ceiling, all to detail as per drg.				
	The intermediate channels suspended from ceiling, through strap hangers 25 x 0.5 mm (MF 8) at 122 cm centre connected to soffit cleats P534 (27 x 37 x 25 x 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with necessary bolts and nuts etc. all connected with additional perimeter channels (MF 6A) for openings for light fixtures, AC ducts, vertical drops, offsets etc. wherever necessary all to detail and as per direction.				

BOQ FOR INTERIOR WORK FOR					
DONGAON BRANCH (NEW PREMISES)					
S.No	Description	Qty	Unit	Rate	Amount
	12.5 mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws to form grids of 45.7 cm x 122 cm varied along wall ends etc. including Architectural boxing, design and painting the underside of gyp board with 2 coats of plastic emulsion paint of approved colour over a coat primer etc. complete.				
	Note: The false ceiling area will be measured in flat area only.				
8	GRID FALSE CEILING				
	Providing and fixing in true horizontal level false ceiling as per the std drawing grid of 15 mm of approved make, using hot dipped galvanized steel section exposed surface chemically cleaned capping prefinished in baked polyester paint wall angle of size 3000 x 19 x 19mm used in the periphery of the ceiling fixed to the wall partition RC column band walls with the help of screws at 600mm C/C.	85	sqm		
	Main runner of size 3000 x 15 x 32 mm suspended at a 1200mm C/C. by using 2mm / 3mm dia GI wire hanger securely fixed to the structural soffit of RC slab by using 6mm anchor fastener at every 1200mm, (max) and 1200mm long cross tee of size 15 x 32 mm to be interlocked between in main runner at 600mm C/C (max) to form a grid of 1200 x 600mm.				
	600mm long cross tee of size 15 x 32 mm fixed in between 1200 mm long cross tee for forming a grid of 600 x 600 mm. Finally laying 15 mm THICK PRIMA FINE FISSURED MICROLOOK EDGE. Fire rating of 60 minutes as per BS 476/23 of 1987, Noise reduction co-efficient (NRC) of 0.55, light Reflectance of > 84%, sound attenuation of 34 db, Thermal conductivity K - 0.052-0.057 W/m ⁰ K, weight of 3.53 kg/m ² and Humidity Resistance of RH - 99%.				
9	SINGLE WINDOW COUNTER CUBICLES				
	Providing and fixing standard Single Window counter cubicles (combination of SW cash counters and one service manager table) as shown in drawing. Each cubicle size is about 1650mm length and 2100mm depth and 1200mm high comprising the following: (Note: cost is inclusive of partition, door, counter table, side table, front and side glass)	3	Nos.		
	The SW cubicle shall be of 1650mmx2100mm size made with partition of 1200mm high as per the specification of item no. 1 with flush door as per specification of item no.3 but it will have night-latch lock with D-handle 150mm. The service manager table shall be an open cubicle without door and front glass.				
	The counter writing top shall be 1650mm width and 875mm depth at about 750mm level made out of 25mm thick HMR Grade MDF Board finished with 0.8mm thick laminate of approved colour and shade with post forming edges on both side. Front counter support for 750mm height shall have a box design to provide cove light with 18mm ply finished with 1mm laminate.				

BOQ FOR INTERIOR WORK FOR					
DONGAON BRANCH (NEW PREMISES)					
S.No	Description	Qty	Unit	Rate	Amount
	One set of 3 drawers with auto locking system about 450mm width, 712.5mm height and 600mm deep supported with 18mm com. ply at Front, two sides. 3 Nos. of drawer which 2 Nos. of equal height and 1 No. drawer at the bottom of 230mm height lipping, telescopic drawer slides, Individual auto locking arrangement (ebco make), 100mm long brush finish SS handles, etc., complete. Top most cash draw should be arranged with provisiona for denomination partition with 10mm thick com. ply. and finished with 1mm thick post-formed laminate of approved colour and shade				
	Providing and fixing side unit of size 1200mm long as per the specification of item no. 13				
	Providing and fixing 12mm thick toughened glass using PT Standard fittings like PT 90/PT 92 of Dorma or equivalent make in the counter front of size 1650mm wide and 600mm high and also in the front edge of the each bifurcating partition of a vertical glass of 1350 high and 450mm wide at the top and 200mm at the bottom including cutting, making holes in glass and fixing the fittings in partition/ glass/ floors etc and making the same good with necessary screws, sealants wherever required.				
	Keyboard tray made out of 18mm thick Com.Ply finished with 1mm thick laminate of approved colour and shade with necessary Telescopic slides and 50mm Dia SS Brush Finish wire manager of approved make and quality.				
	Foot rest cum CPU stand of required length with same 18 mm com. Ply finished with 1mm thick laminate of approved colour and shade.				
	All concealed faces of ply finished with one coat of wood preservative paint and all exposed edges/ faces shall be provided with TW/BW beading finished with DUCO paint to the satisfaction of the Client/ Architect. Table, Drawer inside should be finished with 0.8mm thick laminate of approved colour and shade.				
10	GRAHAKAMITRA COUNTER CUBICLE WITH W.GATE				
	Providing and fixing grahakamitra counter cubicle to shape as per drawing of overall size about 1650 mm X 900/750 mm including side partition comprising of laminated table top at two levels as shown in the drawing made of 18 mm thick ply and stiffner of 75 mm width around the table finished with 1 mm thick laminate of approved colour including TW/BW moulding.In front of the table, at 1050mm level 150mm wide 12mm thick glass writing top is provided with SS mirror studs finished with 1mm laminate of approved shade and colour.(As per drawing enclosed)	1	Nos		

BOQ FOR INTERIOR WORK FOR					
<u>DONGAON BRANCH (NEW PREMISES)</u>					
S.No	Description	Qty	Unit	Rate	Amount
	One set of 4 drawers about 450 mm width, 712.5 mm height and 600 mm deep supported with 18 mm thick commercial ply at bottom, sides and rear. Drawers 3 nos. of which 2 nos. of equal height and 1 no. drawer at the bottom of 230 mm height made out of 12 mm thick ply for sides, rear, bottom and face of drawer with 18 mm thick ply and finished with 1 mm thick post formed laminate of approved colour, with necessary lipping, telescopic drawer slides, locking arrangement, 100 mm long S.S. brush finish handles, etc. complete.				
	Providing and fixing side unit of size 900mm long as per the specification of item no. 13				
	Foot rest cum CPU stand of required length with same 18 mm thick ply .				
	Keyboard tray made out of 18mm thick Com.Ply finished with 1mm thick laminate of approved colour and shade with necessary Telescopic slides and 50mm Dia SS Brush Finish wire manager of approved make and quality.				
	All concealed faces of ply finished with one coat of wood preservative paint and all exposed edges/ faces shall be provided with TW/BW beading finished with DUCO paint to the satisfaction of the Client/ Architect. Table, Drawer inside should be finished with 0.8mm thick laminate of approved colour and shade.				
11	BRANCH MANAGER'S TABLE				
	Providing and fixing BM table of size 1800 x 750 x 750mm high to detail as shown in drawing. Comprising table top out of 25mm thick HMR Grade MDF Board finished with 0.8mm thick laminate of approved colour and shade with post forming edges on both side.	1	Nos		
	Keyboard tray made out of 18mm thick Com.Ply finished with 1mm thick laminate of approved colour and shade with necessary Telescopic slides and 50mm Dia SS Brush Finish wire manager of approved make and quality.				
	One set of 4 drawers about 450 mm width, 712.5 mm height and 600 mm deep supported with 18 mm thick commercial ply at bottom, sides and rear. Drawers 3 nos. of which 2 nos. of equal height and 1 no. drawer at the bottom of 230 mm height made out of 12 mm thick ply for sides, rear, bottom and face of drawer with 18 mm thick ply and finished with 1 mm thick post formed laminate of approved colour, with necessary lipping, telescopic drawer slides, locking arrangement, 100 mm long S.S. brush finish handles, etc. complete.				
	Foot rest cum CPU stand of required length with same 18 mm thick ply .				
	All concealed faces of ply finished with one coat of wood preservative paint and all exposed edges/ faces shall be provided with TW/BW beading finished with DUCO paint to the satisfaction of the Client/ Architect. Table, Drawer inside should be finished with 0.8mm thick laminate of approved colour and shade.				
12	OFFICER'S TABLE				

BOQ FOR INTERIOR WORK FOR					
DONGAON BRANCH (NEW PREMISES)					
S.No	Description	Qty	Unit	Rate	Amount
	Providing & Fixing Officer table of size 1650 x 750 mm made with specification same as Branch Manager table given above, as per drawing enclosed.	3	Nos		
13	DINING TABLE				
	Providing & Fixing meeting table of size 1800MMX900MM made with specification same as in item no.(10) above but without drawer unit as per drawing enclosed.	1	Nos		
14	FIXED TOUGHENED GLASS PARTITION				
	Providing and fixing of fixed glass partitions with 12mm thick toughened glass using PT Standard fittings like PT 90/PT 92 of Dorma make at the top and bottom including cutting, making holes in glass and fixing the fittings in floors, ceilings etc and making the same good with necessary screws, sealants wherever required.	12	Sq.M		
15	SIDE TABLE/ STORAGE UNITS				
	Providing and fixing side table/storage unit of 750 to 1200mm long and 750 to 1200 mm high made of 25mm thick HMR Grade MDF Board finished with 0.8mm thick post-formed laminate for top and intermediate shelves with necessary SS Bracket, 8mm thick ply for rear side, hung shutter in both the panels using 18mm com. ply and finished with 1mm thick laminate of approved colour and shade, including all necessary TW lipping finished with DUCO paint, Butt hinges, locking arrangement, 100mm long SS brush finish handles, tower bolt, ball catch, complete to the satisfaction of the Client/ Architect. Table, Drawer, storage inside should be finished with 0.8mm thick laminate of approved colour and shade.	13	Sqmt.		
16	FIXED WRITING LEDGE WITH BOX PANELING				
	Providing and fixing writing ledge made of 18mm ply and 12mm glass fixed to wall in such a way that the ledge shall be supported to the side boxing 6"x6". The 6"x6" boxing shall be extended up to a height of 2100 mm in the shape of inverted U. The ledge table as per drg of size about 1200 mm long and 300 to 450 mm width to shape at about 1050 mm from floor level finished with 1mm thk laminate of approved colour and shade. The ledge will have 12mm clear float glass with edge polished at top & bottom and 6 verticals to be fixed on ply boxing with with necessary S.S "D" bracket.	1	Nos		
17	ROLLER BLINDS				
	Providing and fixing Roller blinds of Approved make/ Colour. Rate shall be inclusive of necessary scotch guard treatment on both side. The overlaps should be uniform and adequate. Basic cost of blinds should not be less than Rs.1200 per Sqm	12	sqm		
18	EMULSION PAINT				
	Prepare surface and paint two coats of plastic emulsion paint of approved colour and shade over a coat of primer including Alteck putty after thoroughly scrapping the existing internal walls.	195	sqm		
19	ENAMEL PAINT				

BOQ FOR INTERIOR WORK FOR DONGAON BRANCH (NEW PREMISES)					
S.No	Description	Qty	Unit	Rate	Amount
	Prepare surface and applying two coats of Synthetic Enamel paint of approved colour and shade over a coat of anti corrosive paint after thoroughly scrapping the existing paint	98	sqm		
20	ROLLING SHUTTER BOXING				
	Providing and fixing rolling shutter boxing with 18mm thick com. ply with required aluminium frame work fixed to wall with necessary screws, rawl plugs etc., complete and finished with 1.5mm thick laminate of approved colour and shade	20	sqm		
21	ACP WALL CLADDING - EXTERIOR				
	Supply, fabrication & erection of 4mm thick Aluminium Composite Panels - (0.5+3+0.5mm) (Alstrong / Durabuilt) duly pre-fabricated on Holzer machines and fixed to the masonry /RCC wall with aluminium framework at desired levels, made with Aluminium box section of size 50mmx25mmx3mm with necessary MS brackets for 5' Projection on both side, bolt nut arrangement with SS Screw,aluminium L cleats, brackets, rod, DOWCORNING multipurpose silicon weather sealant no 789.The aluminium composite panel will be bent in the curved form, and to any profile to the required size and fixed over the framework with necessary L clamps and finished with backer rod and silicon sealants stated above and as the specification and including louver etc. all complete. The shop drawing must be prepared by the contractor and should be approved by the Architect before erection. The rate will include all inputs of labour, materials, T & P, taxes, duties and other inclusive charges, wastages etc. involved in the work. The rate inclusive of all necessary scaffolding, leads, lifts etc. complete.	30	sqm		
TOTAL TENDER AMOUNT EXCLUDING GST					
					+GST