



**PART – B: PRICE BID**

E- REVERSE AUCTION TENDER  
FOR PROPOSED INTERIOR WORK  
OF STATE BANK OF INDIA,  
GUEST HOUSE AT 3049, SECTOR 21-D  
CHANDIGARH

TENDER SUBMITTED BY :

NAME OF FIRM: \_\_\_\_\_

ADDRESS: \_\_\_\_\_

MAIL ADDRESS:- \_\_\_\_\_

PHONE NO.: \_\_\_\_\_

**PRICE BILL OF QUANTITIES OF INTERIOR WORK FOR SBI GUEST HOUSE  
AT H.NO. 3049, SECOT-21-D, CHANDIGARH**

S.No	ITEM	UNIT	QTY	RATE	AMOUNT
B	<b>INTERIOR WORK</b>				
1	Plaster of Paris (P.O.P) ceiling including making coves, offsets, cost of GI Frame work, etc. Complete in all respects as per instructions of Architect/ Engineer-in-charge.	Sqm	<b>180.0</b>		
2	Extra for making Cornice, Moulding in POP on Wall & Ceiling as per Design/ instructions of Architect/ Engineer-in-charge.	Rmt	<b>200.00</b>		
3	POP punning on the wall to give even and smooth finish including making Offset, Grooves etc. complete in all respect.	Sqm	<b>310.00</b>		
4	Wall panelling with 1mm th. Mica over 8mm th. MR Grade Ply over Aluminium Frame work including making offset, making grooves, Moulding etc. complete as per Architect/ Engineer in	Sqm	<b>27.00</b>		
5	Wall panelling with 4mm th. Veneer over 8mm th. MR Grade Ply over Aluminium Frame work including making offset, making grooves, Moulding and Melamine polish etc. complete as per Architect/ Engineer In Instruction (Cost of Veneer to be 65/- Sqft)	Sqm	<b>15.00</b>		
6	Wall panelling with Leatherite/ Velvet/ Fabric duly pasted on 12mm th. Foam to fixed 8mm th. MR Grade Ply over Aluminium Frame work including making offset, making grooves, Moulding and Melamine polish to Moulding etc. Complete as per Architect/ Engineer In Instruction ( Leatherite/ Velvet/ Fabric cost Rs. 1000 per M <sup>2</sup> )	Sqm	<b>15.00</b>		
7	Providing and fixing Wall paper on Wall & Ceiling of approved design including base preparation etc. complete as per instructions of Architect/ Engineer-in-charge. (Wall Paper Cost range to be 65/- Per Sqft)	Sqm	<b>50.00</b>		
8	Painting the wall with Velvet touch Premium Paint including Base preparation with acralic putty, Priming coat and the two/ three coats of Velvet Touch Primium Paint as per manufacturer's specification complete as per instructions of Architect/ Engineer-in	Sqm	<b>490.00</b>		
9	Remoulding of Wooden Doors with fixing 4mm th. Veneer on existing ply on both side in pattern including fixing new Brass Finish handle, Lockset, SS Hinges, Tower bolts, Door Stopper and Side Moulding to Chowkhat etc. including Melamine Polish etc. Complete in all Respect as per instructions of Architect/ Engineer-in-charge	Nos	<b>12.00</b>		
10	Remoulding of Jalli Doors Shutter with fixing Teak Wood moulding on both side of Jalli including replacing the jalli with SS wiremesh in pattern including fixing new handle, Hinges, Tower bolts, Door Stopper and Side Moulding to Chowkhat etc. including Melamine Polish etc. Complete in all Respect as per instructions of Architect/ Engineer-in-charge	Nos	<b>5.00</b>		
11	Providing and Fixing silver colour (or matching with colour scheme as per site) hydraulic door closer Godrej / Hyper / Everrite make, to Doors complete in all respects.	Nos	<b>15.00</b>		
12	Providing and Fixing 18mm th MDF Jalli Partition having 6"x4" wooden frame made from 19mm ply duly finished duly Deco Painted as per Design with provision of Cove Light around the Partition Complete in all respect	Sqm	<b>5.50</b>		
13	Providing and placing Cupboard with Sliding shutter made from 19mm MR ply duly finished with 1mm th. Mica all inside Front door to be Duco painted complete with Soft Sliding Channel, dividing Partitions, Pull out Drawers 2 Nos and Shelves etc complete in all respect with all necessary Hardware as per Design and instruction of Architect/ Engineer-in-charge.	Sqm	<b>4.00</b>		

S.No	ITEM	UNIT	QTY	RATE	AMOUNT
14	Providing and placing Cupboard with Sliding shutter made from 19mm MR ply duly finished with 1mm th. Mica all inside Front door to have High Gloss Mica 1mm th. including Aluminium Side Edging handle complete with Soft Sliding Channel, dividing Partitions, Pull out Drawers 2 Nos and Shelves etc complete in all respect with all necessary Hardware as per Design and instruction of Architect/ Engineer-in-charge.	Sqm	4.00		
15	Providing and placing Dressing Counter having 1'3" high pullout storage at bottom and upper part to have 5mm th. Looking Mirror with Cove Light effect. The cabinet to be made from 19mm MR ply duly finished with 1mm th. Mica all inside. Front and sides to Duco painted complete with Pull out Drawers 4 Nos with all necessary Hardware i.e Drawer Channels, Knob/ Handles, teak wood edging duly Duco Painted as per Design and instruction of Architect/ Engineer-in-charge.	Sqm	2.50		
16	Providing and placing Dressing Counter having 1'3" high pullout storage at bottom and upper part to have 5mm th. Looking Mirror with Cove Light effect. The cabinet to be made from 19mm MR ply duly finished with 1mm th. Mica all inside. Front and sides to have High Gloss Mica Finish complete with Pull out Drawers 4 Nos with all necessary Hardware i.e Drawer Channels, Knob/ Handles, teak wood edging duly Painted/ Polished as per Design and instruction of Architect/ Engineer-in-charge.	Sqm	2.50		
17	Providing and fixing TV cabinet made from 19mm MR grade Ply duly finished with Duco paint. Cabinet to have storage up to 2'0" with top layer of storage to have Pullout Drawers bottom layer to have openable shutters. Cabinet to have TV back panel 2" th. made from 19mm ply finished with Duco paint. All inside area to have 1.0mm th. mica. The work includes all hardware i.e handle, locks, Drawer Channels, Crank Hinges etc. all exposed face of Ply to have teak margin duly painted complete in all respect	Rmt	2.30		
18	Providing and fixing TV cabinet made from 19mm MR grade Ply duly finished with 1mm High Gloss Mica. Cabinet to have storage up to 2'0" with top layer of storage to have Pullout Drawers bottom layer to have openable shutters. Cabinet to have TV back panel 2" th. made from 19mm ply finished with 1.0 mm th. High Gloss Mica. All inside area to have 1.0mm th. mica. The work includes all hardware i.e handle, locks, Drawer Channels, Crank Hinges etc. all exposed face of Ply to have teak margin duly painted complete in all respect	Rmt	2.30		
19	Providing and fixing Kitchen Under Counter Storage made from 19mm th MR grade ply duly laminated with 1mm th. Mica all over (outside & Inside) including internal Dividing partition @ 3' c/c, Shelves, Pullout Baskets with all necessary Hardware i.e Drawer Channels, Knob/ Handles, teak wood edging duly Painted/ Polished etc. complete in all respect. (Old Steel Basket to be Used)	Sqm	3.25		
20	Providing and fixing Kitchen Overhead Storage made from 19mm th MR grade ply duly laminated with 1mm th. Mica all over (outside & Inside) including internal Dividing partition @ 3' c/c, Shelves, with all necessary Hardware i.e Crank Hinges, Knob/ Handles, teak wood edging duly Painted/ Polished etc. complete	Sqm	2.00		
21	Providing and Fixing Double Curtain, One of Fabric and One Net as per approved design including Sliding channel, Stitching, fixing in position complete in all respect. (Fabric cost 750/- Mtr)	Sqm	24.00		
22	Providing and fixing Laminated wooden Flooring including base form and corner profile molding etc complete as per instructions of Architect and Engineer-in-Charge.	Sqm	18.00		
23	Providing and fixing Rug, Carpet as per Design for Drawing room & Bed rooms (make Dazehome, The Rug Republic or equivalent)				

S.No	ITEM	UNIT	QTY	RATE	AMOUNT
i	Size (8'x10')	No	1.00		
ii	Size (4'x6')	Nos	2.00		
iii	Size ( 8'x3')	Nos	2.00		
24	Providing and Fixing Wall Art Painting and Artifacts as per approved design by Architect/ Engineer- In-charge.				
i	Metal Art Arctifact of Copper Finish ( Size 4'6"x4'0")	Nos	2.00		
ii	Wall Art Paintings ( 2'6"x2'6")	Nos	4.00		
ii	Wall Art Paintings ( 1'0"x2'0")	Nos	6.00		
25	Providing and fixing in position Planter box made from 19mm MR grade ply finished with 1.0mm th. Mica of approved shade inside and out side Complete (Size 6'6"x1'6")	No	1.00		
26	Providing and fixing in position Polyethylene Artificial Grass 25mm th. as approved by Architect/ Engineer- In-charge.	Sqm	70.00		
27	Natural Green Plant of different type (3'0" to 4'0" High) Indoor & Out Door with pot	Nos	25.00		
	<b>TOTAL FOR PART B (INTERIOR WORK)</b>				

**NOTE :**

**The Rates quoted shall be include all costs, allowances, taxes, levies, octroi etc. All statutory deductions will be made from the payment issued to the contractor. (Only G.S.T as applicable shall be paid extra over the final bill by Bank).**