

Tender ID: AMRRJVM001

Date :21.10.2021

PRICE – BID**Schedule of Quantities of Interior works for Renovation of DGM'S Flat at Rajamahendravaram****Note: All materials, design patterns are to be approved by Bank before using. Basic costs mentioned for some of items is exclusive of GST.**

S.No	Description	Unit	Qty	Rate	Amount
1	False Ceiling: Providing and fixing suspended ceiling system in given design of 12.5mm plaster of paris is fixed to Frame Work / Rondo / Boral Metal System concealed grid key lock suspended ceiling system consisting of 5mm suspension rod, adjustable spring loaded suspension clip, top cross rail of 3000mm long of 0.55BMT and furring channel 4000mm long made of 0.5mm BMT the top cross rail to be suspended from ceiling at every 1200mm and furring channel to be fixed to top cross rail at every 600mm to make a grid of 1200 x 600m. All the above components are to be made of galvanized steel. The rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed. The rate quoted should include finishing the surface with putty, a coat of primer and two coats of royal emulsion paint of approved brand and color.	Sq.m	160		
2	Lamination to Doors: Providing and fixing lamination to doors in the following procedure. 1. Existing door to be removed and 6mm thick BWR Plywood of approved brand is to be fixed on both sides of door. 2. 6mm thick plywood is to be fixed to existing door and 1mm thick glossy laminate in given is to be pasted 3. Doors are to be provided with Godrej mortise locks, 2 brass half round tower bolts (top and bottom) of 200mm length, kick down door stopper of length 125mm(with hard rubber base) and handle 4. Door is to be re-fixed again to door frame with heavy duty brass hinges	Sq.m	20		
3	Lamination to Door Frame: Providing and Fixing lamination to existing door frame with 6mm thick BWR grade plywood and 1mm thick glossy laminate.	Mts	66		

4	Wall Paneling: Providing and Fixing wall paneling with 12mm thick BWR Plywood (with suitable framing work as per site condition) and 1mm thick glossy laminate.	Sq.m	50		
5	Full Height Solid Partition: Providing and fixing full height solid partition with 12mm BWR plywood and 1mm thick laminate with metal stud partition.	Sq.m	10		
6	Wall Paper: Providing and fixing Wall paper on Wall & Ceiling of approved design including base preparation etc. complete as per instructions of Architect/ Engineer-in-charge. (Wall Paper Cost range to be ₹600/- Per Sq.m)	Sq.m	15		
7	MDF JOLLY: Providing and Fixing 18mm thick MDF Jaali Partition having 150mm x 100mm wooden frame made from 18 mm BWR ply duly finished duly Du co Painted as per Design with provision of Cove Light in the Partition Complete in all respect .	Sq.m	10		
8	Curtain Rods: Providing and fixing in position approved design Heavy duty Stainless Steel curtain rods for doors and windows, 25 mm dia. 16 gauze thick, Kohinoor/ Berry/equivalent make (having minimum basic price Rs.120/- per mts) with matching approved design brackets at both sides and curtain supports at intermediate positions where length of span exceeds 1.5 m as directed by Bank's Engineer. The rate quoted shall include for the cost of materials, necessary fittings and fixtures, transportation of materials, labour charges, taxes etc. complete including removal and taking away from site the existing old wooden pelmets/rods wherever exists.	Mts	25		
9	Entrance Door Frame: Providing wood work in frames of doors framed and fixed in position including painting the portion in contact with masonry/RCC with two or more coats of Anti-termite treatment paint and fixing the frames with suitable MS holdfast duly embedded in PCC 1:3:6 or with dash fasteners in column surfaces wherever required including a coat of wood filler as per directions of Engineer-in-Charge. Using well seasoned teak wood with two or more coats of melamine polishing on one side and Duco paint on the other side to give an even shade complete as per site condition/requirement and approval of Engineer-in-Charge. The rate quoted should be for complete work and nothing extra will be paid for any minor variation required to complete the work.	Cum	0.1		

10	<p>Main Door: Providing and fixing ISI marked 30mm thick solid core flush door shutters, non-decorative type, BWP & borer resistant, core of block board construction with frame of 1st class hard wood and with 3mm commercial ply on both faces. The front side of the door shutter shall be provided with 4mm thick teak wood veneer of approved pattern and colour(Basic price: Rs.1200/- per sqm). The shutters shall be fixed to the teak wooden frames using ISI marked Stainless Steel butt hinges(100 x 60 x 1.9mm, 4Nos) with necessary screws including necessary cutting/chiseling/modifications including provision of additional wooden pieces to the door frames before fixing the doors. The work also includes providing and fixing lipping made of 2nd class teak wood battens having actual thickness from 9mm to 15mm and width equal to thickness of door, on all edges of flush door shutters with wooden adhesive of approved quality and screws/ nails as per direction of Bank's Engineer. Each door shall be provided with one Bank approved Godrej Night latch-inside opening rim lock (Product code 8261 - LKYLDN71L)with accessories and approved variety SS fixtures such as Door Handles(10" size decorative type, 1 No for outer side of door & 6" size, 1No for inner side), Tower bolt(6" size, 1No), Aldrop(10" size, decorative type, 1No for outer side & 6" size 1 no for inside), door stopper, eye piece, chain lock etc.</p>	Sq.m	4		
11	<p>MS Grill work (All windows) :Removing existing window M.S grills and modifying the same with necessary welding/cutting and fixing the same outside the new sliding window by providing & fixing additional M.S flats of same or higher size on all the sides with necessary anchorage, fastenings etc. complete as directed. The work also includes making provision for an openable shutter in the grill for fixing of window air conditioner with necessary cutting/welding and by supplying and fixing handles and aldrop with locking arrangement. The modification is to be done by providing and welding additional M.S flat sections so that the grill is fixed approximately 6" away from the wall and 3" away from the opening of window to make a box type shape. The contractor has to quote for the overall work including material, labour, T&P etc. as required complete.</p>	Sq.m	25		

12	<p>Cot : Providing and fixing of king size cot of size (2100mm x 2000mm) with 25mm thick block board for Head Board, Footboard & Side runner. The sheet of bed is to be provided with 18mm thick BWR grade plywood. The cot have 2 sliding storage units on both sides (Total 4) with suitable hinges and pull-out mechanism. Internal storages to be finished with 1 mm laminate. All Hardware fittings/accessories should be of Hettich\ Hafele with telescopic drawer units. All edge to be covered by rehau edge banding of matching color. Head board is to be provided with high density foam (100mm thick) with superior fabric (Basic cost of fabric : ₹ 500/meter) .</p>	Nos	1		
13	<p>Bed Side Tables: Providing and fixing of Side table of size 450mmx450mmx600mm by 18mm BWR plywood . Table to have two drawer units. Top of table to be provided with 6mm thick acrylic solid surface of matching color. All inner sides of table are to be provided with 0.8mm thick backer laminate.</p>	Nos	2		

14	<p>UPVC Windows: Providing and fixing factory made uPVC white colour sliding glazed window upto 1.50 m in height dimension comprising of uPVC multi-chambered frame with in-built roller track and sash extruded profiles duly reinforced with 1.60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile), appropriate dimension of uPVC extruded glazing beads and uPVC extruded interlocks, EPDM gasket, wool pile, zinc alloy (white powder coated) touch locks with hook, zinc alloy body with single nylon rollers (weight bearing capacity to be 40 kg), G.I fasteners 100 x 8 mm size for fixing frame to finished wall and necessary stainless steel screws etc. Profile of frame & sash shall be mitred cut and fusion welded at all corners, including drilling of holes for fixing hardware's and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-Charge. (Single / double glass panes, wire mesh and silicon sealant shall be paid separately). Variation in profile dimension in higher side shall be accepted but no extra payment on this account shall be made. Note: For uPVC frame and sash extruded profiles minus 5% tolerance in dimension i.e. in depth & width of profile shall be acceptable. Three track three panels sliding window with fly proof SS wire mesh (Two nos. glazed & one no. wire mesh panels) made of (small series) frame 92 x 44 mm & sash 32 x 60 mm both having wall thickness of 1.9 ± 0.2 mm and single glazing bead of appropriate dimension</p>	Sq.m	20		
15	<p>Wardrobe shutters: Providing and fixing Cupboard shutters of height (to existing built-in cupboards of height 2100mm) in given size made from 19mm BWR ply duly finished with 1mm thick laminate on exposed side and 0.8mm thick backer laminate inside. Edges of shutter are to be provided with teak wood lipping with matching paint over putty. Doors to be provided with auto closing hinges, brass tower bolts, locks and brass handles complete as per instructions of Engineer-in-charge</p>	Sq.m	35		
16	<p>Kitchen Storage shutters: Same as above but cup boards are to be made with BWP grade ply wood. Bottom shutters are to be made soild openable with auto close hinges. Middle shutters are to be glazed shutters with 6mm thick glass in ply woof frame work. Top shutters made with soild openable shutters.</p>	Sq.m	7		

17	<p>Dressing Counter: Providing and placing Dressing Counter having 450mm high x 1000mm width pullout storage at bottom and upper part to have 6mm thick Mirror of size 1000mm x1800mm with Cove Light effect. The cabinet to be made from 19mm BWR ply duly finished with 1mm thick laminate and 0.8mm thick backer laminate inside. Pull out storage to have 3 Nos Drawers with all necessary Hardware i.e Drawer Channels, Knob/ Handles, teak wood edging duly Duco Painted as per Design and instruction of Architect/ Engineer-in-charge.</p>	Nos	1		
18	<p>TV Cabinet: Providing and fixing TV cabinet made from 18mm BWR grade Ply duly finished with 1MM thick glossy laminate . Cabinet to have storage from flooring level to height of 600mm. Cabinet top to be made with 25mm thick block board finished with 6mm thick acrylic solid surface. Cabinet to have door shutters up to a height of 400mm and top 200 mm to have pull out drawers. All inner sides of storage to be laminated with 0.8mm thick backer laminate. Cabinet to have wall paneling from 600mm to 2100 mm height with aluminum stud frame work and 18mm thick BWR grade plywood and 1mm thick glossy laminate. A vertical storage unit of size 400mm x 1500mm is to be provided on top of bottom storage. Vertical storage unit have 12 mm thick glass and 8mm thick glass door. The work includes all hardware i.e handle, locks, Drawer Channels, Crank Hinges etc. All edges of plywood to have teak wood lipping with matching duco paint.</p>	Sq.m	7		
19	<p>Storage Units: Providing, making and placing in position storage units upto 750 mm height or height as directed and 450 mm deep made with 18/19 mm BWP plywood front sides and to be laminated with 1mm thick laminate of given color. All inner surfaces are to be laminated with backer laminate of 0.8mm thick. Storage unit to have pull-out drawers/openable shutters as directed by Engineer-in-charge. The rate to include cost of all necessary hardware viz., cabinets hinges, locks, handles, sliding channels tower bolts etc. The unit should have beech wood beading 25 X 40 mm at top and edge lipping 20 X 6 mm complete.(Basic Cost of laminate is Rs450/Sq.Mt). All makes and materials are to be get approved by Engineer-in-charge before using. All edges of door should be provided with edge banding.</p>	Sq.m	5		

20	<p>Granite Platform: Supply and laying of 18-25mm thick Black galaxy granite slabs with double edge moldings and granite strip attached under the granite over hung to make it look thick all material, labour, installation, transportation, lead, lift, consumables, tools, tackles, instruments, machines, etc all complete as directed by the Engineer-in-charge.</p>	sq.m	7		
21	<p>Supply and installation of cement particle board of 18mm thickness beneath the granite slab including all material, labour, installation, transportation, lead, lift, consumables, tools, tackles, instruments, machines, etc all complete as directed by the Engineer-in-charge</p>	Sq.m	5		
22	<p>Modular Kitchen :Supply and installation of modular kitchen consisting Floor Unit, Top Unit & Accessories. (Make-Godrej Interio or Space wood or Sleek or equivalent to already installed modular kitchen at site) for floor unit of IS 710 Marine plywood boiling water proof carcass, post form look IS 710 Marine plywood boiling water proof plywood of 16mm thick with lamination of 1mm each sides shutters (Make- Greenlam / Merino/ Century / Archid / Vir Laminate / Aica/Formica or Equivalent) Handle with Aluminum profile handle fixed to door, soft closing hinges for hinged doors, M10 screw type leveler with hexagonal plastic base and all cooking, bottle pullout baskets, etc of SS 304 grade Hettich/Hafele or equivalent make. All Complete as per the approved colour, dimensions, drawings, shapes and detailed specifications of the manufacture with overall allowable tolerance ranging from length 100- 150mm, height 15-30mm and depth 30-50mm. The scope of work includes all material, labour, installation, transportation, lead, lift, consumables, tools, tackles, instruments, machines, etc all complete as directed by the Engineer-in-charge.</p> <p>Floor and Top wall cabins should be fixed as mentioned.</p> <p><u>Floor Unit:</u> Consisting 8 units of each depth 560mm, height 700mm and comprises the following items as shown in the drawing.</p> <p>A. 300mm wide Cargo Bottle Pull Out Kit with 2 baskets. B. 900mm wide Cooking Kit (2 nos Plain Basket of 100mm ht with 175mm ht drawer front & 1 no Plain Basket of 150 mm ht with 350mm ht drawer front + Hettich/Hafele make PVC cutlery Tray).</p>	Ls	1		

	<p>C. 600mm Wide Thali Kit (1 Drawer with cutlery tray, 1 Cup-saucer basket with 100 mm height, 1 Thali basket 150 mm height for Thali plates)</p> <p>D. 900mm Utensil Kit (2 nos plain basket 150 mm ht)</p> <p>E. 900mm wide sink unit with 2 nos 450mm wide hinged door excluding sink.</p> <p>F. 1000mm wide Plain Shelf Unit each with 2 nos 500mm wide hinged door</p> <p>G. 900mm wide plain shelf with 1 no 450mm hinged door.</p> <p>H. 800mm wide plain shelf unit with 2 no 400mm wide hinged door.</p> <p>J. 40mm wide filler</p> <p>Top Unit (Wall cabinet): Consisting 2 units of each of depth 300mm, height 700mm and 2 units of 350mm height and 300mm depth and comprises the following items as shown in the drawing.</p> <p>a) 4 nos. 1000mm wide plain shelf unit each with 2nos 500mm wide shutter.</p> <p>Accessories: In Dado Space(Between top and floor units) made of SS304 Grade</p> <p>a) Double Multi Purpose Rack</p> <p>b) Plate Rack</p> <p>c) Double corner rack</p> <p>d)Cutlery Drainer</p> <p>e)Rods with Hooks</p>				
23	Chimney :Supplying, commissioning and testing of Chimney (Ebony 90/ Elica 1100/ Faber or equivalent)	Nos	1		
24	SS Sink : Supplying and fixing stainless steel sink of overall size 610 x 458 mm with bowl size 22" x 16" x 9" conforming to SS 304 grade/1mm thick of approved make, the joints with granite slab shall be sealed thoroughly with epoxy/ silicon sealant, including all necessary fittings and fixtures, CP waste coupling, PVC flexible waste pipe etc. all complete as directed by the Bank's Engineer.	Nos	1		
25	Royal Emulsion Painting with Putty: Cleaning the surface of the wall & then applying Two coat of Wall-care putty one coat of primer to give smooth finish exactly in line and level & then finally applying one coat primer and two coats of NO VOC or LOW VOC Plastic Emulsion Paint of approved shade to give a neat finish including cost of all materials necessary scaffolding etc., complete for walls & ceiling.	Sq.mt	480		

26	Plastering: Providing and laying 12-15mm thick plaster in cement mortar 1:4 (1cement : 4 fine sand) to all types of brick work surfaces.	Sq.mt	50		
27	Brick Work with plastering: Providing and laying 115 mm thick brick masonry in walls with bricks of class designation 75 in cement mortar 1:4 (1 cement : 4 coarse sand) at all levels in proper plumb, line and level, including scaffolding, curing, racking of joints etc. including providing 3 nos.8 mm dia bars after every fourth course complete as per instructions at site. Rate quoted should include providing openings. Rate quoted should include plastering the surface with two coats of Cement plastering using 1:4 Cement mortar	Sq.mt	8		
28	Same as above but 230mm thick Brick work	Sq.mt	5		
29	Wall Tiles: Providing and fixing of wall tiles of 300x600size or approved size of approved colour, design and make over a base plaster of 15mm thick on the dismantled surface and 12 mm thick cement plaster 1:4 leveling course and filling / grouting the joints with white cement slurry mixed with approved matching colour with tiles at all levels with all required tools, plants, materials and labour required to complete the work in all respects as directed by Bank. The Basic cost of the tile is ₹600.00 per Sq.Mt the above basic cost does not include tax, transportation etc at site should be assumed to arrive the tender rate. No extra claim towards wastage. Make: Johnson,AGL, Kajaria or Equivalent all complete as directed by Bank	Sq.mt	100		
30	Floor Tiles: Providing and laying of anti skid vitrified floor tiles of approved colour and design 10 mm thick floor tiles of approved make and 2" x 2" size fixed over 20 mm thick cement base mortar 1:6. The scope work is inclusive of providing proper slopes for better drainage of water to the traps, filling the joints with neat cement and matching pigment etc complete in all respects as directed by Bank. The basic cost of the tile is Rs 650.00 per Sq.Mt. The above basic cost does not include tax, transportation etc at site should be assumed to arrive the tender rate. No extra claim towards wastage Make: Johnson, Somany, Kajaria or Equivalent	sq.mt	15		

31	Wash basin Counter: Providing and fixing Wash basin cabinet of depth 600mm in 6mm thick Acrylic Solid over 12mm thick cement board. Rate quoted should include necessary frame (if required) with Aluminum Box Sections of size 50mmx 50mm. Rate quoted should be inclusive of drawer units along with handles. All Exposed surfaces should be covered with 6mm thick acrylic solid surface. Area will be measured multiplying length and height of unit.	Sq.m	1		
32	EWC : Supply, installation and commissioning approved make wall hung EWC with built-in flush tank, angle stop cock complete including cost all taxes and all labor charges etc., complete including, cutting and making good the walls and floors wherever required. Basic cost of EWC is ₹10000.00	Nos	1		
33	EWC: Supply and installation and commissioning approved make floor mounted EWC with flush tank, angle stop cock complete including cost all taxes and all labor charges etc., complete including, cutting and making good the walls and floors wherever required. Basic cost of EWC is ₹8000.00	Nos	2		
34	Wash Basin: Supply and fixing of counter top wash basin of approved make & design along with all required fixtures. The scope of work is inclusive of provision of Bottle trap with coupling, hose pipe etc complete in all respects as directed by Bank. Basic cost of counter top wash basin is Rs.8500/- complete and as directed by Engineer-in charge.	Nos	4		
35	Providing & fixing C.P. heavy quality Bib cock, with wall flange, including jointing using Teflon tape etc. complete. The rate shall be inclusive of all the material, labour, hardware, transportation necessary required for the complete execution of the item complete and as directed by Engineer-in-charge.	Nos	7		
36	Providing and fixing (with all necessary materials like Telflon Tape etc) 2 in 1 angle cock of basic cost ₹ 1500	Nos	3		
37	Providing and fixing Health Faucet with hook and pipe of Hindware , Jaquar or approved equivalent. Basic cost of Health faucet is ₹2000.00	Nos	3		
38	Providing and fixing Master Control valves in toilets (with all necessary materials like Telflon Tape etc)	Nos	3		
39	Providing and fixing sink cock (with all necessary accessories) of Hindware/Jaquar or approved equivalent with basic cost of ₹ 2500	Nos	3		
40	Providing and fixing of wall mixture of basic cost ₹ 7000	Nos	1		
41	Providing and fixing wall mixer of basic cost ₹5000	Nos	2		

42	Providing and fixing of corner shelves of Hindware are jaquar make	Nos	6		
43	Providing and fixing of Shower enclosuer along with suitable frame work made with 8mm toughned glass with etching (Jaquar/hindware or approved equivalent)	Sq.m	4		
44	Providing and fixing Towel Shelf of Hindware or approved equivalent brand with basic cost of ₹3100	Nos	1		
45	Providing and fixing of double Towel rod of Hindware or approved equivalent with basic cost of ₹1950	Nos	2		
46	Providing and fixing of Robe hooks of Hindware or approved equivalent brand with basic cost of ₹650	Nos	3		
47	Providing and fixing of Over head showers along with rod of Hindware or approved with basic cost of ₹2000	Nos	3		
48	Providing and fixing of Hand shower with all accessories of hindware or approved equivalent with basic cost of ₹ 3000	Nos	1		
49	Providing and fixing of Hand shower with all accessories of hindware or approved equivalent with basic cost of ₹ 2000	Nos	2		
50	Providing and fixing swan neck sink cock of Hindware or approved equivalent	Nos	1		
51	Providing and fixing chlorinated polyvinyl chloride (CPVC) pipes of 20 mm diameter of approved quality and make, having thermal stability for hot and cold-water supply, including providing and fixing CPVC plain & brass threaded specials of same make, fixing the pipes with clamps at 1 mtr. spacing for concealed work including cutting chases in the wall to the required depth, connecting to the existing duct line, jointing of the pipes and fittings with one stop CPVC solvent cement of approved quality and make, making good the damages, etc. complete. The rate shall include for pressure testing of joints/ pipelines for leakage etc., all complete as directed by the Bank's Engineer.	Mts	75		
52	Same as above but for 25mm diameter pipe	Mts	25		
53	Providing, laying and testing 150mm diameter PVC drain pipes along with bends , coupling etc.	Mts	10		
54	Providing and fixing of frame less mirrors of 8mm thick with SS Studs along with suitable water proofing boards. Rate quoted should be inclusive edge bevelling etc.	Sq.m	4		
55	PCC: Providing and laying PCC (1:2:4) with 20 mm nominal size coarse aggregate and river sand	Cum	5		

56	Providing and fixing of Paver tiles of basic cost ₹500/Sq.m inclusive of all adhesive materials	Sqm	10		
57	Providing and applying at all heights the Berger weather coat smooth/Apex Ultima paint to all type of cement plasters, concrete, exterior ceiling etc. or surface/ sub straits (which are subjected to continuous seepage and dampness). The surface to be painted shall be made free from any loose paint, dust, grease and any fungus, algae or moss on it shall got be removed thoroughly by vigorous wire brushing and cleaning with water. Then one coat of professional exterior grade wall primer be applied after which any surface imperfection such as holes, dents, fine cracks shall be corrected by filing with wall putty. Thereafter second coat of exterior grade wall primer and again surface imperfection to be corrected. Thereafter Berger weather coat smooth/Apex Ultima paint be applied in two coats. All materials shall be of Asian/ British/ Nerolac make. The color and pattern/ color combination of the paint shall be got approved form Engineer in Charge. The stock of the quantity for all material as per manufacturer's theoretical consumption (per unit of surface area) shall be made available at site before commencement of the painting work. The rate shall include cost of all material, labor, scaffolding, ladders charges, storing & safeguarding the material etc all complete. (The rate quoted should be inclusive of scaffolding at all heights if required, labour, materials etc all complete as directed)	Sqm	170		
58	Enamel painting to Grills: Providing 2 or more coats of enamel painting existing iron grills after scrapping the existing paint. Rate quoted should be inclusive of one coat of primer. Area of grill will be taken for measurement	Sqm	40		
59	Providing and fixing nahni traps with ss jolly	Nos	4		
60	Providing & injecting chemical emulsion for post-constructional anti termite treatment for already built up area on all floors complete with Chloripyrophos Emulsifiable concentrate 1%. The treatment shall be carried out through an authorized/specialized agency. (only plinth area at ground floor shall be measured for payment)	Sq.m	170		
61	Carefully dismantling existing GI Sheet shutters to existing cupboards kitchen and stacking the removed items outside the premises	Sq.m	40		
62	Dismantling the existing ceramic tile, Glazed tile, IPS floor/ wall dado and carting away derbies to a dump yard approved by local municipal authorities	Sq.m	100		

63	Carefully dismantling existing windows/ventilators and stacking them in the premises and making them good for fixing UPVC windows.	Sq.m	21		
64	Dismantling false se ceiling, partitions or any wood furniture along with supporting channels and carting away derbies to a dump yard approved by local municipal authorities	Sq.m	120		
65	Dismantling of all sanitary Fixtures like EWC, Wash basin etc in 3 Wash rooms	Job	1		
66	Dismantling of existing plumbing lines and carting away derbies	Job	1		
67	Dismantling of Brick work and carting away derbies.	Sq.m	10		
	Total				
	Discount if any (Express in terms of percentage)				
	NET TOTAL				

Dated Signature of Agency with Seal.