

SBI UNIFORM LAYOUT & COLOUR SCHEME POLICY

(A) INTERIOR FURNISHING WORKS IN SBI RAWATBHATA BRANCH (31265)

S.No	Title	Description	Unit	Quantity	Rate	Amount
False ceiling						
1	Gypsum False Ceiling	A) P&F false ceiling with Gypsum Board 12.5mm thick fixed to a metal frame comprised of ceiling channel of size 80mm X 26mm X 0.5mm @ every 450 cms centres, inter channel 45mm X 15mm X 0.9mm @ every 1220mm centres, peri-meter channel 20mm X 26mm all along the wall, strap hanger suspendeds 25mm X 0 5mm with nuts and bolts 6.4mm x 12.7mm, connecting clip 2.64mm thick, dry walls screw 25mm long , soffit cleat. 27mm X 37mm X 25mm X 1.6mm thick and dash fastener/ rawl plug 12.5mm dia X 35mm long with 6mm dia bolt. The joint of gypsum board to be taped 3 times and sealed with jointed compound with three coat plastic emulsion paint finished. Cut-out are provided to accommodate luminaries, air conditioning grills and fire warming detectors if any. The rate to include two or more coats of approved paint after preparing the surface. All fitting to be separately hung from the ceiling and should not rest on the false ceiling.	Sqm.	70		
2	Grid False Ceiling	The grid false ceiling shall be provided in the Banking Hall, Manager's etc. The ceiling height and level shall be determined at the perimeter. The minimum height of the ceiling cavity should be 100mm. All service fittings integrated within the suspended ceiling must be independently supported from the ceiling grid by a structure designed for the purpose. <input type="checkbox"/> Ceiling files Shall be of Armstrong brand ◆ Installation Main runners will be placed at 1200mm centers securely fixed to the structural soffit by approved hangers at 1200mm maximum centers and not more than 150mm from spliced joints. The last runner at the end of each main runner should not be greater than 600mm from the adjacent wall. 1200mm long cross tees to be interlock between main runners at 600mm centers to form 1200x600mm modules. Cross tees longer than 600mm require independent support. 600x600mm modules to be formed by fitting 600mm long cross tees centrally between the 1200mm cross tees. The 1200mm cross tees to have central "birdsmouth" notches to facilitate fitting of 600mm cross tees. The perimeter trim to be Armstrong Trulok equal wall angle of white color secured to walls at 450mm maximum centers.	Sqm.	110		
Full Height Partition						
3	Full Height Partition (Wooden with Laminate)	providing fabricating & fixing of partition made out with unanodised G.I Framework consisting of 2'x1' 18 gauge section placed at min 2'x2' horizontally & vertically (as per site requirement) with 12mm water proof MDF Board /12mm thick commercial grade ply ply finished with 1mm thick high gloss laminates (of approved shade) on both sides (as approved) . The sides /top shall be finished with teak wood beading (3' x 1') with high gloss PU finish . This partition will be 3' ht. with up to 15" ht.12mm thick toughened clear glass / of aqua blue shade (approved make) . The partition shall also be provided with 12mm toughened glass partition between counter from 4'3" ht. with top width into 12.5" wide at top & sloping downwards with 6" x 3" x15" pillar . The back side of counter will be provided similar partition upto 4'3" ht. with flap door of 2' width with hinges, handle ,ultra lock complete .	Sqm.	20		
Partition as above in Sqft. (top width including partition glass & ht. will be measured for payment)						
4	Low Height Partition (Wooden with Laminate)	providing fabricating & fixing of partition made out with unanodised G.I Framework consisting of 2"x1", 18 gauge section placed at min 2'x2' horizontally & vertically (as per site requirement) with 12mm thick water proof MDF Board /12mm thick commercial grade ply finished with 1mm thick high gloss laminates (of approved shade) on both sides. The sides / top shall be finished with teak wood beading (3" x 1") with high gloss PU finish. This partition will be upto 3' ht. with 18" ht.12mm thick toughened clear glass / aqua blue shade (approved make). The partition shall also be provided with 12mm toughened glass partition between counter upto 4'-6" ht. with 6" x 3" x15" pillar. (Partition in sqft. including glass ht. & width will be measured for payment)	Sqm	32		
Note: All partition frame work shall be fixed to beam / slab soffit. Measurement shall be paid upto finished partition level only.						
Wall Finishing / Panelling						
5	column /wall panelling (Laminate)	Providing & fabricating of column / wall panelling made out with unanodised G.I Framework consisting of 2" x 1" ,18 guage section placed at min. 2'x2' horizontally & vertically (as per site requirement) with 12 mm water proof MDF Board 12 mm thick commercial grade ply. G.I Framework with MDF Board skinning 1mm th. mica of approved shade over the coloumns / wall & necessary vinyl prints as per approved drawings. The rates are including the design provided in the approved	Sqm.	136		

6	MDF Jali column	MDF jali work in central column with 8mm thk blue lacquered glass behind & cove with LED lights finished with high glass paint central columns as per design & pattern approved by Architect / Bank's Engineer.	Sqm.	0		
7	A.C.P. PANELLING (Internal 3 mm)	Providing & fixing full height interior grade A.C.P. wall paneling 3 mm thick in two or more shades/ design fixed on 50 X 25 Aluminum frame at 600 centre to centre both sides horizontal & vertical. The paneling to be finished with silicon complete in all respects as per Bank/ Architect.	Sqm.	0		
8	A.C.P. PANELLING (External 4 mm)	Providing and fixing in position Aluminium composite panel Boxing with PVDF coating & LDPE core laminated Eurobond / Altobond/ Alukbond Exterior Grade 4 mm thick with composite of (0.5mm - 3mm- 0.5mm) including fabrication for the same with aluminium sections, required hardware, silicon sealant (Dow Corning 789) masking tape, necessary scaffolding etc. complete in all respects.	Sqm.	46		
9	Plastic Emulsion	Supply and application of washable interior grade Dulux 3-in-1 plastic emulsion paint on walls with 1 coat of wallprimer and 2 or more coats of plastic emulsion paint as per manufacturer's specifications etc. all complete. All painting final coats to be done after removal of face plates of switch boards in coordination with the electrical contractor and face plates to be fixed only after satisfactory completion of painting.	Sqm.	240		
10	Enamel Paint	Providing & laying 2 or more coats of Synthetic Enamel paint for existing grill & railing as per Bank's instructions.	Sqm.	35		
STORAGE CABINET						
11	Storage (Laminate top)	Providing and fixing wooden storage 450 mm wide having sides, partitions shelves and shutter made of 19 mm th. Board with 1 mm th. High gloss laminate with all other exposed internal / external surface provided with Duco paint with melamine coating complete with side hinged shutter complete with handles , locks etc. (for the purpose of contractor's payment only front elevation area of a cabinet will be measured .	Sqm	20		
TABLE/ COUNTERS & RACKS						
12	Branch Manager table	Supply & fixing in position branch head table (size 3' x6') made out of 19 mm thick BWR board with 4mm th. /teak veneer with high glass PU FINISH on table top complete. Drawers shall have ball bearing slides & locks etc. complete internal surface shall be finished with 1.00 mm th. laminated with high glass white laminate. each table shall have the provision of key board with ball bearing slides. Table glass top 10 mm is included in the rate . The Design will be as per drawing approved	No.	1		
13	Officer's table with laminations	Supply & fixing in position officer's table (size 2'-6" x upto 5'-0") made out of 19 mm thick board with 1 mm white laminate top at 2'6" ht. with drawer , CPU & keyboard tray as per single window counter & shutters complete as for single window cabinets completed in all respects . The table top will have glass of 10 mm th. is also included in the item .	No.	8		
15	Centre table	Providing & Keeping centre table made out of 18 /12 mm thick plywood & 6/12 mm thick the plywood as per design . The top should be finished with edges of 2" thick the vertical support should be of 24" dia. Etc. complete with necessary hardware . The top surface with edges should be finished with 12 mm th. salt colour dupont corian solid surface etc. complete as per detailed drawing & instruction of Architect / engineer.	No.	1		
16	HELP DESK / TECH MITRA	GRAHAK MITRA / TECH MITRA counter made out of 19 mm BWR BOARD WITH WHITE Corian & blue acquired glass as per approved drawing with conceal LED light in skirting level of size 2'3x 5' .Top shall be finished with white CORIAN . THE Rates are including the design provided in the approved drawing . complete in all respect with necessary drawers etc as directed . A SS 304 plate of size 10" x 20" with GRAHAK.	RM	0		
17	HELP DESK / TECH MITRA (With Laminated top)	Same as above except 1 mm laminate instead of Coarian top Counter as above in Running feet.	RM	3		
18	PRODUCT RACK	Providing & placing in position 2'-6" / 3'-0" .High and 1'-6" deep box type PRODUCT RACK made out of 19 mm BWR Board with white CORIAN. Outside edge of the working top shall be provided with blue lequered glass / blue shed high glass PU coating facia. inside edge finished with 0.8 mm th. laminate with side hinged shutters complete with handles ,locks etc.complete. (for the purpose of contractors payment only front elevation area will be measured for payment.	SQM	0		
19	PRODUCT RACK (with Laminate)	Same as above except 1 mm laminate instead of Coarian top Counter as above in Running feet.	sqm	2		
TOUGHENED GLASS WORK						
20	12 MM TH. TOUGHENED GLASS PARTITION	FULLY GLAZED 12 MM TH. TOUGHENED GLASS PARTITIONAs above item no 1 Aa (both side gyp. board finished partition but partition shall have 12 mm th. Toughened plane glass fixed with 1 1/2" x 1" teak wood moulding finished with white high gloss laminate 4mm teak wood veneer finished with stainless steel "D" Brackets etc . Complete as per	Sqm	6		

21	12 MM TH. TOUGHENED GLASS Door	12 MM TH. TOUGHENED GLASS Cabin door providing & fixing main doors/cabin made out of/cabin door made out of HNG/ Asahi India MAKE 12 MM TH.toughened plain glass in single piece with computerised diamond cut & diamond edge polish including making required cutout holes for lock , handles , pivot patch fitting , corner fitting hinges etc. the rate is inclusive of patch fitting of dorma make floor spring ,pivot patch fitting with cover plate locks handles , singsges with necessary hardware rtc. as per intructions of Architect/Engineer.	SQM	8		
22	Wicket Gate	Wicket gate have to match with the partition / counters. Wicket gate should be made up of 32mm flush door finished with 1mm laminate. The door shall have SS finished door lock, heavy duty SS hinges, SS handles, door stopper etc. as per schedule of interior, furniture & finishes. Refer schedule of interiors, furniture & finishes. Refer drwgs.	SQM	3		
FINISHING WORKS						
23	3M Frosted Film	Providing & fixing in position '3M' make frosted glass film in stardust range fixed to glass as per pattern. Area of application to be measured as maximum length x maximum height of application on that particular piece of glass.	Sqm	14		
24	Roller Blinds	Providing and fixing Roller blinds of required width & Length quality of approved make fabric made of 100% polyester thickness 0.30mm with Acrylic coating resistance to Cracking & Fraying and treated for dust repellency, UV proof , virtually maintenance free having plastic bottom chain thickness of chain 0.50mm and diameter-3mm, weight per sqm 201g, Degree of opacity 100%, Light frastness 4/6, Plastic with metal bottom weight - 116.20mmX48.30mm and suitable coating on exterior, including all fixtures and fittings complete in all respect as per design/color/shade including requisite installation brackets etc as required for installation at site with anchoring arrangements complete as directed.	Sqft	100		
25	Louver Shutter for electrical panel	Providing & fixing Shutter Boxing for rolling shutter made 19mm thick fire resistant boards such as Bison board etc. finished with 1.0mm thick laminate including hinged cover as per approval of Architect / Bank's Engineer.	Sqm	7		
OTHER WORKS						
26	FLUSH DOOR	Providing and fixing flush door with 35mm water proof door with 1mm high glass laminate (of approved shade) on both sides The item includes 75C50mm TW chouchat , 7 lever mortise lock, SS handle, stopper hinges, paint/polish etc complete	Sqm.	2		
27	DOOR CLOSURE	providing & fixing door closure of Godrej/ Dorma/ Ozone of two speed (heavy duty , light weight thin. Type code : 3976) as approved by etc.	No.	2		
Total Excluding GST (A)						