

**PRICE BID**  
**BOQ FOR PROPOSED INTERIORS FOR STATE BANK OF INDIA,**  
**DAMARCHARLA BRANCH. (TELANGANA.)**

**SCHEDULE OF QUANTITIES AND DETAILED SPECIFICATIONS**

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
<b>I.</b>	<b>INTERIOR WORKS:</b>				
<b>1</b>	<b>FULL HEIGHT PARTITIONS:</b>	20		Sq.M.	
	Providing and fixing metal stud dry wall partition with following specifications: The Partition will be fully opaque OR partly opaque and partly glazed as per specific site conditions and drawings.				
	(a) Supporting system comprising of 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs at 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings.				
	(b) 12mm MDF Exterior Grade Board fixed on both sides with 25mm dry wall screws for the entire height of the partition.				
	(c) Partition from floor level upto 2350mm level to have 8mm x 100mm Fiber Cement Board / Calcium Silicate Board / Reinforced Magnesium Silicate Board as Skirting clad with 1mm glossy Laminate (silver color) at bottom + from 100mm to 300mm level to have 1mm Glossy Laminate (blue color) + from 300mm level to 1050mm level to have 1mm Glossy Laminate (white color) + from 1050mm level to 1185mm level 1mm Glossy Laminate (blue color) + from 1185mm level to 2250mm level to have 1mm Textured Glossy Laminate (white color) + from 2250mm level to 2350mm level 1mm Glossy Laminate (blue color) on both sides as shown in drawing.				
	(d) Partition to have 8mm clear float glass fixed with 85mm x 15mm around MDF Exterior Grade jamb and 12mm x 12mm MDF Exterior Grade button beading on both sides of the glass, to a neat finish as per drawings and directions etc., complete.				
	(e) Partition above 2350mm level to have 1mm Laminate (White color - Matt finish) / NO VOC or LOW VOC plastic emulsion paint finish on both sides as shown in drawing.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(f) All exposed surfaces of MDF Exterior Grade members to have minimum two coats of LOW VOC or NO VOC duco paint finish. (g) All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				
<b>2</b>	<b>HALF HEIGHT PARTITIONS:</b>	25		Sq.M.	
	Same as item 1.1 above, but for height of 1200mm from finished floor level, to a neat finish as per drawings and directions etc., complete and the following: (a) 15mm x 75mm capping of MDF Exterior Grade Board on top, 38mm x 12mm bands of MDF Exterior Grade Board on both sides of the partitions horizontally and vertically upto skirting finished with minimum two coats of LOW VOC or NOW VOC duco paint as per drawings and directions etc., complete. (b) Partition from floor level upto 1200mm level on both sides to have 8mm x 100mm Fiber Cement Board / Calcium Silicate Board / Reinforced Magnesium Silicate Board as Skirting clad with 1mm glossy Laminate (silver color) at bottom + from 100mm to 300mm level to have 1mm Glossy Laminate (blue color) + from 300mm level to 1085mm level to have 1mm Glossy Laminate (white color) + from 105mm level to 1185mm level 1mm Glossy Laminate (blue color) + from 1185mm level to 1200mm level to have 15mm thick MDF Exterior Grade Board on both sides finished with minimum two coats of LOW VOC or NOW VOC duco paint as shown in drawing. (c) The cost to include all materials and hardware required etc., as per site conditions. The rate is for a finished item of work etc., complete as directed.				
<b>3</b>	<b>FIXED GLASS WORKS: (12MM TOUGHENED GLASS WORK WITH MAIN ENTRANCE DOOR AND GLASS</b>	21		Sq.M.	
	Providing, making and fixing in position Fixed 12mm / 10mm toughened glass as fixed glass from Floor to available Ceiling level along with Main Entrance Door and for Partitions. The glass is to be fixed with patch fittings and all the edges of the glass have to be polished for a smooth finish. The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
4	<b>12MM TOUGHENED GLASS MAIN ENTRANCE DOOR AND PARTITION DOORS:</b>	9		Sq.M.	
	Providing, making and fixing in position Fixed 12mm / 10mm toughened glass openable shutters work as per specifications given below and for the openings mentioned. Main Entrance Glass Work comprising of Door opening of approximate size 1800mm x 2250mm - 2400mm in two pieces, and Partition Doors of approximate size 900 - 1000mm x 2250mm - 2400mm. The entire work to be done as per site conditions with following specifications etc., complete as directed.				
	(a) Entrance door - Providing, fixing in position glazed entrance Double door and Single door with patch fitting or approved make (Double Door approx. Size: 1800mm - 1500mm x 2400mm - 2250mm and Single Door approx. Size: 900mm - 12mm x 2400mm - 2250mm) using 12mm / 10mm toughened glass edge polished. The Door to consist of Heavy Duty Floor spring, Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Corner Lock and the side fixed glass to have 2 Nos. Bottom Patch and 2 Nos. Upper Patch for each door to a neat finish etc., complete as per drawing.				
	(b) The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.				
5	<b>WALL PANELLING:</b>				
5.1	<b>WALL PANELLING IN BANKING HALL:</b>	25		Sq.M.	
	Same as item 1.1 above, but for Wall Panelling. The basic frame work to comprise all cladding specified only from one side to a neat job as per drawings and directions etc., complete.				
	(a) Providing 15mm thick MDF Exterior Grade jamb for door and window openings of suitable depth as per site conditions.				
	(b) All exposed surfaces of MDF Exterior Grade members to have NO VOC or LOW VOC duco paint finish.				
5.2	<b>WALL PANELLING WITH SPECIAL HIGH GLOSS LAMINATE FOR E-LOBBY:</b>	30		Sq.M.	
	Same as item 1.4 above to be cladded with 1mm High Gloss Laminate ( <b>Laminate Base Rate Rs - 600/- Sq.M.</b> ) from one side to a neat finish as per drawings and directions etc., complete. (Wall Panelling back of Machines to be with Blue color and other walls to have White color 1mm Special High Gloss Laminate)				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
5.3	<b>COLUMN PANELLING:</b>	16		Sq.M.	
	Providing and fixing metal stud column panelling with following specifications:				
	(a) Supporting system comprising of 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs at 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings.				
	(b) 12mm MDF Exterior Grade Board fixed on all four sides with 25mm dry wall screws for the entire height of the partition.				
	(c) Column Panelling from floor level upto 2350mm level to have 8mm x 100mm Fiber Cement Board / Calcium Silicate Board / Reinforced Magnesium Silicate Board as Skirting clad with 1mm glossy Laminate (silver color) at bottom + from 100mm to 2350mm level to have 1mm Glossy Laminate on two longer sides of the column as shown in drawing.				
	(d) Column Panelling to have 8mm toughened lacquered glass in blue color fixed with 12mm x 12mm MDF Exterior Grade button beading on two shorter sides of the column, to a neat finish as per drawings and directions etc., complete.				
	(e) Column Panelling above 2350mm level to have 1mm Laminate (White color - Matt finish) / NO VOC or LOW VOC plastic emulsion paint finish on all four sides as shown in drawing.				
	(f) All exposed surfaces of MDF Exterior Grade members to have minimum two coats of LOW VOC or NO VOC duco paint finish.				
	(g) All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				
6	<b>FALSE CEILING:</b>				
	Providing, making and fixing in position the following types of different false ceilings with different materials as specified below for a finished item of work as per drawings and directions etc., complete.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
6.1	<b>GRID FALSE CEILING:</b>	60		Sq.M.	
	<p>Providing &amp; Fixing of Mineral Fibre Acoustical Suspended Ceiling System with 15mm Tiles and Exposed GRID. The tiles should have Humidity Resistance (RH) of 90% - 99%, NRC 0.5, Light Reflectance ≥87%, Thermal Conductivity k = 0.052 - 0.057 w/m K, Colour White, Fire Performance UK Class 0 / Class 1 (BS 476 pt - 6 &amp;7) in module size of 600 x 600 x 16mm, suitable for Green Building application, with Recycled content of 30% - 45% . (DUNE SUPREME / DUNE OF ARMSTRONG MAKE - RADAR CLIMAPLUS / PIN PERF CLIMAPLUS OF USG BORAL / CELOTEX PIN OF GYPROC)</p>				
	<p>The tile shall be laid on Silhouette / Microline / Omega DXM profile grid system with 15mm - 16mm white flanges incorporating a 6mm central reveal in white/black colour and with a web height of 38mm and a load carrying capacity of minimum 8 Kgs/M2 &amp; minimum pull out strength of 100 Kgs. Microline / Silhouette, Main Runners &amp; Cross Tees to have mitred ends &amp; "birdsmouth" notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 90 grams per M2 and need to be installed with Suspension system as per manufacturers details.</p>				
	<p>The Instalation to comprise main runner spaced at 1200mm centres securely fixed to the structural soffit using US Boral / Gyproc / Armstrong suspension system (specifications below) at 1200mm maximum centre. The First/Last suspension system at the end of each main runner should not be greater than 450mm from the adjacent wall.</p>				
	<p>Flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm centre to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees. Perimeter trim to be Wall angles of size 3000mm x 19mm x 19mm, secured to walls at 450 mm maximum centres.</p>				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
6.2	<b>PLAIN FALSE CEILING:</b>	90		Sq.M.	
	<p>Providing and fixing Concealed Grid suspended ceiling system of 12.5mm Gypsum Boards / Standard Plaster Boards fixed to ceiling Frame Work as per manufacturers instructions and details for a concealed grid key lock suspended ceiling system consisting of following:</p> <p>(a) 27 x 37 x 1.6mm Soffit Clip, 5mm suspension rod / 25 x 10 x 0.5mm Ceiling Angle, adjustable spring loaded suspension clip / 2.64mm dia Connecting Clip, 20 x 28 x 30 x 0.5mm Perimeter Channel, Top Cross Rail of 3000mm long of 0.55BMT Furring Channel / 15 x 45 x 15 x 0.9mm Intermediate Channel and 4000mm long made of 0.5mm BMT the Top Cross Rail / 80 x 26 x 0.5mm Ceiling Section to be suspended from ceiling at every 1200mm and Furring / Intermediate Channel to be fixed to Top Cross Rail / Ceiling Section at every 600mm to make a grid of 1200 x 600mm.</p> <p>(b) All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.</p> <p>(c) Further the rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed.</p>				
6.3	<b>VERTICAL FACES IN FALSE CEILING:</b>	10		Sq.M.	
	Same as item 1.9.2 above but for vertical faces in false ceiling as per drawing including cut outs for AC grilles etc., complete as directed.				
7	<b>STORAGE UNITS:</b>	10		Sq.M.	

S.No.	Item. / Particulars.	Quantity.	Rate.	Unit.	Amount.
	<p>Providing, making and placing in position Storage Units with horizontal partitions of 1200mm high abutting wall and 750mm high as back credenza or abutting partition made in 18mm MDF Exterior Grade Board to all members except table top and 25mm block board for table top. The top of the storage unit to have 1mm thick Laminate and the front facia of the storage unit to have 50mm x 12mm MDF Exterior Grade Board finished with minimum two coats of LOW VOC or NOW VOC duco paint. All other exposed faces of the unit to have 1mm Glossy Laminate as specified and all unexposed faces to have 0.8mm Laminate OR NO VOC or LOW VOC enamel painting with putty finish on all unexposed faces including NO VOC or NO VOC duco paint finish for all other exposed surfaces of MDF Exterior Grade members and all necessary hardware viz., 'W' or wing hinges, locks, handles, tower bolts etc., and MDF Exterior Grade beading 36mm x 36mm at top and MDF Exterior Grade edge lipping 18mm x 12mm etc., as per drawings and directions etc., complete.</p>				
8	<b>BRANCH HEAD TABLE:</b>	1		Each.	
	<p>Providing, making and placing in position Executive Table and Side Table of approximate size 2400mm - 2100mm x 900mm x 750mm + 1200mm - 1050mm x 450mm x 750mm with following specifications.</p> <p>(a) Main Table and side Table top and to be made in 25mm block board with 1mm thick Laminate. The front side of the table to have a " C " made with 2 x 18mm thick MDF Exterior Grade Board cladded with 1mm Laminate on the front and the verticals towards the modesty panel. The modesty panel to have 18mm MDF Exterior Grade Board cladded with 1mm Laminate as specified.</p> <p>(b) The " L " shaped table top on the back side to have 50mm edge alround and to be cladded with 12mm MDF Exterior Grade Board finished with minimum two coats of LOW VOC or NOW VOC duco paint.</p> <p>(c) All other members to be with 18mm MDF Exterior Grade Board and all exposed faces of the table to have 1mm Laminate OR 1mm Glossy Laminate OR 12mm thick MDF Exterior Grade Board finished with minimum two coats of LOW VOC or NOW VOC duco paint as specified above to be used.</p> <p>(d) All the edges of 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping.</p>				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(e) One readymade CPU mobile pedestal.				
	(f) One Molded Key Board Tray with channels etc.,				
	(g) One Three Drawer Unit made with 18mm MDF Exterior Grade Board and 12mm MDF Exterior Grade Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,				
	(h) One Side Table with shutter unit of 600mm with 2 drawers and two openable shutters made with 18mm MDF Exterior Grade Board and 19mm plywood with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,				
	(i) All the unexposed faces to have 0.8mm Laminate OR minimum two coats of NO VOC or LOW VOC enamel paint with putty finish.				
	(j) Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
9	<b>OFFICER's EXECUTIVE TABLES AND SIDE TABLES:</b>	2		Each.	
	<p>Providing, making and placing in position Executive Table and Side Table of approximate size 1650mm - 1550mm x 750mm x 750mm + 1050mm x 450mm x 750mm with following specifications.</p> <p>(a) Main Table and side Table top and to be made in 25mm block board with 1mm thick Laminate. The front side of the table to have a inverted " U " made with 2 x 18mm thick MDF Exterior Grade Board clad with 1mm Laminate on the front and the verticals towards the modesty panel. The modesty panel to have 18mm MDF Exterior Grade Board clad with 1mm Glossy Laminate and 1mm Laminate as specified.</p> <p>(b) The " L " shaped table top on the back side along with side table to have 49mm edge around, which is to be achieved by adding a 75mm piece of 18mm MDF Exterior Grade Board to the table top from bottom and this vertical edge is to be clad with 1mm Laminate OR 12mm MDF Exterior Grade Board finished with minimum two coats of LOW VOC or NOW VOC duco paint.</p> <p>(c) All other members to be with 18mm MDF Exterior Grade Board and all exposed faces of the table to have 1mm Glossy Laminate as specified above to be used.</p> <p>(d) All the edges of 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping.</p> <p>(e) One readymade CPU mobile pedestal.</p> <p>(f) One Molded Key Board Tray with channels etc.,</p> <p>(g) One Three Drawer Unit made with 18mm MDF Exterior Grade Board and 12mm MDF Exterior Grade Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,</p> <p>(h) One Side Table with shutter unit of 400mm, with one drawers and one openable shutters made with 18mm MDF Exterior Grade Board with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,</p> <p>(i) All the unexposed faces to have 0.8mm Laminate OR minimum two coats of NO VOC or LOW VOC enamel paint with putty finish.</p>				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(j) Ready Made Modular Foot Rest - 400mm x 350mm x 65mm. The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
<b>10</b>	<b>GRAHAK MITRA AND TECH MITRA TABLE:</b>	1		Each.	
	Providing, making and placing in position Grahak Mitra and Tech Mitra Table of approximate size 2600mm x 800mm - 900mm x 750mm with following specifications.				
	(a) Main Table Top to have 25mm block board with 1mm thick Laminate. The vertical supports of the table is to be made with two side boxing of 75mm x 800mm x 750mm made with 18mm MDF Exterior Grade Board and the front side boxing to 200mm x 450mm x 750mm on either sides and central boxing of 250mm x 600mm x 750mm, all made with 18mm MDF Exterior Grade Board clad with 1mm Laminate OR 12mm thick MDF Exterior Grade Board				
	(b) The front of the table to have a 600mm x 1050mm proud portion with provision for cove lighting at bottom and this central portion to be clad with 6mm thick blue colored lacquered glass.				
	(c) All other members to be with 18mm MDF Exterior Grade Board and all exposed faces of the table to have 1mm Laminate or horizontal and 1mm glossy Laminate for verticals and the drawer unit to have 1mm Glossy Laminate as specified to be used.				
	(d) All the edges of 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping.				
	(e) 2 Nos. readymade CPU mobile pedestals.				
	(f) 2 Nos. Molded Key Board Trays with channels etc.,				
	(g) 2 Nos. Three Drawer Unit made with 18mm MDF Exterior Grade Board and 12mm MDF Exterior Grade Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 18mm x 12mm MDF Exterior				
	(i) All the unexposed faces to have 0.8mm Laminate OR minimum two coats of NO VOC or LOW VOC enamel paint with putty finish.				
	(j) 2 Nos. Ready Made Modular Foot Rests - 400mm x 350mm x 65mm. The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
	COUNTERS:				
<b>11</b>	<b>SINGLE WINDOW COUNTERS:</b>	4		Each.	

S.No.	Item. / Particulars.	Quantity.	Rate.	Unit.	Amount.
	<p>Providing, making and placing in position Single Window Counters along with necessary partitions as per item 1.2 above (The partiltions will be measured and paid as per item 1.2 i.e., Half Height Partitions) with following specifications and per dimensions specified. The front side of the Single Window Counter to have 8mm x 100mm Fiber Cement Board / Calcium Silicate Board / Reinforced Magnesium Silicate Board as Skirting cladded with 1mm glossy Laminate (silver color) at bottom.</p>				
	<p>(a) The overall size of each Single Window Counter to be 1650mm - 1500mm x 900mm - 975mm x 750mm + 1050mm x 450mm x 750mm.</p>				
	<p>(b) Tabletop of main table and side table to be made in 25mm block board with 1mm thick Laminate for horizontal</p>				
	<p>(c) All other members to be with 18mm MDF Exterior Grade Board / 2 Nos. of 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and all exposed faces of the table to have 1mm thick Laminate for horizontal surfaces and 1mm thick glossy Laminate for vertical surfaces and 12mm thick MDF Exterior Grade Board as specified in the drawing to be used.</p>				
	<p>(d) All the edges of 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping.</p>				
	<p>(e) One readymade CPU mobile pedestal.</p>				
	<p>(f) One Molded Key Board Tray with channels etc.,</p>				
	<p>(g) One Three Drawer Unit made with 18mm MDF Exterior Grade Board and 12mm MDF Exterior Grade Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 18mm x 12mm MDF Exterior Grade edge lipping etc.,</p>				
	<p>(h) One Side Table with shutters made with 25mm block board top and 18mm MDF Exterior Grade Board for all other members with necessary hardware viz., ' W ' hinges, SS handles, locks, SS tower bolts, etc., and 18mm x 12mm beech wood edge lipping etc.,</p>				
	<p>(i) All the unexposed faces to have 0.8mm Laminate OR minimum two coats of NO VOC or LOW VOC enamel paint with putty finish.</p>				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(j) Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	(k) All wooden members to have minimum two coats of NO VOC or LOW VOC duco paint finish.				
	The cost to include the " L " shaped Single Window Counter and to include all materials, hardware, labour for a neat and finish job as per drawings and directions etc., complete.				
<b>11.2</b>	<b>12MM TOUGHENED GLASS DIVIDERS FOR SINGLE WINDOW COUNTERS:</b>	4		Each.	
	Providing, making and fixing in position 12mm thick toughened clear float glass in the front side of half height partitions of Single Window Counters of approximate size 1250mm x 400mm - 100mm in tapered shape. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.				
<b>11.3</b>	<b>12MM TOUGHENED GLASS ON TRANSACTION SIDE FOR SINGLE WINDOW COUNTERS:</b>	4		Each.	
	Providing, making and fixing in position 12mm thick clear float glass in the front side of approximate size 1650mm x 450mm with a central cut out of 200mm x 175mm. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.				
<b>12</b>	<b>FLOOR MOUNTED WRITING DESK:</b>	1		Each.	
	Providing, making and placing in position Wall Mounted Circular Writing Desk 900mm dia x 750mm with following specifications.				
	(a) A Octogonal support boxing is to be made 450mm at floor level tapering upwards to 600mm at 900mm from floor made in 12mm MDF Exterior Grade Board cladded with 1mm Glossy Laminate. A top to be provided at 900mm level from floor to be made with 25mm Block Board cladded with 1mm Glossy Laminate which will have verticals made with 12mm MDF Exterior Grade Board cladded with 1mm Glossy Laminate upto the table top level of 1050mm from floor level.				
	(b) The Writing Desk Circular Top to have 12mm dia toughened clear float glass with 25mm champered bull nosing alround.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	<p>(c) All members to be with 12mm / 18mm MDF Exterior Grade Board and all exposed faces to have 1mm Glossy Laminate as specified.</p> <p>(d) All the edges of 12mm / 18mm MDF Exterior Grade Board to have 18mm x 12mm MDF Exterior Grade edge lipping.</p>				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(e) All the unexposed faces to have 0.8mm Laminate OR minimum two coats of NO VOC or LOW VOC enamel paint with putty finish. The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
<b>13</b>	<b>PLASTIC EMULSION PAINTING:</b>	150		Sq.M.	
	Cleaning the surface of the wall & then applying one coat of altex putty followed by one coat of primer & then applying second coat of putty to give smooth finish exactly in line and level & then finally applying a minimum of two coats of NO VOC or LOW VOC Plastic Emulsion Paint of approved shade to give a neat finish including cost of all materials necessary scaffolding etc., complete for walls & ceiling.				
<b>14</b>	<b>ROLLER BLINDS:</b>	8		Sq.M.	
	Providing and fixing in position of Roller Blinds of approved Fabric (Fabric Cost - RS. 1,000/- per Meter) of Hunter Douglas / Mac / Vista make or approved equivalent of approved shade etc., as directed.				
<b>15</b>	<b>DESIGNER FILM WORK:</b>	5		Sq.M.	
	Providing and fixing in position Designer Film with elipse design on all glasses as per draswings and heights mentioned. The Designer Film is of Harmony / 3M or equivalent approved make. The rate is for a finished item of work etc., complete as directed.				
<b>16</b>	<b>ACP CLADDING:</b>	10		Sq.M.	
	Supplying and fixing aluminium composite cladding with skin material 0.5 mm thick aluminium sheet cover material natural polyethylene aluminium cladding panel fixed with extruded aluminium basis frame (50x25x1.5mm) angle cleats, weather sealants, rivets, GI brackets all as approved, using suitable bolts on structural steel work including necessary accessories complete in all respects including all labour charges etc., complete for finished item of work but excluding cost of structural steel fabrication, scaffolding charges, if any, ACP Cladding - 4 mm thick.				
<b>17</b>	<b>BUYBACK OF EXISTING COUNTERS, PANELLING, LOOSE FURNITURE (**BUYBACK ITEMS DOES NOT INCLUDE RACC FURNITURE &amp; PARTATIONS**)</b>	-1		L.S	

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	Dismantling and removing the existing Counters, Wall Panelling, Loose Furniture, False Ceiling etc., removing existing plumbing lines if required with proper closing of valves etc., complete and carting away nonservicable material to dump yard or approved land fill as directed complete as per directions of SBI. the following are the list of Buyback items: 1. Counters-8 No's 2.Partitions- 10 Sq.mts. 3. Tables-6 No's				
	<b>TOTAL</b>			<b>RS.</b>	

(Rupees

only)

Signature of the Contractor with seal