

CORRIGENDUM NOTICE-I

SUB: TENDER FOR INTERIOR FURNISHING WORK OF SBI HARSIL

Refer to our tender No. DEL/DDN/R-IV/06-2023/01 Dated 28.06.2023 on the captioned subject, following changes in tender document has been made and should be read as below :

Relevant section of Tender Document	Existing provision	New / Modified to be read as
Page No. 3, Notice Inviting Tender 3. Earnest Money Deposit	Rs 16,400/- (Rupees Sixteen Thousand Four Hundred only)	Rs 15,840/- (Rupees Fifteen Thousand Eight Hundred Forty only)
Page No. 3, Notice Inviting Tender 13. Estimated work value	16,41,566+GST	15,84,416+GST
Page No. 14	2.0 The tenderer shall furnish EMD of Rs. 16,400/- (Rupees Sixteen Thousand Four Hundred only)to be deposited in online mode as directed of e-Tender Service Provider.	2.0 The tenderer shall furnish EMD of Rs. 15,84,416/- (Rupees Fifteen Thousand Eighty-four Thousand Four Hundred Sixteen only)to be deposited in online mode as directed of e-Tender Service Provider.

BOQ (Price Bid)

BOQ of Interior works for SBI Upcoming Branch at Harsil, Uttarkhand					
S.No	Description	Unit	Qty	Rate	Amount
1	Metallic False Ceiling : Providing and fixing perforated Tegular edge Metallic False Ceiling of Armstrong make metallic false ceiling of size 24" X24" (Model Desigflex Tegular or equivalent) with required suspension system (Suprafine XL or equivalent) as per manufacturer's specification. The ceiling to be finished as per manufacturer's specification along with provision of all necessary cut outs for electrical / air conditioning grills and necessary frame work including cove and curve designs etc. complete to the satisfaction of Architect/ Bank's Engineer.	Sq.ft	1140.00		
2	Deodar Wooden ceiling : Providing and fixing of frame work made of special sections power pressed from M.S. sheet and galvanized in accordance with zinc coating 600 as per IS: 277 and consisting of angle cleats of size 25 mm wide X 15 mm thick with flanges of 22 mm and 37 mm at 1200 mm centre to centre one flange fixed to the ceiling with dash fastner 12.5 mm dia X 40 mm long with 6 mm dia. Bolts to the angle hangers of 25 X 25 X 5 mm of required length, and other end of angle hanger being fixed with nuts and bolts to 6.1 channels 45 mm X 15 mm X 0.9 mm running at the rate of 1200 mm centre to centre to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having clips of 10.5 mm at 450 mm centre to centre shall be fixed in a direction perpendicular to 6.1 channel with connecting clips made out of 2.64 mm dia. X 230 mm long 6.1 mm wire at every junction including fixing the gypsum board with ceiling section and perimeter channels. Supplying and installing wooden false ceiling as per specifications and drawings. The work includes the provision of all necessary materials, labor, equipment, and accessories required for a complete installation. Specifications: Material: 8 mm thick Deodar wood planks 150 mm wide and varying lengths as per design requirements Natural wood finish with clear varnish. Surface Treatment: Flame-retardant coating Installation Method: Suspended installation using metal framework and hangers	Sq.ft	100.00		

Estimate of Interior works for SBI Upcoming Branch at Harsil, Uttarkhand					
S.No	Description	Unit	Qty	Rate	Amount
A False ceiling					
1	PVC Laminate Gypsum tile ceiling				
	Supply and installation of 12.5 mm thick square edge PVC Laminated Gypsum Tile of size 595x595 mm, made of Gypsum plasterboard, manufactured from natural gypsum as per IS 2095 part 1 and laminated with white 0.16mm thick fire retardant PVC film on the face side and 12micron metalized polyester on the back side with all edges sealed with the face side PVC film which goes around and wraps the edges and is bonded to the edges and the back side metalized polyester film so as to make the tile a completely sealed unit, Silhouette steel angle grid system of armstrong, main tee are doud web design roll formed from hot dipped galvanized steel with prepainted steel capping, Main Tees are 3600 X 38 mm long with Base Metal thickness of 0.38 mm, has cross Tee slots at 100 mm centres and suspension holes in the bulb conveniently located at every 52mm, suspended with CL 315 Clip with heavy duty plugs to be suspended with the ceiling. Cross Tee are 1200 X 28mm and 600 X 28 mm and 600 X 28 mm long. Lay visual appeal. Perimetre wall angle is 3000 X 24 X 24 mm with Base metal thickness of 0.45mm.	Sq.ft	750.00		
2	Deodar Wooden ceiling	Sq.ft	250.00		
	Providing and fixing of frame work made of special sections power pressed from M.S. sheet and galvanized in accordance with zinc coating 600 as per IS: 277 and consisting of angle cleats of size 25 mm wide X 15 mm thick with flanges of 22 mm and 37 mm at 1200 mm centre to centre one flange fixed to the ceiling with dash fastner 12.5 mm dia X 40 mm long with 6 mm dia. Bolts to the angle hangers of 25 X 25 X 5 mm of required length, and other end of angle hanger being fixed with nuts and bolts to 6.1 channels 45 mm X 15 mm X 0.9 mm running at the rate of 1200 mm centre to centre to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having clips of 10.5 mm at 450 mm centre to centre shall be fixed in a direction perpendicular to 6.1 channel with connecting clips made out of 2.64 mm dia. X 230 mm long 6.1 mm wire at every junction including fixing the Deodar board with ceiling section and perimeter channels				

All other terms and condition of the tender remains unchanged.

The Regional Manager
 State Bank of India,
 Regional Business Office, Region-IV,
 1, New Cantt Road, Dehradun-248001