

RENOVATION OF SBI AO VARANASI**BOQ FOR INTERIOR FURNISHING WORKS****NOTE:**

1. The work has to be done on all the three floors i.e Ground, First and second floor of AO Varanasi Building Rates quoted shall be valid for complete work. As building will be operational in working hours, Vendor has to work in phased manner (in nights and holidays also). Vendor has to take care of safety of workers and building users. Work has to be done and as per direction of Bank/ Architect. Vendors are suggested visit the site prior to quoting rates.

2. Bank may ask for material test certificates, GST paid bills of the items. All works (underground or concealed) shall be recorded, measured and photographed in presence of AO Engineer prior to concealment.

3. All ply shall be BWP grade conforming to IS 710. Inner-side of ply (in partition, wall panels etc and in furniture unlaminated part of ply) shall be spray painted with fire retardent paint of approved brand. Contractor has to keep the branding side of ply/ blockboard on visible side. Laminante shall be pasted after checking of base work by Bank's Engineer / Architect

4. Sample of materials must be submitted to Bank / Architect for approval before put to use . Deviation of item without prior approval will not be accepted.

5. Note : All material shall be as per approved material list. Items other than specified shall be per relevant IS code and approval shall be taken from Bank's Engineer/ Architect.

6. RATES ARE TO BE QUOTED BOTH IN FIGURES AND IN WORDS

SR. NO	DESCRIPTION	QUANTITY	UNIT	RATE (INR)	AMOUNT
1	FULL HT SOLID PARTITION - WITH BOTH SIDE LAMINATE				
a	Providing and fixing full height partition of which framing shall consist of Aluminum Section 50 mmx 50 mm (Wall Thickness shall be 1.5 mm) @ 600mm C/C Both ways Horizontally and Vertically. The framing shall be finished with 8 mm thk. BWP ply on both side 1.00 mm thk. approved shade Laminate shall be fixed from both sides of ply. Provide 100mm high skirting in 1.00 mm thk. approved laminate to fixed as per drawing and direction. (Vertical aluminium pipe will be upto ceiling level but Ply and laminate shall be provided upto false ceiling level). Rate shall be inclusive of necessary hardware items, etc. Complete. (measurement will be Length x height upto false ceiling bottom)	180.00	Sqm		
b	Item same as above but glazed partition. Glass shall be 6mm thick toughen glass and with 3M film in approved pattern.	335.00	sqm		
c	Item same as above but reusing existing Aluminium tubes of old partitions. Rate includes dismantling of old Aluminium partitions and seperating the tubes which will be reused in new partitions with necessary modifications in length.	45.00	sqm		
d	Item same as 1 (a) but with 8 mm bison board (or approved cement board) on both side in place of 8 mm WP ply.	20.00	sqm		
2	SEMI HT. PARTITION IN LAMINATE				

SR. NO	DESCRIPTION	QUANTITY	UNIT	RATE (INR)	AMOUNT
	Specification same as item No-1 but of lower height having 8 mm thk. ply fixed on both sides which shall be finished with 1.0 mm. thk laminate as per the drg. A 3" x 1" steam beach wooden molding with chamfered edge is to be provided on all external edges & finished in melamine / zinc polish as per details. Rate is inclusive of providing and fixing inserted Soft board / White boards maintaining the vertical surface lines. (measurement Length x height)	585.00	Sqm		
3	PANELLING ON WALLS IN LAMINATE FINISH				
	Providing and fixing paneling on wall. Framing shall consist of Aluminum Section 50 mm x 25 mm (Wall Thickness 1.5 mm) @ 600m C/C. Both ways horizontally and vertically on the wall. This framing would be covered by 8 mm thk. Ply finished with approved 1.0 mm. Thk. Laminate. Steam beach wooden molding 50 mm x25 mm with chamfered edge is to be provided on top edge & finished in melamine / zinc as per details / as directed by architect shall be provided . Measurement (Length x height)	300.00	sqm		
a	PANELLING ON WALL IN GYPSUM	125.00	sqm		
	Providing and fixing panelling on wall with gypsum board. Framing shall consist of Gypsum ULTRA GI sections on the wall. This framing would be covered by 6mm thk. Ply and 12mm thk gypsum board. Measurement (Length x height) finished with required taping and nutty works				
4	Wall Paper	10.00	sqm		
	P/F fabric backed <u>customised</u> vinyl wall paper, resistant to high wear and tear, fire retardant, anti fungal, and scratch resistant of <u>Marshalls</u> or equivalent approved brand and of approved pattern and shade. Measurement (Length x height).				
5	ENTRANCE DOORS - WITH TOUGHENED GLASS (PATCH FITTINGS) (DORMA FITTINGS)				
a.	FULLY GLAZED DOOR (12MM THK TOUGHENED	80.00	sqm		
b.	Fixed glazing 12 mm thick toughen glass.	20.00	sqm		

SR. NO	DESCRIPTION	QUANTITY	UNIT	RATE (INR)	AMOUNT
	Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with necessary patch fittings(Dorma make or equivalent) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG 9300 EQ - S 25mm dia X 300mm length).Measurement (Length x height)				
6	P/F DOORS IN LAMINATE FINISH WITH / WITHOUT FRAMES				
	Providing and fixing solid doors of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make and finished with 1mm thick approved laminate on both sides. The edges finished with steam beach lipping. A door frame of 3.5" x 2" teak wood section shall be provided finished in melamine. Rate shall include mortice lock , floor springs / door closure (as the case may be), door stopper, a pair of handles 12" SS Brushed finished, 5" hinges 4 Nos., buffers, tower bolts, etc. with necessary hardware items and with or without door frames as mentioned below.				
a.	Door shutter with frame specification same as above.	35.25	sqm		
b.	Door shutter without frame specification same as above.	32.00	sqm		
c	Frame and shutters made of old Aluminium (ready available on site) sections. Item includes opening sections, repairing/ resizing as required, providing 12 mm both side prelaminated HDHMR (Green/action tesa) / 5mm clear glass, 3 M glass film. changing required hardwares (lock, handles, hinges, door closer, stopper etc) and finishing complete work with Dupont paint of approved shades	13.25	sqm		
7	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid decorative type flush door shutter & frames finished with 1.0 mm laminate on both side.				

SR. NO	DESCRIPTION	QUANTITY	UNIT	RATE (INR)	AMOUNT
a	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid door/window/Ceoseatory windows & other Frames/Chowkhat comprising of virgin PVC polymer of K value 58- 60 (Suspension Grade), calciumB43:B49 and non toxic additives (maximum toxicity index of 12 for 100 gms) fabricated with miter joints after applying PVC solvent cement and screwed with full body threaded star headed SS screws having minimum frame density of 750 kg/ cum, screw withdrawal strength of 2200 N (Face) & 1100 N (Edge), minimum compressive strength of 58 N/mm2, modulus of elasticity 900 N/mm2 and resistance to spread of flame of Class A category with property of being termite/borer proof, water/moisture proof and fire retardant and fixed in position with M.S hold fast/lugs/SS dash fasteners of required dia and length complete as per direction of Engineer-In- Charge	151.00	Rmt		
	(Including cost of M.S hold fast/lugs or SS dash fasteners etc). Note: For WPC solid door/window frames, minus 5 mm tolerance in dimensions i.e depth and width of profile shall be acceptable. Variation in profile dimensions on plus side shall be acceptable but no extra payment on this account shall be made Frame size 50 x 100 mm.				
b	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid decorative type flush door shutter of required size comprising of virgin polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) having minimum density of 650 kg/ cum and screw withdrawal strength of 1800 N (Face) & 900 N (Edge), minimum compressive strength 50 N/mm2, modulus of elasticity 850 N/mm2 and resistance to spread of flame of Class A category with property of being termite/borer proof, water/moisture proof and fire retardant. WPC to be laminated with 1 mm laminate on both faces of shutter and fixing with stainless steel butt hinges of required size with necessary full body threaded star headed counter sunk S.S screws, all as per direction of Engineer-In- Charge. (Note: including cost of stainless steel butt hinges and necessary S.S screws) 35 mm thick.	88.25	sqm		
8	FALSE CEILING - GYP BOARD				

SR. NO	DESCRIPTION	QUANTITY	UNIT	RATE (INR)	AMOUNT
	Providing and fixing false ceiling at all height including providing and fixing of frame work made of (GYPsteel ULtra) special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate	1,250.00	sqm		
	G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter.				
	channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound ,				
	jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with : 12.45.1 12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) :2011 (Board with BIS certification marks)				

SR. NO	DESCRIPTION	QUANTITY	UNIT	RATE (INR)	AMOUNT
	Item includes finishing of Gypsum ceiling, preparing surface and painting with two -three coats of white / specified colour of superior quality plastic emulsion paint. Vertical patta upto 150mm will not be measured above this only difference of extra height will be paid. em includes wooden laminated pelmet as where required. Measurement will be horizontal area only (LxW) for complete work.				
b	Item same as above but with Calcium silicate board 12 mm thick of Hilux make in place of Gypsum board. As per company specifications and specified specifications.	100.00	sqm		
9	FALSE CEILING IN PLY				
	Item same as above but 1mm thick laminate over 12 mm WP Ply in place of Gyp board/ calcium Silicate board. Complete work up to satisfaction of Bank/ Architect. Item includes wooden laminated pelmet as where required. Measurement will be horizontal area only (LxW) for complete work.	50.00	sqm		
10	MODULAR FALSE CEILING				
	<u>P/F Armstrong (Fine Fissured 20 mm thick RH 99 Tegular 15 BE With Micro Look Silhoutte Grid sections) false ceiling of size 24"x24".</u>	1,065.00	sqm		
	Providing and fixing mineral fibre false ceiling tiles at all heights of size 595X595mm of approved texture, design and pattern. The tiles should have Humidity Resistance (RH) of 99%, Light Reflectance 85%, Thermal Conductivity k = 0.052 - 0.057 w/m K, Fire Performance as per (BS 476 pt - 6 &7)in true horizontal level suspended on interlocking T-Grid of hot dipped all round galvanized iron section of 0.33 mm thick (galvanized @120 gsm) comprising of main T runners of 15x32 mm of length 3000 mm, cross T of size 15x32mm of length 1200 mm and secondary intermediate cross T of size 15x32 mm of length 600 mm to form grid module of size 600x600 mm suspended from ceiling using galvanized mild steel item (galvanised@80gsm) 50 mm long 8mm outer diameter M-6 dash fasteners, 6 mm diameter fully threaded hanger rod up to 1000 mm length and L-shape level adjuster of size 85x25x2 mm, spaced at 1200 mm centre to centre along main 'T'.				

SR. NO	DESCRIPTION	QUANTITY	UNIT	RATE (INR)	AMOUNT
	The system should rest on periphery walls /partitions with the help of GI perimeter wall angle of size 24x24X3000 mm made of 0.40 mm thick sheet, to be fixed to the wall with help of plastic rawl plug at 450 mm centre to centre & 40 mm long dry wall S.S. screws. The exposed bottom portion of all T-sections used in false ceiling support system shall be pre-painted with polyester baked paint, for all heights. The work shall be carried out as per specifications, drawings and as per directions of the engineer-in-charge. With 16 mm thick beveled tegular mineral fibre false ceiling tile (NRC 0.55 to 0.6)				
	Flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees. Perimeter trim to be Armstrong wall angles of size 3000x19x19mm, secured to walls at 450 mm maximum. Installation to be carried out by Armstrong Trained Installation team & Installation should be carried out as per Armstrong recommended procedure. ARMSTRONG SUSPENSION SYSTEM - Armstrong make Anchor Fastener, Hanger Wire 2.5mm dia, Hook Clip with J Wire assembly. APPROVED MAKE – Armstrong/ Knauf/ Hunter Douglas/ Tranquill.				
	Measurement will be horizontal area only (LxW).				
11	Furniture Work				
	Providing and laying tables / counters/ desk/ of overall size of top as mentioned in item. It shall consist of 25 mm thk BWP Ply (single ply /board) top as per design sides and modesty panel of on 19 mm thk. BWP (as per Architects design). This shall be finished with 1.0 mm laminate of approved color and make. All inner sides shall be finished with 0.75 mm thick. All edges shall be finished with 2 mm thick edge binding tape . Item includes all accessories and hardware of approved quality. (telescopic channels, pop-ups, SS handles, locks etc.				
	Each top should be provided with 75 mm dia SS wire manager of approved quality near the CPU / Monitor position as shown in drawing. 1 no. ready made, sheet metal CPU trolley with lockable wheel (as approved) finished in black colour powder coating. ready made, white powder coated, metal key board tray -1no. as approved with telescopic / double (ebco make sliders).				

SR. NO	DESCRIPTION	QUANTITY	UNIT	RATE (INR)	AMOUNT
	A drawer unit as shown in the drg shall be provided. 3 nos of drawers and 1 no. of tray with 1.0 mm. Thk. Laminate shall be provided. Height of drawers shall be 3", 4" and 11". Drawer shall consist of ½" thk. BWP Ply sides, back and 6mm thk. BWP Ply base. Facia of drawers shall be of 19 mm thk. BWP Ply finished in 1.0 mm. Thk. Laminate (suede finish) and with a wooden moulding on top/bottom edge for handle. 25 mm gap to be maintained between each drawer. Each drawer shall slide on a pair of telescopic drawer sliders(ebco/beck) and individually lockable. 12 mm beveled edge glass top has to be provided on table top. Glass shall have wire manager according to CPU position All inner side surfaces including shutters shall be finished with 0.75 mm thick balancing laminate of matching colour.Rate shall be inclusive of all necessary approved fittings like locks(Godrej make), SS handle for drawers and any miscellaneous hardware items. Complete work including seperate inclined footrest.				
a	TABLE SIZE (2100 x 900 mm) with Side credenza size 1100 mm x 750 mm high x 450mm deep.Side unit will have three shutters, and one shelf in each section.	5.00	No		
b	TABLE SIZE 1500 x 675 mmx 750 and Side credenza upto size 900 mm x 700 mmx 450 mm deep.Side unit will have three shutters, and one shelf in each section.	27.00	No		
c	Staff Counter L Shape 1500 x 600 mm and width 600 mm with one drawer tower.	147.00	No		
12	Repair / renovation / resizing of existing tables by changing defective ply, accessories (locks, hinges, sliding rails and handles) , changing laminates (as per above specifications, design and new colorscheme) . Item includes complete work including paint and polish.				
a	TABLE SIZE (2100 x 900 mm)	4.00	No		
b	TABLE SIZE 1500 x 675 mm	20.00	No		
13	Repair / renovation / resizing of existing side credenza by changing defective ply, accessories (locks, hinges, sliding rails and handles) , changing laminates (as per above specifications, design and new colorscheme) . Item includes complete work including paint and polish.				
a	Side credenza upto size 900 mm x 700 mmx 450 mm deep	20.00	No		
b	Side credenza more than 900 mm x 700 mmx 450	4.00	No		

SR. NO	DESCRIPTION	QUANTITY	UNIT	RATE (INR)	AMOUNT
14	<p>Conference Table (U shape size 625 mm x 9000 mm x 750 mm) Providing and palcing in position conference table size of top as mentioned. It shall consist of 19 mm thk. BWP Ply top as per design (double edge all-around with 38 mm thk half round moulding of steam beach wood on the edges) supported on 19 mm thk. BWP Ply verticals. Suitable (as per Architects design) wooden moulding with melamine shall be provided to the edge of the top. A 12 mm thk. flexi Ply apron shall be provided as per Architects design with necessary pattern. The Table top should be finished with 1.00 mm laminate of approved colour and all other external to be finished in 1.0 mm. Thk. Laminate (suede finish). Top should be provided with 6 no pop- up boxes (six module) of Legrand make as shown in drawing. All inner surfaces shall be finished with 0.75 mm thick balancing laminate of matching colour.</p>	1.00	No		
15	<p>Repair / renovation / resizing of existing conference table of approximately above size by changing defective ply, accessories, providing 3 No popup boxes (legrand make) , changing laminates (as per above specifications, design and new colorscheme) . Item includes complete work including paint and polish.</p>	1.00	No		
16	<p>Reception table size 675-750 x 2400 mm x 750 H. (As per design) including drawer units, loose footrest-2 No, 2 nos 12mm glass (300 x 900mm) supported on upto 150 mm SS studs, facia made of 12 mm Corianwith approved design and cove for flexible light. Necessary metal key board tary -2 nos , wire managers etc. will be provided at required position</p>	1.00	No		
17	<p>FULL/ Low HT. / Overhead Storages (450 mm DEPTH AND UP TO 2100 MM HEIGHT) IN LAMINATE FINISH.</p>	170.00	Sqm		
	<p>Providing and laying Full / low ht. Storage units of sizes as mentioned above. They shall consist of a top of 25 mm thk. BWP. Ply, 19 mm thk. BWP. Ply sides and base, 6 mm thk. Comm. ply back, 19mm thk. BWP. Ply shutter/ glass shutter with self closing hinges of ebco make (full oval open) . All external surfaces to be finished in 1.0 mm laminate (suede finish) and hidden (internal surface) 0.8 mm laminate of approved make.</p>				

SR. NO	DESCRIPTION	QUANTITY	UNIT	RATE (INR)	AMOUNT
	Division of shutters shall be made equally according to the length of the storage. A 19 mm thk. Fixed Ply shelf on battens shall be provided at 400 mm / specified intervals from the base.				
	2 mm thick PVC Lipping (edge binding) with matching to laminate colour shall be provided to the edge of the storage top . All inner surfaces including shutters, rear side, shall be finished with 0.75 mm thick balancing laminate of matching colour.				
	Rate shall be inclusive of all necessary approved fittings like hinges(ebco make), locks, 4" long brushed finish handles, tower bolts, 100 mm high SS legs (as required) and any miscellaneous hardware items.				
18	Display Unit Item same as above but without shutters but with 12 mm glass shelves.	15.00	Sqm		
19	SHUTTERS PANTRY COUNTERS /WALL CABINET / ELECTRICAL CABINET	169.72	sqm		
	SHUTTERS WITH FRAME FOR (ELECTRICAL NITCH, UNDER WINDOW CABINET) Providing and fixing 18mm thk. HDHMR shutters and frame . Division of shutters shall be made equally according to the length. Shutters shall be hinged to the framework and finished with 1.0mm thk. Laminate of approved colour and shade on outer side and inside finished with balancing laminate of app colour and shade. Rate shall be inclusive of all necessary approved fittings like hinges, sliding track (complete fittings), magnet catch,150 mm long SS Brush Finish handle, tower bolts, locks, Aluminium powder coated air vent grills on top and bottom and necessary hardware fittings complete, etc. mm(Measurement wil be of frame + shutter area)				
20	PLASTIC EMULSION PAINT	2,200.00	sqm		
	Providing & applying plastic emulsion paint on walls, columns & ceilings. The rate shall include scrapping, leveling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make , quality & finish shall be provided. NOTE : Rate shall also include - Filling up the cracks in walls & ceiling, making good surface.				
21	TEXTURE FINISH	300.00	sqm		
	Providing & applying a coat of textured finish on walls and columns. The rate shall include scrapping, leveling & preparing the surface. Primer coat + (minimum) 3 coats of approved make, quality & shade shall be provided.				

SR. NO	DESCRIPTION	QUANTITY	UNIT	RATE (INR)	AMOUNT
22a	POP PUNNING Providing and applying POP Punning on walls and columns (average 12 mm thk). The rate shall include scrapping, leveling and preparing the surface. The rate shall be inclusive of all types of grooves above the skirting, around the window and door frames and one step moulding in beam bottom.	300.00	sqm		
b	Item same as above but average thickness 8mm~6mm or less,	1,900.00	sqm		
c	Providing and fixing POP Cornice in straight or circular shape opening. Size 75 x 75 mm	20.00	Rmt		
d	Providing ready mad cornice / moulding of Wainscot make				
	Duco Cornice (W-501) (width 65 mm)	16.00	Rmt		
	Deco Moulding (W-202) (Width-30 mm)	16.00	Rmt		
	Deco Moulding (W-101) (Width-22 mm)	16.00	Rmt		
	Deco Moulding (W-201) (Width-30 mm)	16.00	Rmt		
	Ceiling Moulding (W-401) (Width-45 mm)	16.00	Rmt		
23	PIN-UP BOARDS Providing and fixing pinup boards. It consist 1/2" soft boards of good density to be mounted over 1/2" ply. The soft board will be covered with a plain fabric (appox Rs.450 /Rmt.) from front and edges. Suitable moulding (as directed by architect) will be fixed on all four sides and will be finished in polish. Note : Only soft boards provided on other than the partitions / Furniture will be measured and soft board made in the partitions will be the part of the partition measurement (rate) and not consider separately.	24.00	Sqm		
24	White Board / writing board (3'-0" x 4'-0") Providing and fixing white board. It consist 3/4"ply laminated with high gloss white mica 1.00 mm thick suitable for marker writing. All edges shall be lipped (edge binding) with 1.00 mm thick PVC lipping of specified colour. It shall be fixed or hanged on wall with concealed pelmet clip.	24.00	Sqm		
25	Quarter Glass: Providing and fixing 10 mm glass of size 1'-6" x 2'-0", edges shall be dimond polished and will be fixed with SS D brackets of approved make.	46.00	No		
26	ROLLER BLINDS				
	Vista make Roller blinds (blackout series) with chain mechanism Color as approved.	332.00	Sqm		

SR. NO	DESCRIPTION	QUANTITY	UNIT	RATE (INR)	AMOUNT
27	Providing and fixing 4 mm Lacqured glass (of approved make & colour) in place of laminate over existing ply of partition / wall panel. Complete work including fixing materials and approved adhesive.	5.00	sqm		
28	Providing and fixing 6 mm (bendable) acrylic surface (Corian) in place of laminate as per design and drawing. Complete work including fixing materials and approved adhesive.	5.00	sqm		
29	Providing and fixing 4mm MDF (of approved make) over existing ply/board. Complete work including fixing materials and approved adhesive.	5.00	sqm		
30	Providing and fixing Demore Solidwood Flute panels (total thickness 14 mm) (285 mm x 2780 mm) finished in approved colour. Complete work including fixing materials and approved adhesive.	5.00	sqm		
31	Providing and fixing decorative Jaali made of 12 mm MDF of approved make. Finished in duco paint.	5.00	sqm		
	Total				
	GST will be extra (as applicable)				