

STATE BANK OF INDIA

ADMINISTRATIVE OFFICE, BHAGALPUR

PRICE BID

INTERIOR FURNISHING AND ALLIED CIVIL WORKS AT SUPAUL CITY BRANCH

BRANCH : SUPAUL CITY

UNDER RBO : SAHARSA

S. No	Particulars of Items	Unit	Quantity	Rate (Rs.)	Amount
1.	<p><u>LOW HEIGHT SINGLE WINDOW COUNTER</u> Providing and fixing low height Single Window counters / Case Manager's table with a maximum width of 900 mm in required shape as per typical design. The main structure of the counter is to be made of 19mm thick BWP Phenol Formaldehyde block board of Green/Century / Mayur or equivalent with a teak wood beading of 50 mm x 38 mm in front and necessary beading to cover all the exposed edges of board etc. The width of the counter should have 1500mm (with disc credenza / cabinet of 400mm wide and maximum 1050mm length / depth (including width of counter). The vertical supporting members of counter are to be made of 19 mm thick BPW Phenol Formaldehyde block board of Green/Century / equivalent D-Tel box shall be fitted properly in right hand side. The key board pullout tray to be provided in addition to drawer with lock and key make arrangement of standard make. The left hand side should have cabinet made of 19 mm thick BWP, PF plywood and cavity keeping CPU as per design / drawing. The counter top have a neat hole to be made in the table for connecting the wires which is to be covered with a white colored PVC insert (wire manager) with moveable parts to put the wires and sockets to cover the hole neatly. The exposed block – board/ plywood to be covered with 1.0 mm thick blue / white high gloss/matt finish laminate of Greenlam / Marino / Century or equivalent of approved shade and colour. Exposed portions to be also covered with 1.0 mm thick blue/white high gloss/matt finish laminate of approved shade and colour. The internal and non-visible side of all drawers, cabinets and counter table shall be painted with 3 coats of enamel paint over one coat of primer on the internal side. Glass portion made of 12 mm thick toughen glass of approved make as per design and specification securely fixed in toughen section as per design and details and all necessary standard quality of fittings, hard wares, locks (make or equivalent). Door shutter of 19 mm BWP board to be fixed at the rear side of counter with automatic locking system from Godrej or equivalent. All work to be completed as per approved materials Colour & Laminate etc and specification and direction of Engineer-in-charge.</p>	Rmt	6.20		

2.	<p><u>REDESIGN/ REPAIRING OF GLAZED/ NON GLAZED PARTITION OF FULL HEIGHT PARTITIONS:</u> Repairing of full height partly paneled partly glazed / non-glazed partitions etc as per the direction of R.M / CM (CS & CM), including with 6 mm thick ply board both sides of Century/Green or equivalent make & 1mm thick glossy blue / white laminate of Century / Greenlam or equivalent make with change of Godrej multipurpose locks etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I. The measurement will be considered only for the exposed portion where lamination changes take place and due deduction would be made for glass etc. to arrive at the measurement quantity that will be payable.</p>	Sqm.	53.00		
3.	<p><u>FULL HEIGHT PARTITIONS NON GLAZED:</u> Providing and fixing in position Full Height Partition (up to instructed level) consisting of un-anodized aluminum hollow section of 50x50mm size 1.5mm thick of JINDAL/ INDAL confirming to ISI 303 standard as internal frame structure placed horizontally & vertically in 600 x 600mm interval , except skirting member which shall have 2x50x50mm members at reqd. spacing and 6mm wide grooves or as required as per architectural drawing.(c/c distance to be adjusted as per drawings, door/opening positions). The framing shall be fixed with 8mm thick BWR grade ply (of approved / equivalent make) firmly screwed to the aluminum frame on both side. The board surface so prepared shall be pasted with 1.0mm thick laminate of approved premium shade or texture finish in approved pattern, make & color. The wooden frame of the partition shall continue right up to the ceiling as shall be firmly fixed to the ceiling and ground by means of Rawal Plugs etc necessary fasteners so as to form a stable system / partition all complete work with provision for wring to be done by other agencies all complete work as per Corporate Centre, Mumbai approved materials Colour and Laminate etc and specifications and direction of Engineer-in-charge.</p>	Sq.m	0.00		
4.	<p><u>LOW HEIGHT PARTITION</u> Providing and fixing low / half height partitions up to 4' 0" with double skin paneling up to 3'-0" and 12 mm thick toughened glass of approved make above frameless on the top and sides and sturdily fixed at the bottom on a polished teakwood frame all complete job with all other specifications and details to be as per item No. 2 above and as per the design i.e. shown in sides of low-height counters all complete work. All complete work as per Corporate Centre, Mumbai approved materials Colour & Laminate etc and specifications and direction of Engineer-in-charge /Bank.</p>	Sqm.	40.00		
5.	<p><u>HYDRAULIC DOOR CLOSER</u> Providing and fixing hydraulic Hardwyn, Everite or approved make equivalent door closures of Hardwyn,</p>	Nos.	0.00		

	Everite or equivalent approved brand and sample – all complete as per instructions of the Bank. All work to be completed as per drawing, design. Specification and direction of Engineer-in-charge /Bank.				
6.	<p><u>12 MM THICK TOUGHENED GLASS PARTITION WITH PATCH FITTING</u></p> <p>Supplying and Fixing of fully glazed Partition at approved position. The Partition shall be made of 12 mm thick toughened float glass, machine polished and etching work (acid wash) done on it as per the drawing/ approval. The partition glass shall be fixed with necessary sets of Patch Fittings of approved make and the patch fittings shall be of sleek design fittings on top & bottom etc as suitable & required as per site condition for making the partition fully stable and secure etc. complete as per the design and directions of employer. Preferably each piece of glass (up to 5ft of length) shall be fitted with 4 sets of patch fittings or so as directed by engineer in charge. The partition glass may be fixed on S. S. channel at lintel and floor levels and also with required/ suitable seal/ gaskets at corner/ junction point of two glasses, as per the site condition & instruction. The cost to include all type of fixtures, Labour etc. complete for the execution of item as per design/ approval of Engineer in charge.</p>	Sqm.	7.00		
7.	<p><u>12 MM THICK TOUGHENED GLASS DOOR ETC</u></p> <p>Supplying and Fixing of fully glazed Door (in single / double leaf shutter) at approved position. The door shall be made of 12 mm thick toughened float glass & the glass shall be fitted with Patch Fittings of approved make. The door shall be fixed on approved make floor spring and with 2 Nos. of 18 inch S.S. handles, one dead lock with three keys, its fittings and fixtures, computerized vinyl push/pull sticker etc. complete all of approved make. The 12 mm thick glass shall have etching work (acid wash) done on it as per the drawing/ approval. Door handle shall be of Kich Industries make, stainless steel, AISI 316 grade pull handles, 22 mm dia x 450 mm STAIN CODE PHI 2212 S and shall be fixed in position. The cost to include all fixtures, 6 lever Godrej lock, push/pull stickers, Labour etc. complete. All work to be completed as per drawing, design. Specification and direction of Engineer-in-charge /Bank.</p>	Sqm.	2.00		
8.	<p><u>WORK STATIONS / TABLES</u></p> <p>(a). Making and erecting Desk-top with provision of wire manager having two sides vertical support panels and modesty panel. All made of 19 mm thick BWP grade block board of Green / Century /Mayur or equivalent top laminated with 1.0 mm laminate of Green/ Marino / Century or equivalent. All edges shall be covered with teak wood lapping and front edge shall be covered with half round molding. Inner portion of table shall be painted with matt finish 3 coat of synthetic enamel paint with primer. All wooden surfaces shall be well polished with melamine/sprit polish.</p>				

	<p>(b) Making & providing drawer chest with two drawers and one cupboard with concealed hinges and Godrej multipurpose locks. Box made of 19 mm thick and bottom with 6 mm BWP grade ply of Green/ Century or equivalent front shall be clad with 1.0 mm thick laminate of Green lam / Century or equivalent side edges of drawers and cupboard shall molded in round shape with Gamhar wood. All drawers shall have 'Z' shape powder coated MS runners with PVC sound less rollers. All work to be completed as per Corporate Centre, Mumbai approved materials Colour Laminate and specifications and direction of Engineer-incharge/Bank.</p> <p>(c). Providing and fixing key board tray (as per design and specification at 1- above) try and made of PVC / Laminated board on 'Z' shape powder coated runner with PVC soundless rollers.</p> <p>(i) 1800 mm x 900 mm x 750 mm(For BM and LDM) with side unit 900x450x750</p> <p>(ii) 1500 mm x 750 mm x 750 mm(For officers) with side unit 900x450x750</p>	Nos.	2.00		
		Nos.	3.00		
9.	<p><u>VERTICAL BLINDS:</u> Providing & fixing Vista or equivalent make 100 mm wide vertical blinds made up of powder coated channel & other imported components and rayon polyester fabric of approved shade & colour. Blinds should be mounted on partition, wall using wall mounted or ceiling mounted channels as per requirement. All complete with all mechanisms etc. (Note: The area of the blinds shall be measured for payment). All complete work as per drawing, design Specification and direction of Engineer-in-charge /Bank.</p>	Sqm.	22.00		
10.	<p><u>REDESIGN/ REPAIRING OF COLUMN PANELLING:</u> Repairing of column paneling etc as per the direction of R.M / CM (CS & CM), including with 6 mm thick ply board both sides of Century/Green or equivalent make & 1mm thick glosive blue / white laminate of Century /Greenlam or equivalent make with change of Godrej multipurpose locks etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I.</p>	Sqm.	42.00		
11.	<p><u>Providing and fixing wall & Column Paneling as per drawing & design :</u> P/F panelling with 8mm thick BWP Grade ply with laminate as per item no.2 with GI frame work complete in all respect firmly affixed to the supporting wall make and brand of materials shall be as above item no.1 at a maximum spacing of 450mm x 450mm c/c (the spacing shall need to be closer if the grid so dictates), covered with 1mm thick laminate of approved make mentioned. To be provided at suitable location and column.</p>	Sqm.	125.00		

12.	<p><u>Providing and fixing writing Desks as specified below :</u></p> <p>Providing and fixing Column-mounted Circular Writing Desk as per design. The Desk is to be fixed to the column along the perimeter through peripheral 19 mm thick BWP block boards/Exterior Grade MDF board of Green/Century or equivalent with angled MS plate support as re-quired. The Desk shall have two parts viz. head and stand. The Head, circular in plan, is to have an average 450 mm projection around the column periphery for facilitating writing. The Stand, conical in shape on elevation, is to be fixed to the column with a projection of 200 mm at the junction with head, and 50 mm at the floor-column junction all around. The head is to be provided with two circular disks made out of 19 mm thick BWP block board. The disks are to be fixed to the column keeping one on top & the other at bottom, 200 mm apart to have pigeon hole-shaped cells. Dividers, made out of 12 mm thick BWP block board sections/ Exterior Grade MDF board of Green/Century or equivalent , shall be provided to pigeon hole cells, 200 mm wide at the openings for keeping vouchers, slips etc. Each of the disks shall have an octagonal shaped hole in the centre around the column. The stand is to be made with an inner wooden framework of 50 mm x 37.5 mm well seasoned Malaysian sal wood sections to have a conical shape as per design. The framework shall be covered with 12 mm thick flexi-ply all around.</p> <p>The work is to be finished with 1mm thick high gloss laminate on the surface. The desk is to be fixed properly on the column by angled M.S plates as required with GI screws. The plates shall be welded firmly with rawl plug in RCC along the vertical surfaces. The inner surfaces are to be finished with French polish.</p> <p>The work is to be completed with necessary lipping & polishing to exposed block board edges. A Glazing on the work top is to be done by fixing of 12 mm thick transparent toughened glass on it with SS stud fittings. All edges of the glass are to be finished with mirror polishing. The work top shall be at a height of 1.0 m from FFL. The work is to include all necessary materials, accessories, labour, tools & tackles. This item may be done only if the breadth to width ratio of the column is between 1.0 and 1.2.</p> <p>Payment shall be made for finished work.</p>	Nos.	1.00		
13.	<p><u>Providing, fitting and fixing Drop Boxes as per drawings :</u></p> <p>The box shall have an approximate size of 400 mm width, 200 mm depth and 450 mm height.</p> <p>One drop-slit, 200 mm long & 5 mm wide with edges smoothed properly, is to be provided on the top of the box. The box shall be provided with a small lockable door with 2 no. 75 mm SS butt hinges and a small SS hasp bolt. The item is to be made out of 12 mm thick BWR block board to a pigeon hole shape.</p>				

	<p>The work is to be finished with 1mm thick high gloss/matt finish laminate of approved shade. The inner surfaces are to be finished with French polish.</p> <p>The work is to be completed with necessary lipping & polishing to exposed surfaces.</p> <p>The box shall be fixed to a wall or column in the hall at a height of 1.2 m from FFL or as directed.</p> <p>The work is to include all necessary materials, accessories, labour, tools & tackles. Payment shall be made for finished work. Boxes of the following categories are to be provided.</p>				
(a)	Suggestion Box	No.	1.00		
(b)	Cheque Drop box	No.	1.00		
(c)	Voucher Rack	No.	1.00		
14.	S/F/F Godrej mortise locks/ Night latches including cost of labor & materials etc. to complete job.	Nos.	4.00		
15.	Supplying & fixing/fitting of corian laminate of 6mm thickness of approved make, approved only on table top, table front, & designer beads SBI facia, back black color & rounding of edges to complete in all respect, as per site condition and instruction of SBIIMS with rounding of edges etc to complete job. (SW Counters and BM Table).	Sq.m	14.00		
16.	<u>GRAHAK MITRA :</u> Providing Grahak Mitra Counter of size 900mm x 1050mm with side credenza of 675mm x 1800mm in approved shape as per design of Bank made up of 19 mm thick BWP grade block board of Green / Century brand and make as above mentioned at item – 1 above, top laminated with 1.0 mm high glossive/matt finish laminate with all complete work as per drawing, design., specification and direction of Engineer-in-charge.	Nos.	1.00		
17.	Providing D-Tel depository cabinet of Godrej make in counters of size-691mm x 460mm x 460mm of weight 33.00 kg of automatic locking including of cost of labors & materials etc. to complete job as per specification & direction of E/I.	Nos.	3.00		
18.	<u>FOOT REST:</u> Providing and placing foot rest made of 19 mm BWP grade block board with wooden lippings top clad with rubber mat. All inner portions shall have a coat of mat finish enamel paint all complete work as per drawing, design. Specification and direction of Engineer-in-charge/Bank.	Nos.	10.00		
19.	<u>LOW TYPE STORAGE CABINET:</u> Manufacturing, supplying and fixing of box type cupboards / storage units of required, sizes and as shown in the drawing and of 1' 6" depth and made out of 19 mm thick Plywood (of approved / equivalent make) all-round and 8 mm Plywood (of approved / equivalent make) at the back. The 19mm Plywood shelves /compartments shall be provided at 15" c/c horizontally and 3' 0" c/c vertically. The unit shall have	Sqm.	8.00		

	<p>hinged type shutters on the front made out of 19 mm Plywood with approved quality concealed hinges, locks tower bolts, knobs all as per approved quality. All external surfaces to be laminated with 1.5 mm thick laminate of approved regular shade/ 1.0mm thick laminate of approved premium shade or texture finish and all internal surfaces to be laminated with 0.8mm thick laminate of approved shade & make. Front edges of shelves and all exposed edges of plywood to be leaped with teak wood finished with polish. Footing to be made of 2.5" x 1.5" teak wood frame covering all four sides of bottom surface and covered with 6 mm Plywood of approved make and 1.5 mm thick laminate of same shade. cost to include providing and applying melamine finish on wood surface/grooves including providing and applying 2-3 coats of VIPER over a coat of anti-termite paint where ever required. All work to be completed as per drawing, design. Specification and direction of Engineer-in-Charge/Bank.</p>				
<p>20.</p>	<p><u>FALSE CEILING.</u> Providing and fixing of Armstrong's Mineral Fiber Acoustical False ceiling tiles of type Prima Fine Fissured RH-99% of approx. size 600mm x 600mm x 12mm with square / tegular edge at all heights laid on Armstrong's Prelude XL Hot dipped galvanized exposed grid with 15 m with T-Section exposed flingers which shall be powder coated white. The framework will comprise of main Runner made from 0.33 mm thick GS sheet and of size 24 mm x 38mm x 3600 mm and spaced at 1200 mm centre securely fixed to the structural soffit by approved hangers at 1200 mm maximum centre. Hangers (GI wire of 4.0 mm diameter) to be fixed by approved Rawl plug, level adjusters and screws etc. All complete work as per drawing, design. Specification and direction of Engineer-incharge /Bank. The last hanger at the end of each main Runner should not be greater than 450 mm from the adjacent wall. Flush fitting of 1200 mm long cross tee (with double stitching) to be interlocked between main Runners at 600 mm centre to form 1200 mm x 600 mm modules. Cut cross Tees longer than 600 mm to be supported independently. 600 mm x 600 mm modules top be formed by fitting 600 mm x 600 mm modules to be formed by fitting 600 mm long cross Tee centrally between the 12 mm cross Tee. Perimeter wall Angle shall be of 0.45 thick GS Steel and of size 22 mm and 3000 mm long of white color. The work shall be as per standards and specifications laid down by the manufacturers. Full provision of weight of a/c ducting (if provided) and light fittings, wiring for any use, including co-coordinating with all trades and making any cutouts required for the same, all complete with a minimum of 2 coats of premium quality Acrylic emulsion paint and full finishing for light fittings all complete work as per drawing, design, specification and direction of Engineer-incharge/Bank.</p>	<p>Sqm.</p>	<p>40.00</p>		

21.	GYPSUM FALSE CEILING	Sqm.	83.00		
<p>Providing and fixing in position Seamless Gypsum Board False Ceiling in one or more levels as directed including vertical surfaces between different levels. The Ceiling including vertical surfaces is to be done with 12.5 mm thick plain Gypsum boards of approved make, duly finished with recommended filters, tapes, etc. to have a seamless flush look. The ceiling system is to be fixed to a concealed GI framework (Gypsteel Ultra make or approved equivalent) by 25 mm long GI drywall screws at 250 mm intervals along both ways. The framework shall be suspended securely from MS angle hangers fixed to true ceiling surface by dash fasteners. The whole system is to be fitted with all necessary arrangements like perimeter channels, intermediate channels, ceiling sections, ceiling suspension angles, rawl plug, soffit cleat etc. The work includes applying two coats of approved putty & primer suitable for Gypsum boards after necessary surface preparation and final painting with approved acrylic emulsion paint on the surface. Provisions for openable type lids for facilitating arrangements for rolling shutters are to be made as required. Lids shall be made out of 9 mm thick BWR plywood duly painted to match the ceiling surface and provided with 2 No. 75 mm SS butt hinges & 1 No. 100 mm SS tower bolt along the surface. The work is to be completed with all materials, accessories. Labour, tools & tackles and in strict conformity with manufacturers specifications & recommendations. Rate is to include the cost of making openings for ceiling mounted electrical & air-conditioning accessories. All work to be completed as per drawing, design. Specification and direction of Engineer-in-Charge /Bank.</p>					
22.	SPARKLE FROSTED FILM	Sqm.	38.00		
<p>Providing and fixing self adhesive Sparkle series Frosted Film and/or one way vision film of 3 M make as per design approved. The film has to be pasted on glasses surfaces as directed, cut & fixed as per design including the Bank's logo. Supporting Invoice /bills are to be produced for payment of this item including certificate from the dealer certifying use of the product. All work to be completed as per drawing, design. Specification and direction of Engineer-in-charge /Bank.</p>					
23.	Providing and fixing/fitting 12mm thick toughened glass partition of approved make with all necessary hardware accessories etc. Including cost of labours and materials etc. as per specifications and direction of E/I.	Sqm.	4.50		
24.	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level: Cement mortar 1:4 (1 cement :4 coarse sand)	Sqm.	15.00		
25.	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :	Cum.	0.50		

	Cement mortar 1:4 (1 cement : 4 coarse sand)				
26.	Rcc of (1:1.5:3) cement :sand :stone chips of size 20mm work in at required place or as per EIC. With approved cement, sand, stone chips , including the cost of labour shuttering ,de-shuttering, propping etc and all complete job.	Cum.	0.10		
27.	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level: Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg.	14.00		
28.	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement: 4 fine sand)	Sqm.	32.00		
29.	Providing and applying wall putty of 2 mm average thickness over plastered & white washed walls & ceiling to prepare the surface even and smooth compete as per direction of BANK/etc.	Sqm.	34.00		
30.	<u>SYNTHETIC ENAMEL PAINTING:</u> Providing two or more coat painting with finest 1 st quality synthetic enamel paint of Asian Paints/ICI Dulux/ Berger Nerolac/ Equivalent approved brand of specified colour to give an even shade after proper scraping, sand papering, etc. as per direction of bank.	Sqm.	300.00		
31.	Demolishing existing partition and wood work etc. manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material at suitable place as per direction of Bank.	Lump sum	1		
Total					
#GST will be paid extra as per applicable					