PRICE BID FOR PROPOSED ELECTRICAL AND AIR-CONDITIONING WORKS FOR MALKHARODA BRANCH RBO-2, BILASPUR MODULE L-1 TENDER COST S.No. Description of Item Qty Unit Rate Amount Α Part A : Electrical Works ELECTRICAL WIRING WORK Note: Use of Flexible conduits & Elbows in Circuit wiring is not allowed except in exceptional site conditions with the approval of Bank's Engineer / Architect and All wiring laying in the MS/PVC conduit strickle follow IE(Indian Electricity) rules, IS code, follow in all items of project/ work execution. Proper ferrules, lux, thimble , gland termination to be done in all cabling & wiring from both load/source end. Conduit carrying submain will not carry circuit/point wiring. Similarly conduit carrying circuit wiring will not carry submain/point wiring. Conduit carrying point wiring will not carry submain/circuit wiring. All Electrical works (Cabling/wiring/panel etc) to be carried out as per layout/General Arrangement (GA)Drawing attached only. 1 ELECTRICAL WIRING Providing, fixing, testing and commissioning of POINT WIRING of any length for light point/Wall fan point/Exhaust fan point/ Call bell point/ including call bell/ including fan box(if required), 'S' type fan hook etc with 3 X 1.5 Sq.mm(P/N/E) PVC 650V/1100V Grade FR insulated copper conductor single core multi strended wire in 16 SWG(Medium Gauge) stove enamelled rigid steel conduit 20mm/25mm with conduit accessories like bend, junction box etc in concealed/surface manner as per site requirment with suitable Modular Switches/Sockets with plate and Metal/PVC box,Scaddle, angle bracket (if required), 3 plate ceiling rose/bulb holder etc. The floor/roof/wall junction box shuold be of MS(heavy duty) box of suitable size and covered with Steel finish Steel cover sheet by screw tight and gasket to avoid water/dust insertion. The item includes Circuit wiring from DB to the switch board with 3x2.5 Sq.MM. The above wiring carried out surface or recess in wall/floor/roof should be cutting by cutter/chiesling, replastering, curing, painting with uniform and smooth finish by specilised workman ship and making the surface neat afterwards complete in all respect as per direction of Bank Engg. (EACH Circuit to take NOT MORE than 7oints). The conduit/ Flevible conduit/iuncti Phase- Red, Neutral- Black, Earth-Green Make of Material for items of BOQ:-(i) Modular Type Switch/socket/step electronic fan regulator, plate, box, TV/telephone, bulb holder/3 pin ceiling rose with all accessories:- Lergand/ Anchor(Roma)/MK/ Crabtree (ii) MS conduit/PVC conduit with all accessories:- BEC/AKG/NIC/Precision (iii) PVC insulated copper wire(FR) 650V/1100 V grade:- Finolex/RR cable/ Providing and fixing of point wiring with above specifications. One light point 35 Nos. а controlled by one switch. Providing and fixing of point wiring with same above specifications. Two light 12 b Nos points to be controlled by one switch Providing and fixing of ceiling fan point controlled as under (i) one 6 amp switch С 12 Nos. (ii) one no stepped electronic regulator of two module type providing and fixing 6 Amps Plug Points with same specs as above and install d 6 Nos along with same light switchboard Master switch of 16 Amps(Only Grey/Golden/Wooden colour other than white colour) to install alongwith same light switch board to control all light as a master 6 Nos e. switch ON/OFF in each switch board 2 6 AMP. POINTS ON SEPARATE BOARD : Supply,fixing,testing and commissioning of 1 No 6 A Multi Socket with 1No. 6 A switch (Modular type) with cover plate , sheet steel box / PVC modular box etc on surface / concealed manner I/c electrical connections and making good all the 6 Nos damages, painting, cleaning the site etc complete including all accessories as per site requirement and as directed. (Minimum two and Maximum three points are loop with one circuit as mentioned Power Wring (6 / 16 AMP. POWER POINTS) 3 Supply, fixing, testing and commissioning of 1 No 16 A switch & 1 No.six pin 6/16 Amp. Multi Socket (Modular Type) with cover plate , sheet steel box etc on surface / concealed manner I/c electrical connections and making good all the 8 Nos damages, painting, cleaning the site etc complete including all accessories as per site requirement and as directed. (Maximum two points are loop with one circuit as mentioned below) SPECIAL POINTS : (For Computers)

	Supply, fixing, testing and commissioning of following Modular type switch socket with cover plate, PVC modular box on Surface / sheet steel box in concealed manner I/c electrical connections and making good all the damages, painting, cleaning the site etc complete including all accessories as per site requirement and as directed.	6	Nos	
	2 Nos. 6 A Switch + 3 Nos. 6 A, 3 pin Socket			
	(Minimum two and Maximum three points are loop with one circuit as mentioned beolw)			
5	AC/Geyser Point (Single Phase)			
	Supply, Installation, Testing and commissioning of the surface / recess mounting A.C. / GEYSER power point with the followings :			
	Metra Plug and Socket DBs with one Nos 20 Amp SP MCB, 20 Amp plug and socket with complete Enclosur plate and box 1 set i/c electrical connections and making good all the damages, painting, cleaning the site etc complete including all accessories as required as per site requirement and as directed by Bank Engineer.	4	Nos	
	OR Modular 32A DP 1 way switch with plate & box 1 set. + 25A & 10A twin socket			
	(Only one point is connected with one circuit as mentioned below)			
6	AC Point (Three Phase)			
	Supply, Installation, Testing and commissioning of the surface / recess mounting A.C. Cassette power point with the followings :			
a.	Metal enclose Four way with one Nos 32 Amp FP MCB with complete Enclosur plate and box 1 set i/c electrical connections and making good all the damages, painting, cleaning the site etc complete as required as per site requirement and as directed. (Only one point is connected with one circuit as mentioned below)	3	Nos	

7	CIRCUIT WIRING :				
	Supplying, providing circuit wiring for Power/UPS with following PVC insulated				
	copper conductor single core multi strended wire (HRFR) in mentioned conduit				
	i/c electrical connections in suitable size MS / PVC modular boxes and it laying,				
	fixing, testing and commissioning in suitable size 20/25 mm dia,16 SWG (Medium				
	Gauge) thickness rigid MS conduit with conduit accessories like bend/junction				
1	box/ fan box etcwith cover plate, sheet steel box/ PVC modular box etc on				
	surface/ concealed manner i/c electrical connections and making goods all the			ĺ	
	damages,replastering, painting, cleaning the site etc complete as required as per				
	site condition. The floor/roof/wall junction box should be of MS(heavy duty) box of				
	suitable size and covered with Steel finish Steel cover sheet by screw tight and				
	gasket to avoid water/dust insertion. The length of circuit upto 30 meter length or				
	less as per site condition/requirment. Make of Material				
	(i) MO to it/D)/O to ititit II PEO/A/C/NIIO/Di-i				
	(i) MS conduit/PVC conduit with all accessories:- BEC/AKG/NIC/Precision				
	(ii) PVC insulated copper wire(FR) 650V/1100 V grade:- Finolex/RR cable/ Havells				
a	3 X 2.5 sqmm(For UPS Circuit/6 amp Separate Board) in suitable size of 16	10	Nos		
°	SWG (MMS) steel conduit as per IS code.	10	1105		
	3 X 4.0 sqmm (For AC/Power Circuit) in suitable size of 16 SWG (MMS) steel				
b	conduit as per IS code.	3	Nos		
—	- p			 	
—	Ev 4.0 comm /for three phase AC Indeed Circuit\ in suitable size of 40 01410 (4440)			 	
l c	5 x 4.0 sqmm (for three phase AC Indoor Circuit) in suitable size of 16 SWG(MMS	3	Nos		
) steel conduit as per IS code.	-			ļ
8	UPS OUTGOING & OTHER WIRING, As Per Requirment.				
(-)	3 x 10 Sqmm copper multistreand wire in 25 mm 16 SGW (MMS) steel conduit.	40	D 144		
(a)	(UPS INPUT DB TO UPS)	10	R.Mtr		
	,			1	†
—	2 V 1 5 Camm conner multiotreand wire in quitable size of 40 CM/C (MMAC) at all			 	
(b)	3 X 1.5 Sqmm copper multistreand wire in suitable size of 16 SWG (MMS) steel	15	R.Mtr		
L."	conduit.				
(0)	3 X 2.5 Sqmm copper multistreand wire in suitable size of 16 SWG (MMS) steel	40	D M+r		
(c)	conduit.	40	R.Mtr		
	3 X 4 Sqmm copper multistreand wire in suitable size of 16 SWG (MMS) steel				
(d)	conduit.	30	R.Mtr		
	conduit.				
(e)	5 X 4 Sqmm. Copper multistrend wire in suitable size of 16 SWG (MMS) steel	45	R.Mtr		
	conduit (For Cassettee AC)	.0			
(5)	3 X 6 Sqmm copper multistreand wire in suitable size of 16 SWG (MMS) steel	25	D M4:		
(f)	3 X 6 Sqmm copper multistreand wire in suitable size of 16 SWG (MMS) steel conduit.	25	R.Mtr		
(f)		25	R.Mtr		
	conduit.	25	R.Mtr		
(f) 9	conduit. DISTRIBUTION BOARDS	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar,	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested.	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority,	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered)	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority,	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered)	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised,	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work,enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with	25	R.Mtr		
	conduit. DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work, enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated, with		R.Mtr		
	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work, enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated, with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50		R.Mtr		
	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work,enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated, with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply i/c providing and fixing the following switchgear mounted thereon		R.Mtr		
	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work, enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated, with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply i/c providing and fixing the following switchgear mounted thereon complete with gaskets and interconnections, connection as per specification		R.Mtr		
	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work,enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated, with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply i/c providing and fixing the following switchgear mounted thereon		R.Mtr		
	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work, enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated, with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply i/c providing and fixing the following switchgear mounted thereon complete with gaskets and interconnections, connection as per specification complete as required.		R.Mtr		
	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work, enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated, with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply i/c providing and fixing the following switchgear mounted thereon complete with gaskets and interconnections, connection as per specification complete as required. (The board shall be dust & vermin proof with suitable degree of IP protection)		R.Mtr		
	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work, enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated, with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply i/c providing and fixing the following switchgear mounted thereon complete with gaskets and interconnections, connection as per specification complete as required. (The board shall be dust & vermin proof with suitable degree of IP protection) NOTE: All switchgears Ics shall be equal to 100% Icu.		R.Mtr		
	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work, enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated, with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply i/c providing and fixing the following switchgear mounted thereon complete with gaskets and interconnections, connection as per specification complete as required. (The board shall be dust & vermin proof with suitable degree of IP protection) NOTE: All switchgears Ics shall be equal to 100% Icu. Sheet 14 swg: panel sides, upper, lower, and Ft.doors		R.Mtr		
	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work, enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated, with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply i/c providing and fixing the following switchgear mounted thereon complete with gaskets and interconnections, connection as per specification complete as required. (The board shall be dust & vermin proof with suitable degree of IP protection) NOTE: All switchgears Ics shall be equal to 100% Icu. Sheet 14 swg: panel sides, upper, lower, and Ft. doors Sheet 16 swg: back side and compartments.		R.Mtr		
	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work,enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated,with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply i/c providing and fixing the following switchgear mounted thereon complete with gaskets and interconnections, connection as per specification complete as required. (The board shall be dust & vermin proof with suitable degree of IP protection) NOTE: All switchgears Ics shall be equal to 100% Icu. Sheet 14 swg: panel sides,upper,lower,and Ft.doors Sheet 16 swg: back side and compartments. Glande plates: 3 mm thick.				
	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work, enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated, with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply i/c providing and fixing the following switchgear mounted thereon complete with gaskets and interconnections, connection as per specification complete with gaskets and interconnections, connection as per specification complete as required. (The board shall be dust & vermin proof with suitable degree of IP protection) NOTE: All switchgears Ics shall be equal to 100% Icu. Sheet 14 swg: panel sides, upper, lower, and Ft. doors Sheet 16 swg: back side and compartments. Glande plates: 3 mm thick. Cable entry: Provision at bottom and upper sides.		R.Mtr		
9	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work,enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated,with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply i/c providing and fixing the following switchgear mounted thereon complete with gaskets and interconnections, connection as per specification complete as required. (The board shall be dust & vermin proof with suitable degree of IP protection) NOTE: All switchgears Ics shall be equal to 100% Icu. Sheet 14 swg: panel sides,upper,lower,and Ft.doors Sheet 16 swg: back side and compartments. Glande plates: 3 mm thick.				
9	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work,enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated, with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply i/c providing and fixing the following switchgear mounted thereon complete with gaskets and interconnections, connection as per specification complete as required. (The board shall be dust & vermin proof with suitable degree of IP protection) NOTE: All switchgears Ics shall be equal to 100% Icu. Sheet 14 swg: panel sides,upper,lower,and Ft.doors Sheet 16 swg: back side and compartments. Glande plates: 3 mm thick. Cable entry: Provision at bottom and upper sides. The above panel belongs following as under:				
9	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note: Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work, enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated, with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply i/c providing and fixing the following switchgear mounted thereon complete with gaskets and interconnections, connection as per specification complete as required. (The board shall be dust & vermin proof with suitable degree of IP protection) NOTE: All switchgears Ics shall be equal to 100% Icu. Sheet 14 swg: panel sides,upper,lower,and Ft.doors Sheet 16 swg: back side and compartments. Glande plates: 3 mm thick. Cable entry: Provision at bottom and upper sides. The above panel belongs following as under: A. 4 Nos. 200 Amp. Electrolytic grade Aluminum Bus Bars insulated with colored				
9	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note: Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work, enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated, with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply i/c providing and fixing the following switchgear mounted thereon complete with gaskets and interconnections, connection as per specification complete as required. (The board shall be dust & vermin proof with suitable degree of IP protection) NOTE: All switchgears ics shall be equal to 100% icu. Sheet 14 swg: panel sides, upper, lower, and Ft. doors Sheet 16 swg: back side and compartments. Glande plates: 3 mm thick. Cable entry: Provision at bottom and upper sides. The above panel belongs following as under: A. 4 Nos. 200 Amp. Electrolytic grade Aluminum Bus Bars insulated with colored Heat Shrinkable PVC Sleeves & duly supported on SMC/DMC molded supports				
9	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work, enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated, with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply I/c providing and fixing the following switchgear mounted thereon complete with gaskets and interconnections, connection as per specification complete as required. (The board shall be dust & vermin proof with suitable degree of IP protection) NOTE: All switchgears Ics shall be equal to 100% Icu. Sheet 14 swg: panel sides, upper, lower, and Ft. doors Sheet 16 swg: back side and compartments. Glande plates: 3 mm thick. Cable entry: Provision at bottom and upper sides. The above panel belongs following as under: A. 4 Nos. 200 Amp. Electrolytic grade Aluminum Bus Bars insulated with colored Heat Shrinkable PVC Sleeves & duly supported on SMC/DMC molded supports with Antitracking barriers.				
9	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work, enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated, with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply I/c providing and fixing the following switchgear mounted thereon complete with gaskets and interconnections, connection as per specification complete as required. (The board shall be dust & vermin proof with suitable degree of IP protection) NOTE: All switchgears Ics shall be equal to 100% Icu. Sheet 14 swg: panel sides, upper, lower, and Ft. doors Sheet 16 swg: back side and compartments. Glande plates: 3 mm thick. Cable entry: Provision at bottom and upper sides. The above panel belongs following as under: A. 4 Nos. 200 Amp. Electrolytic grade Aluminum Bus Bars insulated with colored Heat Shrinkable PVC Sleeves & duly supported on SMC/DMC molded supports with Antitracking barriers. B.INCOMING SWITCHGEARS: (RYB LED Indicators for Both Main/DG)				
9	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work, enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated, with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply i/c providing and fixing the following switchgear mounted thereon complete with gaskets and interconnections, connection as per specification complete as required. (The board shall be dust & vermin proof with suitable degree of IP protection) NOTE: All switchgears Ics shall be equal to 100% Icu. Sheet 14 swg: panel sides, upper, lower, and Ft. doors Sheet 16 swg: back side and compartments. Glande plates: 3 mm thick. Cable entry: Provision at bottom and upper sides. The above panel belongs following as under: A. 4 Nos. 200 Amp. Electrolytic grade Aluminum Bus Bars insulated with colored Heat Shrinkable PVC Sleeves & duly supported on SMC/DMC molded supports with Antitracking barriers. B.INCOMING SWITCHGEARS: (RYB LED Indicators for Both Main/DG) (i) 1 No. FP.125 A, 25 KA MCCB with thermal magnetic trip unit with digital				
9	DISTRIBUTION BOARDS All MCB to be "C" series Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials Panel- As per IS Standards/CPRI Tested. DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) Supplying, installation, testing and commissioning of indoor type, sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work, enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated, with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply I/c providing and fixing the following switchgear mounted thereon complete with gaskets and interconnections, connection as per specification complete as required. (The board shall be dust & vermin proof with suitable degree of IP protection) NOTE: All switchgears Ics shall be equal to 100% Icu. Sheet 14 swg: panel sides, upper, lower, and Ft. doors Sheet 16 swg: back side and compartments. Glande plates: 3 mm thick. Cable entry: Provision at bottom and upper sides. The above panel belongs following as under: A. 4 Nos. 200 Amp. Electrolytic grade Aluminum Bus Bars insulated with colored Heat Shrinkable PVC Sleeves & duly supported on SMC/DMC molded supports with Antitracking barriers. B.INCOMING SWITCHGEARS: (RYB LED Indicators for Both Main/DG)				

	C. OUTGOING SWITCHGEARS:	1	I	ı	1 1
	(i) 1 Nos- 125Amp TP MCCB for main with 200amp bus bar with indicator.				
	(ii) 160 amp onload changeover with 1 Nos 125 amp 25 KA, TP MCCB for DG				
	supply with 200 amp bus bar with indicator				
	(iii) 200 amp bus bar for parallel connection with DG changeover output				
	(Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority,				
	otherwise it will not considered)				
	Supply & Installation of SDP(Surge Protector Devicve) for general protection of				
b	main Distribution Board Legrad Make Cat No. 412247 (3P+N), 40 KA, T2- Imax 40KA/pole with complete wiring.	1	Nos		
	Providing and fixing 6 way TPN double door DB for LIGHT /POWER POINTS with				
С	63 Amp TPN , controlling 18 Nos. 10/16/32 Amps SPMCBs. & Complete.	2	Nos		
d	Providing and fixing 4 way TPN double door DB for LIGHT /POWER POINTS with 63 Amp TPN, controlling 12 Nos. 16/32 Amps SPMCBs. & Complete.	2	Nos		
е	Providing and fixing (12) way SPDB double door type For UPS points with 1x32 Amps DP, controlling 10 Nos, 16 AMP SPMCB	1	Nos.		
f	Providing and fixing (8) way SPDB double door type For Light DB only for Emergency Lights like glow sign etc with 1x32 Amps DP, controlling 6 NO.10 A./16 AMP SPMCB	1	Nos.		
g	Providing and fixing (4) way TPN double door type For UPS INPUT with 1x63 Amps TPNand 63 amp DP MCB- 3 Nos & 3 Nos, 32 amp SP MCB complete (Elobby/UPS Output)	1	Nos.		
h	Providing and fixing of Kit Kat Rewirable Porcelian fuse carrier & base with wooden frame of 200 amp/415 Volt near meter box	1	Set		
10	CABLES				
	Supplying, unloading, storage, laying, testing and commissioning of PVC/XLPE insulated (Heavy Duty) Al/Cu conductor armoured cable suitable for working voltage upto and including 1100 V grade, laid and tied on existing overhead cable trays, or laid and tied over MS supports in masonry trenches with copper/al cable lugs, single compression brass cable glands, tapping, crimping etc. as required and all cables run with double run(2 No.) of GI wire of 8 SWG size. The size of cables are as under:-				
	Make of Material:- (i) PVC/XLPC Armoured cable:- Finolex, Havells, RR cable, CCI(Cable Corp. of India)				
	(ii) Cable Termination:- Dowells, Comet				
а	3.5 X 70 Sq.mm XLPE. Al. armoured Cable(AC VTPN & BUS BARS)/Main cable	50	Mtr		
b	3.5 X35 Sq.mm XLPE.Al.armoured Cable (POWER)	40	Mtr		
С	4X 25 Sq.mm XLPE.Al.armoured Cable (POWER/LIGHT/UPS)	40	Mtr		
d	4X 16 Sq.mm XLPE.Al.armoured Cable (LIGHT/UPS)	50	Mtr		
11	EARTHING				
⊢''-	COPPER PLATE EARTH STATION:				
	Preparation of the Plate Earth Station: (As per IS:3043)				
	(a) Excavation of hard rocky earth, soft murrum, hard murrum etc and back filling with black cotton soil for the earth station, the earth pit size is 1000 mm X 1000 mm X 2500 mm.				
	(b) Supply and fixing of Copper Plate of Size 600 mm X 600 mm X 3.0 mm thick.				
(i)	(c) Fixing of 50 mm X 6 mm, 3 Mtrs copper strips from Copper Plate to earth terminal including brazing/welding at plate etc.	2	Nos		
	(d) Supply and laying in position 19 mm, 2 Mtrs G.I "B" Class pipe for watering with reducer/funnel with mesh.				
	(e) Supply and Fixing of the following in the earth station.				
	(i) 75 Kg. Charcoal. (ii) 15 Kg. Original Salt.				
	(iii) Black Cotton soil of adequate amount.				
	(f) Construction of earth pit chamber including necessary brick work concrete, plastering, S/F of C.I Cover of size 12" X 12" complete as per site requirment.				
	g. S.				
	G.I.PLATE EARTH STATION :				
	Preparation of the Plate Earth Station: (as per IS:3043)				
	(a) Excavation of rocky earth, soft murrum, hard murrum etc and back filling with black cotton soil for the earth station, the earth pit size is 1000 mm x 1000 mm x 2500 mm deep.				
l	(b) S/F of G.I. plate of size 600 x 600 x 6.0 mm thick.			I	

I	(c) S/F fixing 50 mm x 6 mm, 3 mtrs G.I, strips from G.I.plate to earth terminal			1	
(ii)	including brazing / welding at plate etc.	2	Nos		
''''	(d) Supplying and laying in position 19 mm, 2 mtrs G.I. `B' class pipe for	2	1403		
	watering.with reducer/funnel with mesh.				
	(e) S/F of the following in the earth station. 75 Kg. Charcoal, 15 Kg. Original Salt. and Black Cotton soil of adequate amount.				
	10 kg. Ollarodal, 10 kg. Oliginal dak. and Black Collon son of adequate amount.				
	(f) Construction of earth pit chamber including necessary brick work concrete,				
	plastering, S/F of C.I. Cover of size 12" x 12" complete as per site req.and marking its value and identification etc.				
	marking its value and identification etc.				
	Providing and fixing Copper/GI strip as per specification compete including				
(iii)	connection to earth electrode revetting/sweating/soldering, burying 15 cms below				
	in all types of soil/rocks etc complete as requiued.				
	(a) Copper Strip 25 X 5 mm	10	Mtr.		
	(b) G.I.Strip 25 X 5 mm	10	Mtr		
	(s) ometing 20 % o min				
	Supply and laying of 10 Sq.mm 650V/1100 V PVC grade insulated copper wire in				
(iv)	15 mm G.I. Pipe ISI grade including all accessories complete as required. (Dedicated Earthing for UPS output DB only)	30	Mtr.		
	Dedicated Earthing for OFS output DB only)				
12	OCCUPANCY SENSORS:-				
	Supply, installation , testing and commissioning of occupancy sensor				
	surface/recess mounted as per site condition complete with all wiring/conduit/Switch etc complete in all respect as per site condition as required	2	Nos		
	Honeywell Make K5015/16, Siemens/Johnson Control	_			
	OR Equivalent as per Bank's approved.				
	, 'pp				
13	TELEPHONE POINT				
	Supplying, Installation, testing and commissioning of the telephone point with the followings				
	Two pair, 0.61 mm dla. telephone cable tinned copper conductor, P.V.C. insulated				
	and sheathed , fire retarding, anti termite, colour coded twisted pairs and rip cord,				
	Double outlet The length of telephone cable upto 35 meter length or less as per				
	site condition with shutter modular type Telephone Outlets (RJ — 11) wth suitable size MS / PVC modular boxes and it laying, fixing, testing and				
	commissioning in suitable size 20/25 mm dia,16 SWG (Medium Gauge) thickness				
	rigid PVC conduit with conduit accessories like bend/junction box/cover plate/sheet steel/PVC box on surface/ concealed manner i/c electrical connections	_			
(i)	and making goods all the damages,replastering, painting, cleaning the site etc	2	Nos		
	complete as required as per site condition. The floor/roof/wall junction box shuold				
	be of MS(heavy duty) box of suitable size and covered with Steel finish Steel cover sheet by screw tight and gasket to avoid water/dust insertion.				
	cover sheet by screw light and gasket to avoid water/dust insertion.				
	Make of Material:- Delton/Finolex/RR cable				
	Supplying and fixing of krone telephone tag block on surface/ recess mounted with its accessories suitable for the multi core telephone cable and shall accommodate				
	tin-plated phosphor bronze connectors, the connectors shall splice unskinned				
(ii)	cables up to 0.61 mm dia and shall be terminate both incoming and out going	1	Nos		
	lines, the tag blocks shall be mounted inside, water proof box and locking arrangement and shall be fully accessible.				
	(A) 20 Pair tag block				
	(n) 20 1 all tay block				
	Supply, installation, testing and commissioning of the following size jelly filled				
(iii)	armoured tehephone cable.	20	Mtr		
	20 pair				
14	DATA CABLING FOR LAN				
	Providing, fixing, testing and commissioning of all nodes of four pair UTP CAT 6				
	LAN cables length upto 30 meter length or less as per site conditionin suitable				
	size 20/25 mm dia, 16 SWG wall thickness rigid PVC conduit with conduit accessories like bend/junction box/ fan box etc on surface/recessed manner and				
	making good all the damages, painting, cleaning the site etc complete as required				
	as per site condition and as directed as required. Junction box shuld be covered				
	with Stainless steel plate with screw with gasket for protection of water/dust. Providing, fixing, testing and commissioning of modular type Information Outlets				
а	with suitable size of MS/PVC modular boxes complete, all accessories with	8	Nos		
	insulation displacement connectors etc suitable for CAT 6 UTP cabling with RJ-45	-			
	socket with testing and commissioning of STP cabling with scanner for all the nodes/switches/jack panel complete (Each point/circuit/cable from both load and				
	source end to be marked with ferrules.)				
	Make of Material:-				
	(i) Data Cable, Cat 6 cable, Switch, Jack panel, Rack, Patch cords & Other accessories:- D-Link, Legrand				
	,g				

b	Providing and fixing Patch Panels 24 port (100 base TX) CAT 6 patch/jack panel with connector, out lets and necessary connectivity complete as required & (D-Link make)	1	Nos		
С	Providing, assembling, fixing, testing and commissioning Floor/Wall mounted RACKS for gig switches, patch panels etc including cooling DUAL fan trays, a 10 Point PDU, Fixed Trays as necessarycomplete. 9 U wall mounted RACK	1	Nos		
d	Providing and fixing of flowing factory fabricated Patch cords. (UTP/CAT 6 complte with connector on both side.)				
i)	for 1 Mt. long	8	Nos.		
ii)	for 2 Mt. long	8	Nos		
е	Providing, fixing,testing and commissioning of four pair CAT 6 LAN cable in suitable size of 20/25mm PVC medium gauge 16SWG conduit including all accessories to interconnect the switches from different location.	20	Mtr		
f	Poviding, fixing, testing and commissoining of Jack Panel of reputated brand.	1	Nos		
15	TV POINT:-Supply, installation, testing and commissionig of TV point(Modular) with RG-6 cable in the Medimum Gauge 1.6 mm PVC Conduit with all accessories complete in all respect	2	Nos		
16	Supply and installation of Vinyl sticker for on Electrical DBs like, " Switch Off at Night", Switch Off For Safety, etc	10	Nos		
17	Making & Providing of 3 sets of Asbuilt Drawing with coloured print for entier Electrical work (Power/UPS/Light/Data/Telephone/AC etc.) as advised by the Bank's Authority.	1	Lum sum		
<u> </u>	Description of Bold for Bottom				
	Description of light /fan fixture Supply and Installation, Testing and commissioning of the following fittings / equipments in surface/recess mounted as directed etc down rods of size upto 300 mm where ever required with ball sockets, anchor fastner etc complete as per site conditions. All fittings should be hang with suitable size of GI wire to four corner of fittings to the RCC rooftop with suitable size of anchor fastner/heavy gauge screw. The necessary arrangement is made by the contractor to install fittings in false ceiling especially 2'X2' and 4'X1' etc. as per instruction of Bank Engg.				
	LED LUMBARES OF STATE OF SMITH STATES				
18	LED LUMINARES:- 2' x2' (FULL GLOW TYPE) LED light fittings (600 X600mm) dimension suitable for grid/gypsum ceiling complete with its electrionic driver as required per instruction of Bank's Model No are as under:- PHILIPS:- RC380B G2 LED 35S-6500 PSU OD WH LED (FULLGLOW) WIPRO:- CRC010R0 38 HP57 HAVELLS:- LHECDIL7IL1W036 (Edge- Lit) CG:- LCTAR3-40-CDL	19	Nos		
19	LED DOWNLIGHTER: 15 Watt, recessed mounted circular down lighter, 6" dimension with complete its electronic driver are as under:- PHILIPS:- GREENLED-DN193B LED-12S-6500 PSU WIPRO:- IRIS LED LD 71-121-XXX-50-XX HAVELLS:- LHEBJNP ZPZ 1W 015(ENDURA LOW DEPTH) CG:- LC DD-15-CDL,	33	Nos		
20	LED Spot Light, 3 Watt, 2/3"(Inches) size as per site requirment. PHILIPS, WIPRO, HAVELLS, CG	4	Nos		
21	LED COVE/ STRIP LIGHT WITH ITS ELECTRONIC DRIVER(BLUE COLOUR):- Supply, installation, testing and commissioning of bright LED strip light with its electronic driver complete as required. PHILIPS, WIPRO, HAVELLS, CG	60	Mtr		
22	BOX TYPE LUMINAIRES: LED TUBE FITTINGS, 1200mm, 18/20 Watt PHILIPS/WIPRO/HAVELLS/CG	11	Nos		
23	FAN:-				<u> </u>
23 a	CEILING FAN: CEILING FAN: Single phase heavy duty grease filled double ball bearing, aerodynamically designed heavy gauge aluminium blades, copper wounded and impregnated silicon stamping motors etc 1200 mm sweep, brilliant white CG/USHA/ ORIENT/HAVELLS	12	Nos		
b	WALL FAN:-(Only Metallic Body)	3	Nos		
			1403	<u> </u>	

	Oscillating wall fan with regulator i/c coonections etc complete as required as per			
	approved make, Sweep 400/450 mm , RPM 1300 make are as under: CG/USHA/ ORIENT/HAVELLS			
24	EXHAUST FAN:- Single phase, 300mm sweep, 900 rpm, metallic exhaust fan of the following single phase Exhaust fan continuously rated, capacitor start and run type, totally enclosed and ruggedly built, pre lubricated double ball bearing, copper wounded, A & E class insulation, dynamically balanced, below 40 db sound level etc, front cover with grill/gravity louver for protection purpose with 12 mm plywood complete in all respect make as under: CG/USHA/ORIENT/HAVELLS/ALMONARD/ALSTOM	3	Nos	
	Sub Total : Part A (Electrical Works)			
	, , ,			
В	Part B : AIR CONDITIONING WORKS : AIR CONDITIONING WORK			
	Supply, installation, testing and commissioning of following AIR CONDIRIONERS as under. The Rate shall be inclusive of all taxes excluding GST. GST will be paid additionally by the Bank as applicable subject to GST Number. and system has complete one year warranty & If any additinal warranty provided by company/vendor in any specific part like compressor etc that is acceptable, please mentioned it. Rates include prime quality copper pipe if required extra on site as per site condition. Rates also includes Stablizer of approved make and KVA to be installed with AC.			
	Make of ACs:- Daikin/Hitachi/Voltas/Bluestar/Carrier only			
25	Supply, installation, testing and commissioning of Higher Efficient models of SPLIT AC, THREE STAR RATING OF BEE AIR CONDITIONERS 1.0 Ton Machines confirming to latest Indian Standards and suitable for operation on 230 Volts + 10 %, single Phase, 50 Hz AC supply with rotary compressor, Refrigerant and capable to perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with suitable thermostat. The rate should include installation charges after making appropriate changes in existing false ceiling. Heavy ready made/fabricated M S Stand to house the out door unit as per site conditions including carpentry work, minor civil work and material including copper piping of hard & prime quality of min. 22 G upto 5 metres with class "o" Nitrile insulation 12mm, cabling from indoor to outdoor unit, heavy gauge PVC drain piping with insulation as per site requirement. The copper piping, drains piping and electrical cabling should be fixed with clamps and no loose piping/cabling is allowed. The out door unit should be anti-rust powder coated. Indoor unit should have LED display. The rates inclusive of all repairs of civil and carpentry work The cost includes original fill and additional ton un of Make of ACs:- Daikin/Hitachi/Voltas/Bluestar/Carrier only	2	Nos	
26	Supply, installation, testing and commissioning of Higher Efficient models of SPLIT AC, THREE STAR RATING OF BEE AIR CONDITIONERS 1.5 Ton Machines confirming to latest Indian Standards and suitable for operation on 230 Volts + 10 %, single Phase, 50 Hz AC supply with rotary compressor, Refrigerant and capable to perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with suitable thermostat. The rate should include installation charges after making appropriate changes in existing false ceiling. Heavy ready made/fabricated M S Stand to house the out door unit as per site conditions including carpentry work, minor civil work and material including copper piping of hard & prime quality of min. 22 G upto 5 metres with class "o" Nitrile insulation 12mm, cabling from indoor to outdoor unit, heavy gauge PVC drain piping with insulation as per site requirement. The copper piping, drains piping and electrical cabling should be fixed with clamps and no loose piping/cabling is allowed. The out door unit should be anti-rust powder coated. Indoor unit should have LED display. The rates inclusive of all repairs of civil and carpentry work The cost includes original fill and additional ton un of Make of ACs:- Daikin/Hitachi/Voltas/Bluestar/Carrier only	1	Nos	
27	Supply, installation, testing and commissioning of Higher Efficient models of CASSETTE TYPE AIR CONDITIONERS(Three) BEE Certified rating 2.0 Ton Machines confirming to latest Indian Standards and suitable for operation on 415 Volts + 10 %, three Phase, 50 Hz AC supply with Scroll compressor, Refrigerant (R-32) and capable to perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti dust , anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with suitable thermostat. The rate should include installation charges after making appropriate changes in existing false ceiling. Heavy ready made/fabricated M S Stand to house the out door unit as per site conditions including carpentry work, minor civil work and material including copper piping of hard & prime quality of min. 22 G upto 5 metres with class "o" Nitrile insulation 12mm, cabling from indoor to outdoor unit, heavy gauge PVC drain piping with insulation as per site requirement. The copper piping, drains piping and electrical cabling should be fixed with clamps and no loose piping/cabling is allowed. The rates inclusive of all repairs of civil and carpentry work The out door unit should be anti-rust powder coated. The cost includes original fill and additional top up of refrigerant gas as per site condition. The rate inclusive of all chisel work, plastering, finishing, painting & all civil related Make of ACs:- Daikin/Hitachi/Voltas/Bluestar/Carrier only	2	Nos	

28	Supply and installation of hard & prime quality of min. 22 G Copper pipe for "Cassette AC Only" with class "o" Nitrile insulation of minimum 12 mm for 3 / 4 ton cassette type air conditioner including interconnection power/ communication cable between indoor and outdoor unit as per site requirement.(If required additionally, payment will made as per actual installtion.) The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. Make of Insulation:- Superlon/Aflex/Armacell/Kflex . Make of cable:Finolex/RR	30	Mtr	
29	Supply and installation of soft & prime quality of min. 22 G Copper pipe for "Split AC only" with class "o" Nitrile insulation of minimum 12mm for split air conditioner including interconnection power/ communication cable between indoor and outdoor unit as per site requirement. (If required additionally, payment will made as per actual installtion. The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. Make of Insulation:-Superlon/Aflex/Armacell/Kflex Make of cable:- Finolex/RR/Havells	30	Mtr	
30	Drain Pipe (If Required additional) Applicale to both ACs(Cassette & Split AC). Supply and laying of heavy gauge PVC drain piping of 40mm with insulation as per site requirement with its all accessories like bend, solution etc as per site condition. The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. (If required additionally, payment will made as per actual installtion.) Make:- Kasta/supreme	100	Mtr	
31	Providing & fixing of 4 KVA Voltage stabilizer with time delay option including all accessories with installation at site (For 1Tr /1.5Tr Split AC & 1.5 Tr Cassette AC) Make:-Microtek, V-Gards (Voltage Range 150- 280 Volts)	3	Nos	
32	Providing & fixing of 5 KVA Voltage stabilizer with time delay option including all accessories with installation at site (For 2Tn Split AC & 2 Tn Cassette AC) Make:-Microtek, V-Gards. (Voltage Range 150- 280 Volts)	2	Nos	
	Sub Total : Part B (AIR CONDITIONING WORKS)			

TOTAL WORK (A+B)
GST will be paid as applicable

Vendor's Signature