

STATE BANK OF INDIA
LOCAL HEAD OFFICE, GUWAHATI
PREMISES & ESTATE DEPARTMENT
GUWAHATI, ASSAM.

Supply, Installation, Testing and Commissioning with Comprehensive Annual Maintenance Contract for 5 years of Air-conditioners at Hamren Branch, Karbi Anglong, Assam

PRICE BID

Sl.No.	Description	UOM	Qty.	Rate (Rs.) (Exclusive of GST)	Amount (Rs.) (Exclusive of GST)
A	High Side work: Supply of Machines				
1	Supply of 1.5 TR Capacity Hi Wall mounting 5-star rated having ISEER 4.5 and above Inverter Split AC with cordless remote and double layer Copper Condensor Coil and refrigerant (R32 or R 410A). AC Make, Voltas/Bluestar /Carrier/Daikin /LG/Hitachi (FOR BM CABIN AND CASH OFFICER CABIN)	No.	2		
3	Supply of minimum 2-star rated 2.0 TR Cassette type air conditioners with double layer Copper Condensor Coil and refrigerant (R32 or R 410A) Indoor unit ceiling hung comprising cooling coil, evaporator fan with motor, filters, insulated drain pan, drain pump, expansion valve, refrigerant filter drier with codeless remote control unit, etc. Outdoor unit comprising single phase hermetically sealed scroll / rotary compressors, condenser coil with fan & motor, starters / controls / cutouts / relays etc., mounted inside a powder coated sheet metal cabinet of 2mm thick, duly treated for corrosion protection complete, mounted on ribbed rubber pads. AC Make, Voltas/Blue Star/Carrier/Daikin /LG/Hitachi	No.	5		
TOTAL-A (Excluding GST)					
B	Low Side Work: Installation & Commissioning work				
1	Installation charges of the 1.0/1.5 TR Hi-Wall Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	2		
2	Installation charges of the 2.0 TR Cassette Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	5		
3	For 2.0 TR Copper Cassette type split air conditioners: Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages.	RM	60		
4	For 1.5 TR Hi-Wall type split air conditioners: Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages.	RM	10		
5	Supply and Installation of 4 KVA Stabilizer for 1.0 TR Split Acs	Nos.	2		
6	Supply and Installation of 5 KVA Stabilizer for 2.0 TR Cassette type Acs	Nos.	5		
COMPREHENSIVE AMC					
7	Comprehensive Annual Maintenance Contract of above mentioned 2 No. of 1.0/1.5 TR Hi-Wall type split air conditioners after expiry of defect liability period of 1 year from the date of installation.	year	5		
8	Comprehensive Annual Maintenance Contract of above mentioned 5 Nos. of 2.0 TR Copper Cassette type split air conditioners after expiry of defect liability period of 1 year from the date of installation.	year	5		
TOTAL-B (Excluding GST)					
Total: A+B (Excluding GST)					